

Corrugated Polyethylene Drainage Pipe- M 252

Date last edited: 5/4/2022

Manufacturer	Plant Location	Approved Pipe Sizes	Date Approved	Notes
Advanced Drainage Systems (ADS)	Fairmont, MN	All	1/1/2012	
	Mendota, IL	All	8/8/2013	
	Eagle Grove, IA	All	8/8/2013	
	Findlay, OH	All	8/8/2013	
	London, OH	All	8/8/2013	
	Harrisonville, MO	All	1/4/2018	
	Brazil, IN	4, 6, 8, 10 Inch	5/4/2022	
Haviland Drainage Prodcuts Co.	Haviland, OH	All	1/1/2012	
Lane Enterprises, Inc.	Shippensburg, PA	All	1/27/2021	
	Wytheville, VA	All	1/27/2021	
	Temple, TX	All	1/27/2021	
Prinsco	Chatworth, IL	All	5/24/2012	
	Prinsburg, MN	All	1/4/2018	
	Fresno, CA	All	3/3/2021	
Fratco	Francesville, IN	All	5/13/2016	
Timewell Drainage	Timewell, IL	All	1/1/2012	

All products accepted on the basis of compliance to the National Transportation Product Evaluation Program (NTPEP)

Products must show compliant to both audits and split sample

Production of drainage pipe in a NTPEP fully compliant plant is required .

If the pipe manufacturer plant and size is on the above list and the pipe is stamped "AASHTO M252" and shows no apparent damage , the pipe may be incorporated into the work with a certification of compliance identifying manufacturer, plant , type, size and compliance to AASHTO M 252

Pipe not properly marked AASHTO M 252 shall be rejected

Contact:

DOTProductSubmittal@dot.wi.gov