

**Corrugated Polypropylene Culvert Pipe- M 330**

Date last edited: 8/24/2021

<u>Manufacturer</u>	<u>Plant Location</u>	<u>Approved Pipe Sizes</u>	<u>Date Approved</u>	<u>Notes</u>
Advanced Drainage Systems (ADS)	Fairmont, MN	All	5/19/2016	
	Mendota, IL	All	5/19/2016	
	Findlay, OH	All	5/19/2016	
	Harrisonville, MO	All	1/31/2018	
Lane Enterprises, Inc.	Shippensburg, PA	All	1/27/2021	
	Wytheville, VA	All	1/27/2021	
	Temple, TX	All	1/27/2021	
Prinsco	Chatworth, IL	All	10/4/2017	
	Fresno, CA	All	10/4/2017	
	Prinsburg, MN	All	3/3/2021	
Haviland Drainage Products	Haviland, OH	All	3/16/2020	

All products accepted on the basis of compliance to the National Transportation Product Evaluation Program (NTPEP)  
Products must show compliant to both audits and split sample

Production of pipe in a NTPEP fully compliant plant is required.

If the pipe manufacturer plant and size is on the above list and the pipe is stamped "AASHTO M330" and shows no apparent damage , the pipe may be incorporated into the work with a certification of compliance identifying manufacturer, plant , type, size and compliance to AASHTO M 330

Pipe not properly marked AASHTO M 330 shall be rejected

Contact:

[DOTProductSubmittal@dot.wi.gov](mailto:DOTProductSubmittal@dot.wi.gov)