

**Project ID: 1074-00-31/61**  
**West Salem – Sparta**  
**County C bridge**  
**I-90**  
**La Crosse County**

## **PROJECT INFORMATION**

WisDOT is proposing to rehabilitate the County C bridge over I-90. The need for this project is to address deck delamination on the County C bridge over I-90. The bridge was last treated in 2019 with a concrete deck sealing. In 2021, an infrared survey was conducted that found that approximately 25% of the deck area was delaminated.

**The proposed improvements include the following:**

- Concrete deck overlay
- Guardrail replacement
- Install new drainage system at structures

## **PROPOSED TRAFFIC IMPACTS**

Construction is currently scheduled to begin in Spring 2027 and is expected to be completed in Fall of 2027.

County C will be reduced to a single lane and actuated using temporary traffic signals.

## **REAL ESTATE**

No real estate will be acquired. All work will be completed within existing WisDOT right-of-way.

## **ANTICIPATED SCHEDULE**

Environmental Review Complete:	April 2024
Preliminary Design Complete:	August 2024
PS&E:	August 2026
Let Date:	November 2026
Construction:	April 2027

## **PUBLIC INPUT/COMMENTS**

We encourage you to talk to the project representatives and ask them questions. Your comments assist us in developing a project that will serve the needs of the traveling public as well as the needs of the local community. Your input is welcome and appreciated throughout the design process.

## CONTACTS

**Brian Meyer, P.E.**

WisDOT Project Manager

(608) 789-5676

[Brian.Meyer@dot.wi.gov](mailto:Brian.Meyer@dot.wi.gov)

**WisDOT Southwest Region – La Crosse**

**3550 Mormon Coulee Road**

**La Crosse, WI 54601**

**Dominic Cypher, P.E.**

WisDOT Project Engineer

(608) 785-9044

[Dominic.Cypher@dot.wi.gov](mailto:Dominic.Cypher@dot.wi.gov)

**WisDOT Southwest Region – La Crosse**

**3550 Mormon Coulee Road**

**La Crosse, WI 54601**