



**CAMBER AND SLAB THICKNESS DIAGRAM**

CAMBER SHOWN IS BASED ON 3 TIMES DEAD LOAD DEFLECTION.

CAMBER SPANS AS SHOWN TO PROVIDE FOR DEAD LOAD DEFLECTION AND FUTURE CREEP. CAMBER DOES NOT INCLUDE ALLOWANCE FOR FORM SETTLEMENT.

SELECT ONE

PARAPETS, SIDEWALKS, AND MEDIANS PLACED ON TOP OF THE SLAB SHALL BE POURED AFTER FALSEWORK HAS BEEN RELEASED. (FOR NON-STAGED CONSTRUCTION)

SLAB-SUPPORTING FALSEWORK SHALL REMAIN IN-PLACE UNTIL ALL STAGES OF THE SUPERSTRUCTURE HAS CURED, FOR DEFLECTION CONTROL BETWEEN STAGES. DO NOT RELEASE ANY FALSEWORK UNTIL PARAPETS, SIDEWALKS, AND MEDIANS HAVE CURED. (FOR STAGED CONSTRUCTION)

TO DETERMINE FALSEWORK ELEVATION AT EDGE OF SLAB, CROWN OR REFERENCE LINE FOLLOW THIS PROCEDURE:

- TOP OF SLAB ELEVATION AT FINAL GRADE
  - MINUS..... SLAB THICKNESS
  - PLUS..... CAMBER
  - PLUS..... FORM SETTLEMENT/DEFLECTION DUE TO PLACEMENT OF SLAB CONCRETE (TO BE COMPUTED BY THE CONTRACTOR)
- EQUALS = TOP OF SLAB FALSEWORK ELEVATION

**SURVEY TOP OF SLAB ELEVATIONS**

SHOW FOR EACH SPAN

	€ BRG. SUPPORT NAME	5/10 PT.	€ BRG. SUPPORT NAME
FILL IN GUTTER			
SELECT CROWN AND/OR R			
FILL IN GUTTER			
FILL IN EDGE OF SLAB ☆			

PRIOR TO RELEASING SLAB FALSEWORK, TAKE TOP OF SLAB ELEVATIONS AT THE € OF ABUTMENTS, THE € OF PIERS AND AT 5/10 PTS. TO VERIFY CAMBER. TAKE ELEVATIONS ALONG GUTTER LINES AND CROWN OR R. RECORD THE ELEVATIONS IN THE ABOVE TABLE FOR THE "AS BUILT" PLANS.

**NOTES**

FILL IN THE TABLE OF "SURVEY TOP OF SLAB ELEVATIONS" FOR EACH SPAN ON AS BUILT PLANS.

☆ EDGE OF SLAB ELEVATION IS THE TOP OUTER EDGE OF THE SLAB BENEATH SIDEWALK. (FOR SIDEWALK OR OPEN RAILING APPLICATIONS)

**DESIGNER NOTES**

PROVIDE A "CAMBER AND SLAB THICKNESS DIAGRAM" AND TABLE OF "TOP OF SLAB ELEVATIONS" FOR EACH SPAN ON CONTRACT PLANS.

INCLUDE THE "SURVEY TOP OF SLAB ELEVATIONS" TABLE ON THE CONTRACT PLANS SO THAT IT MAY BE FILLED IN DURING CONSTRUCTION. TO VERIFY CAMBER, SURVEY LOCATIONS SHALL CORRESPOND WITH THE TABLE OF "TOP OF SLAB ELEVATIONS".

FOR BRIDGES WITH R LINE NOT ON THE CROWN, PROVIDE ELEVATIONS AT BOTH LOCATIONS.

**TOP OF SLAB ELEVATIONS**

SHOW FOR EACH SPAN

	€ BRG. SUPPORT NAME	1/10	2/10	3/10	4/10	5/10	6/10	7/10	8/10	9/10	€ BRG. SUPPORT NAME
FILL IN GUTTER											
SELECT CROWN AND/OR R											
FILL IN GUTTER											

FILL IN EDGE OF SLAB ☆ (FOR SIDEWALK OR OPEN RAILING APPLICATIONS)

<b>CONCRETE SLAB DETAILS</b>	
	<b>BUREAU OF STRUCTURES</b>
APPROVED: <i>Laura Shadewald</i>	DATE: 7-23