



Wisconsin Department of Transportation

April 7, 2015

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

Proposal #13: 6995-00-73, WISC 2015 181
City of Beaver Dam, McKinley Street
Prospect Avenue to East Burnett Street
Local Street
Dodge County

Letting of April 14, 2015

This is Addendum No. 1, which provides for the following:

Schedule of Items

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
625.0500	Salvaged Topsoil	SY	0	6760	6760

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
37	Misc. Quantities – Added new quantity table for Salvaged Topsoil

Schedule of Items

Attached, dated April 7, 2015, are the revised Schedule of Items Page 10.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 37.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 1
 ID 6995-00-73
 Revised Sheet 37
 April 7, 2015

TOPSOIL

CATEGORY	STATION	TO STATION	LOCATION	(625.0500) SALVAGED TOPSOIL SY
0010	10+00	16+00	RT & LT	1,493
	16+00	22+00	RT & LT	1,364
	22+00	28+00	RT & LT	1,423
	28+00	34+00	RT & LT	1,763
	34+00	36+50	RT & LT	717
PROJECT TOTAL				6,760

INLET PROTECTION

CATEGORY	STRUCTURE I.D.	STATION	(628.7010) TYPE B EACH	(628.7015) TYPE C EACH	(628.7020) TYPE D EACH
	10+00	16+00	-	7	4
	16+00	22+00	-	12	8
	22+00	28+00	-	-	-
	28+00	34+00	2	6	6
	34+00	36+50	-	-	4
UNDISTRIBUTED			-	20	-
PROJECT TOTALS			2	45	22

SODDING

CATEGORY	STATION	TO STATION	LOCATION	(631.0300) SOD WATER MGAL	(631.1000) SOD LAWN SY
0010	10+00	16+00	RT & LT	6.5	1,091
	16+00	22+00	RT & LT	6.0	994
	22+00	28+00	RT & LT	8.3	1,380
	28+00	34+00	RT & LT	6.7	1,120
	34+00	36+50	RT & LT	3.0	506
UNDISTRIBUTED				3.0	500
PROJECT TOTAL				33.5	5,591

CONSTRUCTION STAKING

CATEGORY	STATION	TO STATION	EACH	LF	(650.4000) STORM SEWER CONCRETE PAVEMENT	(650.4500) SUBGRADE	(650.9820) SLOPE STAKES
0010	10+16	16+00	5	584	584	584	534
	16+00	22+00	14	600	600	600	600
	22+00	28+00	-	600	600	600	600
	28+00	34+00	9	600	600	600	600
	34+00	36+45	4	245	245	245	245
PROJECT TOTAL			32	2629	2629	2629	2629

PERMANENT SIGNING

CATEGORY	STATION	LOCATION	SIZE IN X IN	CODE	POSTS WOOD 4X6-INCH X 14FT	POSTS WOOD 4X6-INCH X 18FT	POSTS WOOD 4X8-INCH X 18FT	REFLECTIVE H	REFLECTIVE F	SF	SF
0010	10+39	27	RT	R12-1	24X30	1	-	-	-	5	-
	10+37	27	LT	R1-1	30X30	1	-	-	-	6	-
	10+94	27	LT	R7-1D	18X24	1	-	-	-	3	-
	11+79	27	RT	R7-51R	18X24	1	-	-	-	3	-
	12+12	27	LT	R7-51L	18X24	1	-	-	-	3	-
	13+08	27	LT	R3-8F	36X30	-	-	-	-	8	-
	13+08	27	LT	R2-1	24X30	-	-	-	-	5	-
	13+08	27	LT	S5-2	24X30	-	-	-	-	5	-
	13+08	27	RT	S1-1	36X36	-	-	-	-	9	-
	13+08	27	RT	W16-9P	24X8	-	-	-	-	1	-
	13+57	44	LT	R2-8P	24X18	-	-	-	-	3	-
	13+95	44	RT	R1-1	30X30	1	-	-	-	6	-
	14+23	27	RT	S4-51	24X48	1	-	-	-	8	-
	15+77	27	RT	R7-51L	18X24	1	-	-	-	3	-
	16+74	60	RT	S4-51	24X48	1	-	-	-	8	-
	16+87	27	LT	R7-52R	18X24	1	-	-	-	3	-
	17+13	28	LT	R3-4	24X24	1	-	-	-	4	-
	17+14	46	RT	R4-7	24X30	1	-	-	-	5	-
	17+50	44	RT	R1-1	30X30	1	-	-	-	6	-
	17+54	30	RT	S1-1	36X36	-	-	-	-	9	-
	17+71	27	RT	WF16-7L	24X12	1	-	-	-	2	-
	17+66	27	LT	S1-1	36X36	1	-	-	-	3	-
	18+23	27	LT	WF16-7L	24X12	1	-	-	-	2	-
	18+41	44	LT	R1-1	30X30	1	-	-	-	3	-
	18+41	27	RT	R7-1D	18X24	1	-	-	-	3	-
	19+05	27	RT	R7-52R	18X24	1	-	-	-	3	-
	19+10	27	LT	R7-51L	18X24	1	-	-	-	3	-
	21+00	27	LT	R7-52L	18X24	1	-	-	-	3	-
	21+13	27	LT	R7-52R	18X24	1	-	-	-	3	-
	21+64	27	RT	R7-1D	18X24	1	-	-	-	3	-
	22+19	27	RT	R7-52R	18X24	1	-	-	-	3	-
	22+15	27	LT	R7-52L	18X24	1	-	-	-	3	-
	24+10	27	LT	R7-51R	18X24	1	-	-	-	3	-
	24+36	27	LT	S4-51	24X48	1	-	-	-	8	-
	24+55	27	RT	R7-52L	18X24	1	-	-	-	3	-
	24+77	44	LT	R1-1	30X30	1	-	-	-	6	-
	25+34	27	RT	R7-52R	18X24	1	-	-	-	3	-
	26+36	27	RT	S5-2	24X30	-	-	-	-	1	-
	26+36	27	RT	R2-1	24X30	-	-	-	-	5	-
	26+36	27	LT	S1-1	36X36	-	-	-	-	1	-
	26+36	27	LT	W16-9P	24X8	-	-	-	-	1	-
	29+11	27	RT	R2-8P	24X18	-	-	-	-	3	-
	29+34	44	LT	R1-1	30X30	1	-	-	-	3	-
	29+90	27	RT	R7-52R	18X24	1	-	-	-	3	-
	32+44	27	RT	R7-52L	18X24	1	-	-	-	3	-
	32+67	44	LT	R1-1	30X30	1	-	-	-	6	-
	33+23	27	RT	R7-52R	18X24	1	-	-	-	3	-
	36+21	27	LT	R12-1	24X30	1	-	-	-	5	-
	36+32	27	RT	R1-1	30X30	1	-	-	-	6	-
PROJECT TOTAL										33	203

PROJECT NO: 6995-00-73 HWY: MCKINLEY STREET COUNTY: DODGE

FILE NAME: P:\2105\218\00218070\cadd\MINPLAN\stis\03-05_M0.dgn

DATE: 01/29/2015

DESIGNER: JANSSEN, TODD M

SHEET 37

WISDOT/CADD SHEET 43

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20150414013

PROJECT(S):
6995-00-73

FEDERAL ID(S):
WISC 2015181

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0970	SPV.0060 Special 02. Water Valve Box Adjustment	11.000 EACH	.		.	
0980	SPV.0060 Special 03. Remove And Replace Hydrant	4.000 EACH	.		.	
0990	SPV.0060 Special 04. Remove And Replace Mainline Valve	1.000 EACH	.		.	
1000	SPV.0060 Special 05. Storm Sewer Pipe Reinforced Concrete Class He-Iii 24x38-Inch X 12-Inch Tee	1.000 EACH	.		.	
1010	SPV.0060 Special 06. Install City Furnished Street Name Sign	8.000 EACH	.		.	
1020	SPV.0105 Special 01. Removing Lighting Conduit & Wire	LUMP		LUMP	.	
1030	625.0500 Salvaged Topsoil	6,760.000 SY	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	