



Wisconsin Department of Transportation

May 26, 2015

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #08: 1009-00-82
Sheboygan Falls – Howards Grove
STH 32 & STH 23 Interchange
STH 32
Sheboygan County

Letting of June 9, 2015

This is Addendum No. 1, which provides for the following:

Special Provisions

Revised Special Provisions	
Article No.	Description
4	Traffic

Schedule of Items

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0300	Drums	DAY	1,140	1,410	1,410
643.0420	Barricades Type III	DAY	60	70	70
643.0705	Warning Lights Type A	DAY	40	80	80
643.0715	Warning Lights Type C	DAY	90	130	130
643.0900	Signs	DAY	345	450	450

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
20	Miscellaneous Quantity Sheet – Revised Traffic Control item quantities to match new reduction in working days.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 1
PROJECT ID 1009-00-82
May 26, 2015

Special Provisions

4. Traffic

Replace entire language with the following:

Keep all STH 32 through lanes and the westbound STH 23 on-ramp open to traffic at all times during construction.

From 6:00 AM, Monday, August 10, 2015 through 6:00 AM, Monday, August 17, 2015 remove all equipment from within the right-of-way; open all lanes to traffic; remove all traffic control devices from within the normal travel lanes and shoulders; remove all traffic control signs and restore normal traffic operations. Reinststate all appropriate traffic control devices on August 17, 2015 prior to commencing work.

Provide the following minimum advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

Lane and shoulder closures*	14 calendar days
Full roadway closures	14 calendar days
System and service ramp closures*	14 calendar days
Full system and service ramp closures	14 calendar days
Project start	14 calendar days
Construction stage changes	14 calendar days
Detours	14 calendar days
Lane and shoulder closures**	3 business days
System and service ramp closures**	3 business days
Modifying all closure types	3 business days

* With height, weight, or width restrictions (available width, all lanes in one direction ≤16')

** Without height, weight, or width restrictions (available width, all lanes in one direction >16')

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.

Notify the engineer if there are any changes in the schedule, early completions, or cancellations for scheduled work.

Schedule of Items

Attached, dated May 26, 2015, are the revised Schedule of Items Page 4.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 20.

END OF ADDENDUM

TRAFFIC CONTROL

LOCATION	DAY	DAY	DAY	DAY	DAY	DAY	NO. OF CYCLES	NO. OF SIGNS	NO. OF SIGNS	DAY
643.0100 TRAFFIC CONTROL PROJECT EACH (1009-00-82)	--	--	--	--	--	--	1	1	1	7
643.0300 DRUMS	300	12	46	0	120	230	0	0	0	7
643.0420 BARRICADES TYPE III	46	46	115	0	27	73	2	1	2	--
643.0705 WARNING LIGHTS TYPE A	0	0	0	0	0	0	0	0	0	--
643.0715 WARNING LIGHTS TYPE C	15	15	15	15	73	73	0	0	0	--
643.0900 SIGNS	120	230	27	73	0	0	0	0	0	--
643.0920 COVERING SIGNS TYPE II	0	0	0	0	0	0	0	0	0	--
643.1050 SIGNS PCMS	0	0	0	0	0	0	0	0	0	--
TOTAL:	1,410	70	80	130	450	2	2	2	2	7

PAVEMENT MARKING

LOCATION	LF	LF
646.0106 PAVEMENT MARKING EPOXY 4-INCH WHITE YELLOW	30	145
Stage 1	30	145
Stage 2	285	--
Stage 3	--	--
SUBTOTAL:	315	145
TOTAL:	460	

CONSTRUCTION STAKING

LOCATION	LF	LF	LS	LF
650.4500 SUBGRADE	170	210	--	160
650.7000 CONCRETE PAVEMENT	230	305	--	260
650.9910 SUPPLEMENTAL CONTROL (1009-00-82)	--	--	1	65
650.9920 SLOPE CONTROL STAKES	--	--	--	--
TOTAL:	400	515	1	485

SAWING

LOCATION	STATION	LF	LF
690.0150 SAWING ASPHALT	18+00, RT	5	--
690.0250 SAWING CONCRETE	142+28, LT	10	--
	18+00 to 19+57, RT	--	160
	17+74, LT	6	--
	18+32 to 19+73	--	140
	142+91 to 143+93, L	--	105
UNDISTRIBUTED		4	10
TOTAL:		25	415

Addendum No. 01
ID 1009-00-82
Revised Sheet 20
May 26, 2015

ALL ITEMS CATEGORY 0010 UNLESS NOTED

PROJECT NO: 1009-00-82

HWY: STH 32

COUNTY: SHEBOYGAN

MISCELLANEOUS QUANTITIES

SHEET NO: 20

E

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20150609008PROJECT(S):
1009-00-82FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	638.2602 Removing Signs Type II	3.000 EACH	.		.	
0340	638.3000 Removing Small Sign Supports	3.000 EACH	.		.	
0350	642.5201 Field Office Type C	1.000 EACH	.		.	
0360	643.0100 Traffic Control (project) 01. 1009-00-82	1.000 EACH	.		.	
0370	643.0300 Traffic Control Drums	1,410.000 DAY	.		.	
0380	643.0420 Traffic Control Barricades Type III	70.000 DAY	.		.	
0390	643.0705 Traffic Control Warning Lights Type A	80.000 DAY	.		.	
0400	643.0715 Traffic Control Warning Lights Type C	130.000 DAY	.		.	
0410	643.0900 Traffic Control Signs	450.000 DAY	.		.	
0420	643.0920 Traffic Control Covering Signs Type II	2.000 EACH	.		.	
0430	643.1050 Traffic Control Signs PCMS	7.000 DAY	.		.	