



Wisconsin Department of Transportation

December 2, 2015

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #06: 5992-08-85, WISC 2015 635
Lower Yahara River Trail Phase One
Capital City Trail to McDaniel Park
Non Highway
Dane County**

Letting of December 8, 2015

This is Addendum No. 01, which provides for the following:

Special Provisions

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
24	Helical Piles

Added Special Provisions	
Article No.	Description
33	Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
113	Structure B-13-837, Guardrail Detail – Modified material notes so that it is consistent with the project Special Provisions.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

5992-08-85

December 2, 2015

Special Provisions

3. Prosecution and Progress

Replace entire article language with the following:

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within 10 calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

A notice to proceed for the contract work will not be issued earlier than March 1, 2016.

Dane County is performing archaeological surveys in Lake Farm County Park between approximately Sta. 78+00 and 84+50. No access will be allowed to the western project limit through Lake Farm County Park until August 1, 2016 when the archaeological surveys are scheduled to be complete.

The contract schedule was developed to extend over both summer and winter months. Dane County has indicated that access to the project site will be granted from the ice on Lake Waubesa during winter months when ice conditions allow it. The contractor will be allowed access to the Lake from the public boat launch on Libby Road year round.

No dredging of the Lake bottom will be allowed without prior written approval of the engineer, Department Natural Resources and Army Corp of Engineers.

Fish Spawning

There shall be no instream disturbance of Lake Waubesa or Upper Mud Lake as a result of construction activity under or for this contract, from March 15 to May 15 both dates inclusive, in order to avoid adverse impacts upon the spawning of fish.

Any change to this limitation will require submitting a written request by the contractor to the engineer, subsequent review and concurrence by the Department of Natural Resources in the request, and final approval by the engineer. The approval will include all conditions to the request as mutually agreed upon by WisDOT and DNR.

Northern Long-eared Bat (*Myotis septentrionalis*)

Northern Long-eared Bats (NLEB) have the potential to inhabit the project limits because they roost in trees and structures (bridges, culverts, buildings). Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the Federal Endangered Species Act.

In order to avoid adverse impacts upon the NLEBs, no vegetation clearing and grubbing within the identified clearing and grubbing limits will be allowed from April 1 to September 30, both dates inclusive.

If the required clearing and removal is not completed by March 31, the department will suspend all clearing and associated work directly impacted by clearing. The department will issue a notice to proceed with clearing and associated work directly impacted by clearing after consulting with the United States Fish and Wildlife Service (USFWS).

Submit a schedule and description of Clearing and/or Grubbing operations with the ECIP 14 days prior to any Clearing operations. The department will determine, based on schedule and scope of work, what additional erosion control measures shall be implemented prior to the start of Clearing operations, and list those additional measures in the ECIP.

Notify the Project Leader 14 days in advance of any work on box culverts or bridges between April 1 and September 30 to allow time for department to complete the Bat Presence Structure Inspection Form.

If bats or evidence of bats are not found during the inspection, construction may proceed.

If bats or evidence of bats are found during the inspection, construction activities affecting the structure's roosting potential must stop until the WisDOT Regional Environmental Coordinator completes consultation with the Wisconsin Department of Natural Resources (WDNR) and/or United States Fish and Wildlife Service (USFWS).

24. Helical Pile, Item SPV.0060.01

Replace entire section titled C.6 Dimension Tolerance with the following:

C.6 Dimension Tolerance

Install Helical Piles to the following tolerances:

1. Centerline of Helical Pile shall not be more than 3-inches from indicated plan location.
2. Helical Pile plumbness shall be within 2° of design alignment.
3. Top elevation of Helical Pile shall be within +1 inch to -1 inch of the design vertical elevation.
4. Deflection in the connection between shaft sections shall be less than 1-inch in 5-feet of length.

33. Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.

Alia Schroeder, License Number All-222369, inspected the existing pedestrian Structure in McDaniel Park for asbestos on October 27, 2015. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: Scott LaCoursiere, OTIE LLC, 5100 Eastpark Blvd, Suite 300, Madison, WI 53718 at (608) 243-6470.

In accordance with NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days prior to beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Scott LaCoursiere, OTIE LLC, 5100 Eastpark Blvd, Suite 300, Madison, WI 53718 at (608) 243-6470 and DOT BTS-ESS Attn: Hazardous Materials Specialist PO Box 7965, Madison, WI. 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Pedestrian Structure over drainage ditch in McDaniel Park
- Site Address: Lat/Long Coordinates: 430350.07 / 893219.05
- Ownership Information: Village of McFarland, 5915 Milwaukee Street McFarland, WI 53558-0110.
- Contact: Scott LaCoursiere
- Phone: (608) 243-6470
- Age: 30 years old. This structure was constructed in approximately 1985.
- Area: 250 SF of deck

Insert the following paragraph in Section 6.g.:

- If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at 608-266-1476 for an emergency response in accordance to standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.
107-125 (20120615)

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 113

END OF ADDENDUM

