



Wisconsin Department of Transportation

January 11, 2016

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

Proposal #22: 4640-05-71, WISC 2016 038
Sheboygan Falls - Sheboygan
Prange Road – Taylor Drive
STH 28
Sheboygan County

Letting of January 12, 2016

This is Addendum No. 03, which provides for the following:

Schedule of Items

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
455.0105	Asphaltic Material PG58-28	TONS	163	27	190
455.0605	Tack Coat	GAL	657	307	964
460.1103	HMA Pavement Type E-3	TONS	2,003	486	2,489
460.4110.S	Reheating HMA Pavement Longitudinal Joints	LF	500	3,094	3,594
465.0125	Asphaltic Surface Temporary	TONS	1,019	-485	534

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
331	Miscellaneous Quantities (Updated quantities)

Schedule of Items

Attached, dated January 7, 2016, are the revised Schedule of Items Pages 4.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 03
ID 4640-05-71
Revised Sheet 331
January 11, 2016

HMA PAVEMENT ITEMS

STATION	LOCATION	455.0105 ASPHALTIC MATERIAL PG58-28	455.0605 TACK COAT	460.1100 HMA PAVEMENT TYPE E-0.3	460.1103 HMA PAVEMENT TYPE E-3	460.4110.S REHEATING HMA PAVEMENT LONGITUDINAL JOINTS	465.0105 ASPHALTIC SURFACE	465.0125 ASPHALTIC SURFACE TEMPORARY	465.0315 ASPHALTIC FLUMES
		TONS	GAL	TONS	TONS	LF	TON	TON	SY
244+94 -	258+77	13	-	241	-	-	-	-	-
245+77 -	258+63	13	-	230	-	-	-	-	-
268+39 -	270+64	2	-	39	-	-	-	-	-
270+64 -	276+58	21	176	104	282	2226	-	-	-
272+14 -	276+58	4	-	77	-	-	-	-	-
276+58 -	280+00	9	73	44	117	1368	-	-	-
276WB+58 -	280WB+00	8	58	60	93	-	-	-	-
237SW+71 -	243SW+16	19	106	-	339	-	-	-	-
243SW+16 -	244SW+92	1	-	25	-	-	-	-	-
245NW+54 -	249NW+43	3	-	61	-	-	-	-	-
249NW+43 -	252NW+00	13	74	-	237	-	-	-	-
237SE+16 -	242SE+25	34	191	-	612	-	-	-	13
242SE+25 -	245SE+08	2	-	36	-	-	-	-	-
245NE+95 -	249NE+36	3	-	47	-	-	-	-	11
249NE+36 -	253NE+62	18	101	-	323	-	-	-	-
0P+00 -	3P+36	-	-	-	-	-	230	-	-
280EB+00 -	310EB+00	-	73	-	-	-	-	409	-
280EB+00 -	310EB+00	-	22	-	-	-	-	125	-
247A+31 -	249A+23	8	25	-	140	-	-	-	-
247A+31 -	248A+41	3	10	-	54	-	-	-	-
281EB+04 -	281EB+49	2	6	-	27	-	-	-	-
244A+07 -	245A+26	5	17	-	95	-	-	-	-
280EB+59 -	281EB+04	1	6	-	26	-	-	-	-
244A+07 -	245A+26	8	26	-	144	-	-	-	-
TOTAL		190	964	964	2,489	3,594	230	534	24

UNLESS OTHERWISE NOTED
ALL ITEMS IN CATEGORY 0010
SHEET NO: 331 E
WISDOT/CADDS SHEET 42

MISCELLANEOUS QUANTITIES

COUNTY: SHEBOYGAN

HWY: STH 28

PROJECT NO: 4640-05-71

FILE NAME : ...03201.mqprt PLOT DATE : 1/26/16 8:10 AM PLOT BY : PLOT NAME : 03201.mq PLOT SCALE : 1:00000:1.00000

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160112022PROJECT(S):
4640-05-71FEDERAL ID(S):
WISC 2016038

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0350	416.1010 Concrete Surface Drains	1.330 CY
0360	440.4410 Incentive IRI Ride	6,000.000 DOL	1.00000	.	6000.00	.
0370	455.0105 Asphaltic Material PG58-28	190.000 TON
0380	455.0605 Tack Coat	964.000 GAL
0390	460.1100 HMA Pavement Type E-0.3	964.000 TON
0400	460.1103 HMA Pavement Type E-3	2,489.000 TON
0410	460.2000 Incentive Density HMA Pavement	1,933.000 DOL	1.00000	.	1933.00	.
0420	460.4110.S Reheating HMA Pavement Longitudinal Joints	3,594.000 LF
0430	465.0105 Asphaltic Surface	230.000 TON
0440	465.0125 Asphaltic Surface Temporary	534.000 TON
0450	465.0315 Asphaltic Flumes	24.000 SY