



Wisconsin Department of Transportation

March 2, 2016

Division of Transportation Systems Development

Bureau of Project Development
 4802 Sheboygan Avenue, Rm 601
 P O Box 7916
 Madison, WI 53707-7916

Telephone: (608) 266-1631
 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #29: 7824-00-09, WISC 2016 071
C Altoona, CTH AA
House Road – USH 12
CTH AA
Eau Claire County

7824-00-13, WISC 2016 072
C Eau Claire, CTH AA
Otter Creek Bridge B-18-0229
CTH AA
Eau Claire County

Letting of March 8, 2016

This is Addendum No. 01, which provides for the following:

Schedule of Items

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
611.0606	Inlet Covers Type B	Each	1	1	2

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
455.0110	Asphaltic Material PG58-34	TON	0	618	618
611.1004	Catch Basins 4-FT Diameter	Each	0	1	1

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
455.0105	Asphaltic Material PG58-28	TON	618	-618	0
611.0642	Inlet Covers Type MS	Each	1	-1	0
611.3901	Inlets Median 1 Grate	Each	1	-1	0

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
43	Revised to PG58-34
46	Removed Median 1 Grate and MS Cover and added Catch Basin and Type B Cover
76	Revised structure type information and elevations

Other

Revise the contract time for completion from 50 working days to 65 working days (an increase in 15 working days).

Schedule of Items

Attached, dated March 2, 2016, are the revised Schedule of Items Pages 1 – 13.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 43, 46, and 76.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

ASPHALTIC ITEMS & MAILBOXES

455.0110 ASPHALTIC MATERIAL PG58-34

Addendum No. 01
ID 7824-00-09
ID 7824-00-13
Revised Sheet 43
March 2, 2016

PROJECT ID	STATION - STATION	LOCATION	455.0110 ASPHALTIC MATERIAL PG58-34 TON	455.0605 TACK COAT GAL	460.1100 HMA PAVEMENT TYPE E-0.3 TON	465.0120 ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES TON	465.0315 ASPHALTIC FLUMES SY	SPV.0060.03 MOVING MAILBOXES EACH
CATEGORY CODE 0010								
7824-00-09								
	104+00 - 186+93	LOWER LIFT	290	1,400	4,900	--	--	--
	104+00 - 186+94	UPPER LIFT	240	--	3,900	--	--	--
	MAYER RD	BOTH LIFTS	9	23	160	--	--	--
	FRILL RD	BOTH LIFTS	9	23	150	--	--	--
	PLEASANT VIEW RD	BOTH LIFTS	10	26	170	--	--	--
	109+75 - 185+75	DRIVEWAYS	--	--	190	--	--	22
	137+40	LT	--	--	--	11	--	--
	137+50	RT	--	--	--	11	--	--
	9+40'S	RT	--	--	--	11	--	--
	138+80	RT	--	--	--	11	--	--
	10+30'P	LT	--	--	--	11	--	--
	10+30'P	RT	--	--	--	5	--	--
PROJECT TOTAL			559	1,472	9,280	190	60	22
CATEGORY CODE 0010								
7824-00-13								
	95+00 - 99+40	MAINLINE (INCLUDES HOUSE RD)	36	91	590	--	--	--
	100+04 - 104+00	MAINLINE	23	61	400	--	--	--
	9+42'HR	DRIVEWAY RT	--	--	3	--	--	1
	99+09	LT	--	--	--	11	--	--
PROJECT TOTAL			59	152	990	3	11	1

STORM SEWER ITEMS

STORM SEWER PIPE REINF. CONC.

608.0418

CLASS IV

18-INCH

LF

611.0606

INLET COVERS

TYPE B

EACH

611.0615

INLET COVERS

TYPE F

EACH

611.1004

4-FT DIAMETER

EACH

611.1005

4-FT DIAMETER

EACH

611.3004

INLETS

EACH

628.7005

INLET PROTECTION

TYPE A

EACH

628.7020

INLET PROTECTION

TYPED

EACH

650.4000

CONSTRUCTION

STAKING

EACH

PROJECT ID STRUCTURE STATION LOCATION

CATEGORY CODE 0010

7824-00-08

2.0 184+50 40' RT

3.0 186+04 32' RT

PROJECT TOTAL

CATEGORY CODE 0010

7824-00-13

1.1 9+27 34' LT

1.2 9+11 41' LT

1.3 9+46 18' RT

PROJECT TOTAL

57

2

1

2

3

3

Addendum No. 01
ID 7824-00-09
ID 7824-00-13
Revised Sheet 46
March 2, 2016

PROJECT NO: 7824-00-09/13

HWY: CTH AA

COUNTY: EAU CLAIRE

MISCELLANEOUS QUANTITIES

SHEET NO: 46

E

FILE NAME : N:\pdsdesign_id

PLOT DATE :

PLOT BY :

PLOT NAME :

ORIG DATE : Dec. 2003

ORIGINATOR : DIST 4

PLOT SCALE : 1:1

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 Roadway Items

0010	201.0105 Clearing	6.000 STA
0020	201.0205 Grubbing	70.000 STA
0030	203.0100 Removing Small Pipe Culverts	16.000 EACH
0040	203.0600.S Removing Old Structure Over Waterway With Minimal Debris (station) 01. 99+70	LUMP	LUMP	.	.	.
0050	204.0155 Removing Concrete Sidewalk	104.000 SY
0060	204.0165 Removing Guardrail	310.000 LF
0070	204.0170 Removing Fence	347.000 LF
0080	204.0220 Removing Inlets	3.000 EACH
0090	204.0245 Removing Storm Sewer (size) 01. 12-INCH	20.000 LF

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	204.0245 Removing Storm Sewer (size) 02. 18-INCH	23.000 LF	.		.	
0110	204.0245 Removing Storm Sewer (size) 03. 19X30-INCH	42.000 LF	.		.	
0120	204.9060.S Removing (item description) 01. APRON ENDWALL	1.000 EACH	.		.	
0130	204.9180.S Removing (item description) 01. RIPRAP	110.000 SY	.		.	
0140	205.0100 Excavation Common	35,345.000 CY	.		.	
0150	206.1000 Excavation for Structures Bridges (structure) 01. B-18-0229	LUMP	LUMP		.	
0160	208.0100 Borrow	8,286.000 CY	.		.	
0170	210.0100 Backfill Structure	900.000 CY	.		.	
0180	213.0100 Finishing Roadway (project) 01. 7824-00-09	1.000 EACH	.		.	
0190	213.0100 Finishing Roadway (project) 02. 7824-00-13	1.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	305.0110 Base Aggregate Dense 3/4-Inch	958.000 TON	.		.	
0210	305.0120 Base Aggregate Dense 1 1/4-Inch	27,337.000 TON	.		.	
0220	416.0160 Concrete Driveway 6-Inch	104.000 SY	.		.	
0230	440.4410 Incentive IRI Ride	6,890.000 DOL	1.00000		6890.00	
0250	455.0605 Tack Coat	1,624.000 GAL	.		.	
0260	460.1100 HMA Pavement Type E-0.3	10,270.000 TON	.		.	
0270	460.2000 Incentive Density HMA Pavement	6,660.000 DOL	1.00000		6660.00	
0280	465.0120 Asphaltic Surface Driveways and Field Entrances	193.000 TON	.		.	
0290	465.0315 Asphaltic Flumes	71.000 SY	.		.	
0300	502.0100 Concrete Masonry Bridges	368.000 CY	.		.	
0310	502.3200 Protective Surface Treatment	327.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	502.3210 Pigmented Surface Sealer	61.000 SY	.		.	
0330	503.0137 Prestressed Girder Type I 36W-Inch	288.000 LF	.		.	
0340	505.0400 Bar Steel Reinforcement HS Structures	13,940.000 LB	.		.	
0350	505.0600 Bar Steel Reinforcement HS Coated Structures	37,120.000 LB	.		.	
0360	506.2605 Bearing Pads Elastomeric Non-Laminated 01. B-18-0229	8.000 EACH	.		.	
0370	506.4000 Steel Diaphragms (structure) 01. B-18-0229	6.000 EACH	.		.	
0380	516.0500 Rubberized Membrane Waterproofing	36.000 SY	.		.	
0390	520.1012 Apron Endwalls for Culvert Pipe 12-Inch	45.000 EACH	.		.	
0400	520.3412 Culvert Pipe Class III-A Non-metal 12-Inch	828.000 LF	.		.	
0410	520.3415 Culvert Pipe Class III-A Non-metal 15-Inch	46.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	520.3418 Culvert Pipe Class III-A Non-metal 18-Inch	80.000 LF	.		.	
0430	521.1515 Apron Endwalls for Culvert Pipe Sloped Side Drains Steel 15-Inch 6 to 1	4.000 EACH	.		.	
0440	521.1518 Apron Endwalls for Culvert Pipe Sloped Side Drains Steel 18-Inch 6 to 1	6.000 EACH	.		.	
0450	522.0124 Culvert Pipe Reinforced Concrete Class III 24-Inch	219.000 LF	.		.	
0460	522.0130 Culvert Pipe Reinforced Concrete Class III 30-Inch	193.000 LF	.		.	
0470	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	6.000 EACH	.		.	
0480	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	8.000 EACH	.		.	
0490	523.0119 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 19x30-Inch	63.000 LF	.		.	
0500	523.0124 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 24x38-Inch	67.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0510	523.0138 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 38x60-Inch	64.000 LF	.		.	
0520	523.0519 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 19x30-Inch	1.000 EACH	.		.	
0530	523.0524 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 24x38-Inch	1.000 EACH	.		.	
0540	523.0538 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 38x60-Inch	2.000 EACH	.		.	
0550	550.2104 Piling CIP Concrete 10 3/4 X 0. 25-Inch	1,840.000 LF	.		.	
0560	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	816.000 LF	.		.	
0570	606.0200 Riprap Medium	49.000 CY	.		.	
0580	606.0300 Riprap Heavy	525.000 CY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0590	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	57.000 LF	.		.	
0600	611.0420 Reconstructing Manholes	1.000 EACH	.		.	
0610	611.0606 Inlet Covers Type B	2.000 EACH	.		.	
0620	611.0615 Inlet Covers Type F	3.000 EACH	.		.	
0640	611.1005 Catch Basins 5-FT Diameter	1.000 EACH	.		.	
0650	611.3004 Inlets 4-FT Diameter	3.000 EACH	.		.	
0670	612.0406 Pipe Underdrain Wrapped 6-Inch	260.000 LF	.		.	
0680	614.0150 Anchor Assemblies for Steel Plate Beam Guard	4.000 EACH	.		.	
0690	614.2300 MGS Guardrail 3	50.000 LF	.		.	
0700	614.2500 MGS Thrie Beam Transition	158.000 LF	.		.	
0710	614.2610 MGS Guardrail Terminal EAT	4.000 EACH	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0720	616.0204 Fence Chain Link 4-FT	134.000 LF	.		.	
0730	619.1000 Mobilization	1.000 EACH	.		.	
0740	621.0100 Landmark Reference Monuments	2.000 EACH	.		.	
0750	624.0100 Water	279.100 MGAL	.		.	
0760	625.0500 Salvaged Topsoil	64,460.000 SY	.		.	
0770	627.0200 Mulching	64,460.000 SY	.		.	
0780	628.1504 Silt Fence	6,745.000 LF	.		.	
0790	628.1520 Silt Fence Maintenance	6,745.000 LF	.		.	
0800	628.1905 Mobilizations Erosion Control	11.000 EACH	.		.	
0810	628.1910 Mobilizations Emergency Erosion Control	6.000 EACH	.		.	
0820	628.2004 Erosion Mat Class I Type B	17,620.000 SY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029

PROJECT(S):
7824-00-09
7824-00-13

FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0830	628.2006 Erosion Mat Urban Class I Type A	5,380.000 SY	.		.	
0840	628.2023 Erosion Mat Class II Type B	200.000 SY	.		.	
0850	628.2037 Erosion Mat Class III Type C	588.000 SY	.		.	
0860	628.7005 Inlet Protection Type A	1.000 EACH	.		.	
0870	628.7020 Inlet Protection Type D	4.000 EACH	.		.	
0880	628.7504 Temporary Ditch Checks	1,344.000 LF	.		.	
0890	628.7555 Culvert Pipe Checks	47.000 EACH	.		.	
0900	628.7560 Tracking Pads	2.000 EACH	.		.	
0910	629.0210 Fertilizer Type B	39.000 CWT	.		.	
0920	630.0120 Seeding Mixture No. 20	1,686.000 LB	.		.	
0930	630.0140 Seeding Mixture No. 40	365.000 LB	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029

PROJECT(S):
7824-00-09
7824-00-13

FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0940	630.0200 Seeding Temporary	859.400 LB	.		.	
0950	633.5200 Markers Culvert End	13.000 EACH	.		.	
0960	634.0614 Posts Wood 4x6-Inch X 14-FT	26.000 EACH	.		.	
0970	634.0616 Posts Wood 4x6-Inch X 16-FT	14.000 EACH	.		.	
0980	637.2230 Signs Type II Reflective F	200.400 SF	.		.	
0990	638.2102 Moving Signs Type II	7.000 EACH	.		.	
1000	638.2602 Removing Signs Type II	46.000 EACH	.		.	
1010	638.3000 Removing Small Sign Supports	34.000 EACH	.		.	
1020	642.5001 Field Office Type B	1.000 EACH	.		.	
1030	643.0200 Traffic Control Surveillance and Maintenance (project) 01. 7824-00-09	90.000 DAY	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1040	643.0300 Traffic Control Drums	2,250.000 DAY	.		.	
1050	643.0420 Traffic Control Barricades Type III	2,250.000 DAY	.		.	
1060	643.0705 Traffic Control Warning Lights Type A	4,050.000 DAY	.		.	
1070	643.0900 Traffic Control Signs	3,060.000 DAY	.		.	
1080	643.0920 Traffic Control Covering Signs Type II	6.000 EACH	.		.	
1090	643.1000 Traffic Control Signs Fixed Message	144.000 SF	.		.	
1100	643.2000 Traffic Control Detour (project) 01. 7824-00-09	1.000 EACH	.		.	
1110	643.3000 Traffic Control Detour Signs	8,100.000 DAY	.		.	
1120	645.0120 Geotextile Fabric Type HR	1,024.000 SY	.		.	
1130	646.0106 Pavement Marking Epoxy 4-Inch	34,810.000 LF	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1140	647.0566 Pavement Marking Stop Line Epoxy 18-Inch	134.000 LF	.		.	
1150	648.0100 Locating No-Passing Zones	1.800 MI	.		.	
1160	650.4000 Construction Staking Storm Sewer	5.000 EACH	.		.	
1170	650.4500 Construction Staking Subgrade	9,772.000 LF	.		.	
1180	650.5000 Construction Staking Base	9,772.000 LF	.		.	
1190	650.5500 Construction Staking Curb Gutter and Curb & Gutter	816.000 LF	.		.	
1200	650.6000 Construction Staking Pipe Culverts	36.000 EACH	.		.	
1210	650.6500 Construction Staking Structure Layout (structure) 01. B-18-0229	LUMP	LUMP		.	
1220	650.9910 Construction Staking Supplemental Control (project) 01. 7824-00-09	LUMP	LUMP		.	
1230	650.9910 Construction Staking Supplemental Control (project) 02. 7824-00-13	LUMP	LUMP		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160308029PROJECT(S):
7824-00-09
7824-00-13FEDERAL ID(S):
WISC 2016071
WISC 2016072

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1240	650.9920 Construction Staking Slope Stakes	9,772.000 LF	.		.	
1250	690.0150 Sawing Asphalt	302.000 LF	.		.	
1260	690.0250 Sawing Concrete	40.000 LF	.		.	
1270	715.0502 Incentive Strength Concrete Structures	2,208.000 DOL	1.00000		2208.00	
1280	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,400.000 HRS	5.00000		12000.00	
1290	ASP.1T0G On-the-Job Training Graduate at \$5. 00/HR	600.000 HRS	5.00000		3000.00	
1300	SPV.0060 Special 01. ADJUSTING MANHOLE COVERS	4.000 EACH	.		.	
1310	SPV.0060 Special 02. ADJUSTING WATER VALVES	6.000 EACH	.		.	
1320	SPV.0060 Special 03. Moving Mailbox	23.000 EACH	.		.	
1330	455.0110 Asphaltic Material PG58-34	618.000 TON	.		.	
1340	611.1004 Catch Basins 4-FT Diameter	1.000 EACH	.		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	