



Wisconsin Department of Transportation

April 21, 2016

Division of Transportation Systems Development

Bureau of Project Development
 4802 Sheboygan Avenue, Rm 601
 P O Box 7916
 Madison, WI 53707-7916

Telephone: (608) 266-1631
 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #03: 3934-00-74
STH 67 – STH 83
Ashippun River Bridge B-14-0214
CTH O
Dodge County

Letting of May 10, 2016

This is Addendum No. 01, which provides for the following:

Special Provisions

Added Special Provisions	
Article No.	Description
16	Seismograph Special, Item SPV.0045.01
17	Crack and Damage Survey, Item 999.1500.S

Schedule of Items

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
630.0120	Seeding Mixture No. 20	LB	28	-12	16

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
630.0140	Seeding Mixture No. 40	LB	0	10	10
999.1500.S	Crack and Damage Survey	LS	0	1	1
SPV.0045.01	Seismograph Special	Day	0	3	3

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
7	Miscellaneous Quantities – Added bid item and revised bid item

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

3934-00-74

April 21, 2016

Special Provisions

16. Seismograph Special, Item SPV.0045.01.

A Description

Furnish a seismograph and employ trained operators to monitor vibration while vibration producing construction is occurring nearby.

B Materials

Use seismographs that are in accordance to SPS 307.43, and are continuous data recorders supplied with all the accessories necessary for making seismograph observations.

C Construction

Monitoring procedures shall be in accordance to SPS 307.43, and the following: Take seismograph readings prior to construction activities to establish an ambient index.

Place the seismograph to continuously monitor all vibration producing construction activities or as direct by the engineer. Vibration producing construction activities may include compaction, excavation, backfilling and trucking as well as other activities.

If construction activities generate ground vibration in excess of the Peak Particle Velocity Limits as shown in SPS 307.43, stop the construction operations in progress and consider and implement alternate construction methods. Monitoring may be reduced at the discretion of the engineer if Peak Particle Velocity Limits are continuously less than those shown in SPS 307.43. Construction occurring in multiple areas will require multiple seismographs.

D Measurement

The department will measure Seismograph Special by the day of completed work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0045.01	Seismograph Special	Day

Payment is full compensation for furnishing and operating a seismograph, an operator, and accessories.

17. Crack and Damage Survey, Item 999.1500.S.

A Description

This special provision describes conducting a crack and damage survey of the residences and business located at:

W1041 County Road O, Oconomowoc, WI 53066
W1046 County Road O, Oconomowoc, WI 53066

This Crack and Damage Survey shall consist of two parts. The first part, performed prior to construction activities, shall include a visual inspection, photographs, and a written report describing the existing defects in the building(s) being inspected. The second part, performed after the

construction activities, shall also include a visual inspection, photographs, and written report describing any change in the building's condition.

B (Vacant)

C Construction

Prior to any construction activities, thoroughly inspect the building structures for existing defects, including interior and exterior walls. Submit a written report of the inspector's name, date of inspection, descriptions and locations of defects, and photographs. The intent of the written report and photographs is to procure a record of the general physical condition of the building's interior and exterior walls and foundation. The report shall be typed on bond paper and be in text form.

The photographs shall be taken by a professional photographer capable of producing sharp, grain free, high-contrast colored pictures with good shadow details. The photographs shall be 3½ inch by 5 inch color prints, glossy, and mounted in protective storage pages with clear slip-in pockets and clear background. Each sheet shall hold four prints. The back of each photograph shall contain the following information:

ID _____
Building Location _____
View looking _____
Date _____
Photographer _____

Prior to the start of any construction activities pertinent to this survey, submit a copy of the written report and photographs to the engineer.

After the construction activities are complete, conduct another survey in the same manner, take photographs, and submit another written report to the engineer.

In lieu of photographs, a professional videographer may be hired to use a video camera capable of producing a video with the clarity required to perform this work.

D Measurement

The department will measure Crack and Damage Survey as single complete unit of work.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
999.1500.S	Crack and Damage Survey	LS

Payment is full compensation for providing the before and after written reports, and for photographs or video.

999-010 (20130615)

Schedule of Items

Attached, dated April 21, 2016, are the revised Schedule of Items Pages 4 and 6.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 7.

END OF ADDENDUM

EROSION CONTROL ITEMS

STA	TO	STA	LOCATION	SY	LF	628.1504	628.1520	628.2008	629.0210	630.0120	630.0140	630.0200	630.0300
8+09	9+78	RT	155	180	180	260	0.3						
8+09	9+78	LT	105	180	180	200	0.2						
10+22	11+86	RT	215	180	180	315	0.4						
10+22	11+86	LT	110	180	180	205	0.3						
UNDISTRIBUTED			60	70	70	100	0.1						
TOTALS			645	790	790	1,080	1.3						

EROSION CONTROL MOBILIZATION ITEMS

LOCATION	EACH	628.1905	628.1910
EROSION CONTROL	2	EROSION CONTROL	EROSION CONTROL
EROSION CONTROL	2	EROSION CONTROL	EROSION CONTROL
TOTALS	2	2	2

* PAY PLAN QUANTITY

LOCATION	SY	LF	628.7504
NORTH ABUT	70	12.5	
SOUTH ABUT	65	12.5	
UNDISTRIBUTED	15	12.5	
TOTAL	150	50	

TURBIDITY BARRIERS

LOCATION	SY	LF	628.6005
NORTH ABUT	70	12.5	
SOUTH ABUT	65	12.5	
UNDISTRIBUTED	15	12.5	
TOTAL	150	50	

TEMPORARY DITCH CHECKS

LOCATION	OFFSET	LF	628.0612
NORTH ABUT	LT	12.5	
NORTH ABUT	RT	12.5	
SOUTH ABUT	LT	12.5	
SOUTH ABUT	RT	12.5	
TOTAL		50	

OBJECT MARKERS

POSTS WOOD	4X6-INCH X 12-FT	REFLECTIVE F	SF	637.2230
1	3	3	3	W5-52L
1	3	3	3	W5-52R
1	3	3	3	W5-52L
TOTALS	4	12	12	

FIELD OFFICE TYPE B

CATEGORY	EACH	642.5001
0010	0.3	
0020	0.7	
TOTAL	1	

TRAFFIC CONTROL (ID 3934-00-74)

PROJECT	LOCATION	LF	643.0100.01
6208-00-75	8+09 - 11+86	335	
TOTAL		335	

STAKING ITEMS

CONSTRUCTION	CONSTRUCTION	CONSTRUCTION	CONSTRUCTION	CONSTRUCTION	CONSTRUCTION
BASE	STAKING	CONSTRUCTION	CONSTRUCTION	CONSTRUCTION	CONSTRUCTION
650.5000	650.5000	650.5000.01	650.9910.01	650.9920	650.9920
335	335	335	335	335	335
TOTALS	335	335	1	1	335

CRACK & DAMAGE SURVEY

PROPERTY	LS	999.1500.5
W1041 COUNTY ROAD O & W1046 COUNTY ROAD O	1	
TOTAL	1	

SEISMOGRAPH SPECIAL

PROJECT	DAY	SPV.0045.01
3934-00-74	3	
TOTAL	3	

DRY HYDRANT

CATEGORY	LS	SPV.0105.01
0030	1	
TOTAL	1	

SAWING ASPHALT

STATION	LOCATION	LF	690.0150
8+09 - 8+75	LT & RT	160	
11+25 - 11+86	LT & RT	150	
TOTAL		310	

MISCELLANEOUS QUANTITIES

CATEGORY	QUANTITY	650.0030
0030	1	
TOTAL	1	

ALL QUANTITIES CATEGORY 0010 UNLESS OTHERWISE NOTED

CATEGORY	QUANTITY	650.0030
0010	1	
TOTALS	1	

PROJECT NO: 3934-00-74

HWY:	CTH O	COUNTY:	DODGE

PROJECT NO: 3934-00-74

PROJECT NO:	3934-00-74

SHEET NO: 7

SHEET NO:	7

EROSION CONTROL MOBILIZATION ITEMS

LOCATION	EACH	628.1905	628.1910
EROSION CONTROL	2	EROSION CONTROL	EROSION CONTROL
EROSION CONTROL	2	EROSION CONTROL	EROSION CONTROL
TOTALS	2	2	2

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160510003PROJECT(S):
3934-00-74FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	628.1504 Silt Fence	790.000				
		LF	.		.	
0330	628.1520 Silt Fence Maintenance	790.000				
		LF	.		.	
0340	628.1905 Mobilizations Erosion Control	2.000				
		EACH	.		.	
0350	628.1910 Mobilizations Emergency Erosion Control	2.000				
		EACH	.		.	
0360	628.2008 Erosion Mat Urban Class I Type B	1,080.000				
		SY	.		.	
0370	628.6005 Turbidity Barriers	150.000				
		SY	.		.	
0380	628.7504 Temporary Ditch Checks	50.000				
		LF	.		.	
0390	629.0210 Fertilizer Type B **p**	1.300				
		CWT	.		.	
0400	630.0120 Seeding Mixture No. 20 **p**	16.000				
		LB	.		.	
0410	630.0200 Seeding Temporary **p**	28.000				
		LB	.		.	
0420	630.0300 Seeding Borrow Pit	10.000				
		LB	.		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20160510003

PROJECT(S):
3934-00-74

FEDERAL ID(S):
N/A

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	650.9910 Construction Staking Supplemental Control (project) 01. 3934-00-74	LUMP	LUMP			.
0540	650.9920 Construction Staking Slope Stakes	LF 335.000	.			.
0550	690.0150 Sawing Asphalt	LF 310.000	.			.
0560	715.0502 Incentive Strength Concrete Structures	DOL 1,200.000	1.00000			1200.00
0570	SPV.0105 Special 01. DRY HYDRANT	LUMP	LUMP			.
0580	630.0140 Seeding Mixture No. 40 **p**	LB 10.000	.			.
0590	999.1500.S Crack and Damage Survey	LUMP	LUMP			.
0600	SPV.0045 Special 01. Seismograph Special	DAY 3.000	.			.
	SECTION 0001 TOTAL					.
	TOTAL BID					.