



# Wisconsin Department of Transportation

---

June 30, 2016

**Division of Transportation Systems Development**

Bureau of Project Development  
 4802 Sheboygan Avenue, Rm 601  
 P O Box 7916  
 Madison, WI 53707-7916

Telephone: (608) 266-1631  
 Facsimile (FAX): (608) 266-8459

**NOTICE TO ALL CONTRACTORS:**

**Proposal #07: 1706-00-73**  
**Janesville-Darien**  
**STH 140 Intersection**  
**USH 14 / STH 11**  
**Rock County**

**3320-00-75**  
**Bergen – Emerald Grove**  
**Bradford / Clinton Rd – Avalon Rd**  
**STH 140**  
**Rock County**

**Letting of July 12, 2016**

This is Addendum No. 01, which provides for the following:

**Special Provisions**

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

**Schedule of Items**

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
646.0106	Pavement Marking Epoxy 4-Inch	LF	92,882	-35,877	57,005
649.0400	Temporary Pavement Marking Removable Tape 4-Inch	LF	12,208	2,198	14,406

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
646.0406	Pavement Marking Same Day (Epoxy)	LF	0	35,877	35,877

## Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
63	Miscellaneous Quantities revise pavement marking epoxy and pavement marking same day quantities
65	Miscellaneous Quantities revise temporary pavement marking quantities

## Special Provisions

### 3. Prosecution and Progress

*Add the following:*

To prevent a 2-inch drop at the centerline of the road, centerline milling and asphaltic surface replacement shall be completed in any area in the same day. Temporary Pavement Marking Removable Tape (4-inch) for project 3320-00-75 is to be installed along the centerline of STH 140 on the same day that the 2-foot wide centerline pavement is constructed. The intent of the Same Day Pavement Marking (Epoxy) bid item is for the permanent centerline pavement markings to be installed after, and on the same day, the STH 140 centerline rumble strips are installed.

### Schedule of Items

Attached, dated June 30, 2016, are the revised Schedule of Items Pages 8 - 10.

### Plan Sheets

The following 8 ½ x 11-inch sheets are attached and made part of the plans for the proposal:  
Revised 63 and 65

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

STATION	STATION	ITEM NO. 646.0106 PAVEMENT MARKING EPOXY 4-INCH WHITE		ITEM NO. 646.0406 PAVEMENT MARKING SAME DAY (EPOXY) 4-INCH YELLOW *		ITEM NO. 646.0126 PAVEMENT MARKING EPOXY 8-INCH		ITEM NO. 647.011 PAVEMENT MARKING RAILROAD CROSSING EPOXY		ITEM NO. 647.0566 PAVEMENT MARKING STOP LINE EPOXY 18-INCH		ITEM NO. 647.0746 PAVEMENT MARKING DIAGONAL EPOXY 24-INCH		REMARKS	
		LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF			
PROJECT LENGTH LEFT	28200	--	--	--	--	--	--	--	--	--	--	--	--	--	
PROJECT LENGTH RIGHT	28150	--	--	--	--	--	--	--	--	--	--	--	--	LT SOLID, RT SKIP	
30+96	40+71	94	372	1038	11178	1052	534	863	45	815	547	1080	976	1047	LT SKIP
40+71	55+59	--	--	--	--	--	--	--	--	--	--	--	--	--	LT & RT SOLID
55+59	63+89	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SOLID, RT SKIP
63+89	119+78	--	--	--	--	--	--	--	--	--	--	--	--	--	RT SKIP
119+78	128+18	94	372	1038	11178	1052	534	863	45	815	547	1080	976	1047	LT & RT SOLID
128+18	149+52	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SOLID, RT SKIP
149+52	156+42	--	--	--	--	--	--	--	--	--	--	--	--	--	RT SKIP
156+42	158+22	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SKIP, RT SOLID
158+22	164+74	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SKIP
164+74	186+59	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SOLID, RT SKIP
186+59	195+22	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SKIP
195+22	200+10	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SKIP, RT SOLID
200+10	208+47	--	--	--	--	--	--	--	--	--	--	--	--	--	LT & RT SOLID
208+47	209+66	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SOLID, RT SKIP
209+66	218+02	30	1045	2647	1057	189	1047	57	782	1232	35877	0	2	0	LT SKIP
218+02	231+26	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SKIP, RT SOLID
231+26	239+71	--	--	--	--	--	--	--	--	--	--	--	--	--	LT & RT SOLID
239+71	247+26	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SOLID, RT SKIP
247+26	255+62	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SKIP, RT SOLID
255+62	271+29	3134	2098	2136	782	57	307+25	315+36	321+65	56350	1096	1096	1096	35	205
271+29	288+07	--	--	--	--	--	--	--	--	--	--	--	--	--	LT & RT SOLID
288+07	298+75	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SKIP, RT SOLID
298+75	305+00	782	57	307+25	315+36	321+65	56350	1096	1096	1096	35	205	205	205	LT & RT SOLID
305+00	307+25	--	--	--	--	--	--	--	--	--	--	--	--	--	RT SKIP
307+25	315+36	--	--	--	--	--	--	--	--	--	--	--	--	--	LT SOLID, RT SKIP
315+36	321+65	--	--	--	--	--	--	--	--	--	--	--	--	--	LT & RT SOLID
PROJECT 3320-00-75 SUBTOTAL		56350	0	2	0	0	2	0	0	0	0	0	0	0	0
US 14 / STH 11 INTERSECTION	655	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PROJECT 1706-00-73 SUBTOTAL	655	0	1096	1096	1096	35	35	35	35	35	35	35	35	35	205
TOTAL	57005	35877	1096	1096	1096	35	35	35	35	35	35	35	35	35	205

Addendum No. 01  
ID 1706-00-73  
ID 3320-00-75  
Revised Sheet 63  
June 30, 2016

\* QUANTITY ESTIMATED BASE ON EXISTING MARKINGS. ACTUAL QUANTITY MAY VARY  
BASE ON RESULTS FROM LOCATING NO PASSING ZONES

LOCATING NO PASSING ZONES


ITEM NO.	
648.0100	
LOCATING NO	
PASSING ZONES	
MI	
PROJECT 3320-00-75 SUBTOTAL	5.314
PROJECT 1706-00-73 SUBTOTAL	---
TOTAL	5.314

3

3

TEMPORARY PAVEMENT MARKING

ITEM NO.		649.0400	
TEMPORARY PAVEMENT MARKING REMOVABLE TAPE 4-INCH			
LOCATION	STATION	WHITE LF	BLACK LF
USH 14 / STH 11	INTERSECTION	3455	5298
PROJECT 1706-00-73 SUBTOTAL		3455	5298
41'CL' +96 - 316'CL'+60	CENTERLINE	0	0
PROJECT 3320-00-75 SUBTOTAL		0	0



SAWING

LOCATION	ROADWAY	DESCRIPTION	ITEM NO.	ITEM NO.	ITEM NO.
CURB 97+75 - 98+55, RT	STH 140	100' BACK FROM POST 3	690.0150	690.0250	SPV.0090.02
CURB 103+12 - 103+70, RT	STH 140	100' BACK FROM POST 3	SAWING	SAWING	SAWING
PROJECT 3320-00-75 SUBTOTAL			ASPHALT *	CONCRETE *	CURB OPENINGS *
			LF	LF	LF
PAVEMENT 400+50 - 407+57.22	USH 14/STH 11	CURB AND CULVERT REMOVAL	---	---	---
CURB 321+28 - 321+38	USH 14/STH 11		---	6	---
PROJECT 1706-00-73 SUBTOTAL			898	6	0
TOTAL			898	6	138

\* - ADDITIONAL QUANTITIES SHOWN ELSEWHERE.

Addendum No. 01  
ID 1706-00-73  
ID 3320-00-75  
Revised Sheet 65  
June 30, 2016

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20160712007PROJECT(S):  
1706-00-73  
3320-00-75FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0710	643.0500 Traffic Control Flexible Tubular Marker Posts	24.000 EACH	.		.	
0720	643.0600 Traffic Control Flexible Tubular Marker Bases	24.000 EACH	.		.	
0730	643.0715 Traffic Control Warning Lights Type C	310.000 DAY	.		.	
0740	643.0900 Traffic Control Signs	224.000 DAY	.		.	
0750	643.1050 Traffic Control Signs PCMS	82.000 DAY	.		.	
0760	646.0106 Pavement Marking Epoxy 4-Inch	57,005.000 LF	.		.	
0770	646.0126 Pavement Marking Epoxy 8-Inch	1,096.000 LF	.		.	
0780	647.0110 Pavement Marking Railroad Crossings Epoxy	2.000 EACH	.		.	
0790	647.0566 Pavement Marking Stop Line Epoxy 18-Inch	35.000 LF	.		.	
0800	647.0746 Pavement Marking Diagonal Epoxy 24-Inch	205.000 LF	.		.	
0810	648.0100 Locating No-Passing Zones	5.314 MI	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20160712007PROJECT(S):  
1706-00-73  
3320-00-75FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0820	649.0400 Temporary Pavement Marking Removable Tape 4-Inch	14,406.000 LF	.		.	
0830	690.0150 Sawing Asphalt	898.000 LF	.		.	
0840	690.0250 Sawing Concrete	6.000 LF	.		.	
0850	SPV.0060 Special 001. Baseline CPM Progress Schedule	1.000 EACH	.		.	
0860	SPV.0060 Special 002. CPM Progress Schedule Updates and Accepted Revisions	2.000 EACH	.		.	
0870	SPV.0060 Special 250. Sign Blinder	1.000 EACH	.		.	
0880	SPV.0090 Special 001. Fence Barbed Wire Special	346.000 LF	.		.	
0890	SPV.0090 Special 002. Sawing Curb Openings	138.000 LF	.		.	
0900	SPV.0090 Special 003. Temporary Fence	346.000 LF	.		.	
0910	SPV.0105 Special 001. Survey Project (1706-00-73)	LUMP	LUMP		.	

SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20160712007

PROJECT(S):  
1706-00-73  
3320-00-75

FEDERAL ID(S):  
N/A  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0920	SPV.0105 Special 002. Survey Project (3320-00-75)	LUMP	LUMP			.
0930	646.0406 Pavement Marking Same Day Epoxy 4-Inch	35,877.000 LF	.			.
	SECTION 0001 TOTAL					.
	TOTAL BID					.