



Wisconsin Department of Transportation

December 11, 2016

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

Proposal #16: 1130-44-71, WISC 2016 475
Appleton – Green Bay
CTH J – Orange Lane
IH 41
Brown/Outagamie

Letting of December 13, 2016 Letting

This is Addendum No. 02, which provides for the following:

Schedule of Items

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
205.0100	Common Excavation	CY	34,841	118	34,959

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
313	Updated Misc. Quantity sheet

Schedule of Items

Attached, dated December 11, 2016, are the revised Schedule of Items Page 1.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 313

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 02
ID 1130-44-71
Revised Sheet 313
December 11, 2016

MARKERS_CULVERT_END

STATION	LOCATION	MARKERS CULVERT END 633.5200 EACH
PROJECT		
TOTAL 0010		30

RI PRAP_MEDIUM

STATION	LOCATION	RI PRAP MEDIUM 606.0200 CY	GEOTEXTILE FABRIC TYPE HR 645.0120 SY
1410+11 NB(*)	I-41 NB LT	3	10
1410+51 SB(*)	I-41 SB RT	3	10
1412+49 NB(*)	I-41 NB LT	3	10
1412+86 SB(*)	I-41 SB RT	3	10
1326+39 NB(**)	I-41 NB RT/LT	6	20
1326+39 SB(**)	I-41 SB RT	3	10
1326+56 SB(**)	I-41 SB LT	3	10
1458+08 NB	CTH S, NB 115' RT	27	91
1459+40 NB	CTH S, NB 118' RT	28	96
UNDISTRIBUTED		15	50
TOTAL 0010		94	317

FRENCH DRAIN

STATION	LOCATION	EXCAVATION COMMON^ 205.0100 CY	BASE AGGREGATE DENSE 3/4- 1 INCH^ 305.0110 TON	SELECT CRUSHED MATERIAL 312.0110 TON	GEOTEXTILE FABRIC TYPE DF SCHEDULE B 645.0112 SY
213+14 U SE	. 217+57 U SE CTH U SE LT	67	35	140	476
1309+37 U NW	. 1312+81 U NW CTH U NW RT	51	13	107	371
UNDISTRIBUTED		-	-	25	42
TOTAL 0010		118	48	272	889

^ ADDITIONAL QUANTITY SHOWN ELSEWHERE

DELI NEATOR_SUMMARY

STATION	TO	STATION	LOCATION	DELI NEATOR POSTS STEEL BRACKETS 633.0100 EACH	DELI NEATOR REFLECTORS 633.0500 EACH	DELI NEATOR BRACKETS 633.1000 EACH
1188+00 NB	1400+00 NB(*)	I-41 SB LT		140	170	3
1400+00 NB(*)	- 1623+78 NB(*)	I-41 NB RT		268	418	4
UNDISTRIBUTED				10	20	-
TOTAL 0010				418	608	7



Proposal Schedule of Items

Proposal ID: 20161213016

Project(s): 1130-44-71

SECTION: 0001 Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0010	201.0110 Clearing	606.000 SY	_____.	_____.
0020	201.0210 Grubbing	606.000 SY	_____.	_____.
0030	203.0100 Removing Small Pipe Culverts	11.000 EACH	_____.	_____.
0040	203.0600.S Removing Old Structure Over Waterway With Minimal Debris (station) 01. 1327+50.60	LS	LUMP SUM	_____.
0050	204.0100 Removing Pavement	6,750.000 SY	_____.	_____.
0060	204.0105 Removing Pavement Butt Joints	1,333.000 SY	_____.	_____.
0070	204.0115 Removing Asphaltic Surface Butt Joints	130.000 SY	_____.	_____.
0080	204.0120 Removing Asphaltic Surface Milling	304,217.000 SY	_____.	_____.
0090	204.0157 Removing Concrete Barrier	1,526.000 LF	_____.	_____.
0100	204.0170 Removing Fence	4,398.000 LF	_____.	_____.
0110	204.0180 Removing Delineators and Markers	378.000 EACH	_____.	_____.
0120	204.0190 Removing Surface Drains	2.000 EACH	_____.	_____.
0130	204.0210 Removing Manholes	1.000 EACH	_____.	_____.
0140	204.0270 Abandoning Culvert Pipes	1.000 EACH	_____.	_____.
0150	204.9060.S Removing (item description) 01. Culvert Endwalls	13.000 EACH	_____.	_____.
0160	205.0100 Excavation Common	34,959.000 CY	_____.	_____.

