



Wisconsin Department of Transportation

December 8, 2016

Division of Transportation Systems Development

Bureau of Project Development
 4802 Sheboygan Avenue, Rm 601
 P O Box 7916
 Madison, WI 53707-7916

Telephone: (608) 266-1631
 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #38: 1550-04-61, WISC 2016 497
 Clear Lake - Cumberland
 Tributary Lake Magnor C-48-0019
 USH 63
 Polk County**

Letting of December 13, 2016

This is Addendum No. 01, which provides for the following:

Special Provisions

Added Special Provisions	
Article No.	Description
23	Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 87x136-Inch, Item SPV.0090.02

Deleted Special Provisions	
Article No.	Description
20	Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-V 87x136-Inch, Item SPV.0090.01

Schedule of Items

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
SPV.0090.02	Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 87 x 136-Inch	LF	0	68	68

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
SPV.0090.01	Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-V 87 x 136-Inch	LF	68	0	0

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
10	Miscellaneous Quantities (Remove SPV.0090.01 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-V 87 x 136-Inch and replace with SPV.0090.01 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 87 x 136-Inch).

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1550-04-61

December 8, 2016

Special Provisions

20. DELETED.

23. Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 87x136-Inch, Item SPV.0090.02.

A Description

This special provision describes furnishing and installing a reinforced concrete horizontal elliptical pipe culvert.

B Materials

Furnish reinforced concrete that is in accordance to the pertinent requirements of section 523.2 of the standard specifications.

C Construction

This section shall meet all applicable requirements of section 523.3 of the standard specifications.

D Measurement

This section shall meet all applicable requirements of section 523.4 of the standard specifications.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.01	Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 87x136-Inch	LF

Payment is full compensation for providing, hauling, and placing the Reinforced Concrete Horizontal Elliptical Class HE-IV culvert pipe, geotextile joint wrapping, and joint ties for the connection between pipe sections and the connection to concrete masonry endwalls; for furnishing all excavating, including foundation or bed, and any associated dewatering; for providing and placing granular backfill or graded aggregate for granular foundation or cushion; for backfilling unless granular backfill is specified; for maintaining temporary drainage; and for replacing damaged installations. The department will pay separately for cast-in-place concrete and alternate endwall installations under the Concrete Masonry Endwalls bid item as specified in Section 504.5 and other associated bid items.

Schedule of Items

Attached, dated December 8, 2016, are the revised Schedule of Items Page 4.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 10.

END OF ADDENDUM

Addendum No. 01
ID 1550-04-61
Revised Sheet 10
December 8, 2016

CLEARING AND GRUBBING

CATEGORY	STATION	LOCATION	201.0105 CLEARING	201.0205 GRUBBING	STA	STA
0010	239+00 - 240+00	RT & LT	1	1	1	1
TOTAL			1	1		

REMOVING OLD STRUCTURE

CATEGORY	STATION	LS	REMARKS
0010	239+85	1	10'x6' CONC. BOX CULVERT
TOTAL		1	

EXCAVATION

CATEGORY	STATION	205.0100 EXCAVATION COMMON	208.0100 EXPANDED BORROW (2)
0010	238+85 - 240+10	240	182
TOTAL		240	182

(1) - NOT ABID ITEM - FOR INFORMATIONAL PURPOSES ONLY.
 (2) - FILL EXPANSION = 30%

COFFERDAMS

CATEGORY	STATION	206.5000 COFFERDAMS C-48-0019
0010	238+85	1
TOTAL		1

BACKFILL ITEMS

CATEGORY	STATION	209.1500 BACKFILL GRANULAR GRADE 1	209.0200.S BACKFILL CONTROLLED LOW STRENGTH	210.2100 BACKFILL STRUCTURE TYPE B
0010	239+85	60	75	120
TOTAL		60	75	120

NOTE: BACKFILL GRANULAR GRADE 1 WAS CALCULATED USING 2.0 TONS/CY.
 USE BACKFILL STRUCTURE TYPE B ADJACENT TO CONCRETE MASONRY ENDWALLS.

BASE AGGREGATE ITEMS

CATEGORY	STATION	305.0120 BASE AGGREGATE DENSE	624.0100 WATER
0010	238+85 - 240+10	55	7
TOTAL		55	7

NOTE: BASE AGGREGATE DENSE (3/4-INCH & 1 1/4-INCH) WERE CALCULATED USING 2.0 TONS/CY.
 **ADDITIONAL QUANTITIES LISTED ELSEWHERE

ASPHALT PAVEMENT ITEMS

CATEGORY	STATION	THICKNESS	455.0605 TACK ASPHALTIC COAT SPECIAL	GAL	TON
0010	238+85 - 240+10	6.75	46	165	165
TOTAL			46	165	165

NOTE: TACK COAT CALCULATED AT 0.05 GALLONS PER SQUARE YARD

CULVERT PIPE

CATEGORY	STATION	LOCATION	504.0900 CONCRETE MASONRY ENDWALLS	CY	633.5200 CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL CLASS HE-NV87X136-INCH	EA
0010	239+85	LT	15	32	2	2
0010	239+85	RT	16	36	2	2
TOTAL			31	68	4	4

NOTE: TACK COAT CALCULATED AT 0.05 GALLONS PER SQUARE YARD

RIPRAP ITEMS

CATEGORY	STATION	LOCATION	606.0100 RIPRAP LIGHT	645.0130 GEOTEXTILE TYPE R	CY	SY
0010	239+85	LT	10	38	14	50
0010	239+85	RT	14	50	24	88
TOTAL			24	88		

MOBILIZATION

CATEGORY	STATION	PROJECT	MOBILIZATION
0010	1550-04-61	1	1
TOTAL		1	1

RESTORATION ITEMS

CATEGORY	STATION	LOCATION	624.0100 WATER MGAL	625.0500 SALVAGED TOPSOIL	627.0200 MULCHING SY	629.0210 FERTILIZER TYPE B	630.0140 SEEDING MIXTURE #40	630.0200 SEEDING TEMPORARY
0010	238+85 - 240+10	LT	5.2	157	231	0.1	5	4
0010	238+85 - 240+10	RT	7.0	237	313	0.2	6	5
0010	UNDISTRIBUTED		2.8	79	109	0.1	3	2
TOTAL			15	473	653	0.4	14	11

**ADDITIONAL QUANTITIES LISTED ELSEWHERE



Proposal Schedule of Items

Proposal ID: 20161213038

Project(s): 1550-04-61

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0500	650.9920 Construction Staking Slope Stakes	125.000 LF	_____.	_____.
0510	690.0150 Sawing Asphalt	74.000 LF	_____.	_____.
0520	999.1500.S Crack and Damage Survey	LS	LUMP SUM	_____.
0540	SPV.0105 Special 01. Research and Locate Existing Property Monuments	LS	LUMP SUM	_____.
0550	SPV.0105 Special 02. Verify and Replace Existing Property Monuments	LS	LUMP SUM	_____.
0560	SPV.0090 Special 02. Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 87x136-Inch	68.000 LF	_____.	_____.
Section: 0001			Total:	_____.
				Total Bid: _____.

