



# Wisconsin Department of Transportation

April 6, 2017

## Division of Transportation Systems Development

Bureau of Project Development  
4802 Sheboygan Avenue, Rm 601  
P O Box 7916  
Madison, WI 53707-7916

### NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

**Proposal #33: 7995-02-46**  
**City of Eau Claire, Grand Avenue**  
**Half Moon Lake Bridge B-18-0230**  
**Loc Str**  
**Eau Claire County**

### Letting of April 11, 2017

This is Addendum No. 01, which provides for the following:

#### Special Provisions

Revised Special Provisions	
Article No.	Description
14	Excavation Marsh, Item 205.0400
34	Flagstone Paving, Item SPV.0165.02
35	Stone Screenings with Binder, Item SPV.0195.01

#### Schedule of Items

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
SPV.0165.01	Stone Retaining Wall	SF	440	120	560

#### Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
28	Miscellaneous Quantities (Revised information for item SPV.0165.01 Stone Retaining Walls)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**7995-02-46**

**April 6, 2017**

**Special Provisions**

**14. Excavation Marsh, Item 205.0400.**

*Replace entire article language with the following:*

*Add the following to standard spec 205.3:*

Haul excavated material to the Veolia ES Seven Mile Creek landfill located at 8001 Olson Drive, Eau Claire, WI 54703, in lined trucks to limit drainage of wet material from trucks during hauling operations. All tipping fees for disposal of material will be paid directly by the City of Eau Claire.

**34. Flagstone Paving, Item SPV.0165.02.**

*Replace entire section titled B.1 Flagstone Pavers with the following:*

**B.1 Flagstone Pavers**

Acceptable Suppliers: Provide flagstone pavers by one of the suppliers below or approved equal.

Halquist Stone, Sussex, Wisconsin, 800-255-8111, 1

Central Wisconsin Stone, Mosinee, Wisconsin, 715-693-4535, info@centralwisconsinstore.com

Lemke Stone, Lannon, Wisconsin, 262-502-1579, info@lemke.com

Description: Irregular shaped limestone paving stones as shown on plan, with split faces and cut or split edges.

Color and Grain: Light buff with medium grain.

Sizes: As indicated on the plans.

Samples: Submit samples of the stone proposed for use at least 10 days prior to installation for review and approval. Samples shall range in color, finish, and variations expected in final construction.

**35. Stone Screenings with Binder, Item SPV.0195.01.**

*Replace entire section titled B.2 Binder with the following:*

**B.2 Binder**

Non-toxic, colorless, odorless, concentrated organic binder powder that binds decomposed granite or crushed 3/8-inch or 1/4-inch minus aggregate. Binder color to be selected by the City of Eau Claire from manufacturer's standard product colors.

Product shall have 64% pre-consumer recycled content.

Product shall have 25 years' experience at same formulation.

Provide 1-year product manufacturer's warranty for permeable stabilizer binder.

**Schedule of Items**

Attached, dated April 6, 2017, are the revised Schedule of Items Page 8.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: Sheet #28, Miscellaneous Quantities

END OF ADDENDUM

LIGHTING UNITS AND ELECTRICAL WIRE LIGHTING

UNIT	STATION	OFFSET	DESCRIPTION	QUANTITY
L1	204+50	21' LT	DECORATIVE LIGHTING UNIT	1
L2	206+25	21' RT	UNDERDECK LIGHTING UNIT	1
L3	203+50	23.5' LT	12 AWG WIRE	170
L4	204+70	21' RT	UNDERDECK LIGHTING UNIT	1
L5	202+30	21' LT	UNDERDECK LIGHTING UNIT	1
L6	203+10	21' RT	UNDERDECK LIGHTING UNIT	1
L7	200+70	21' LT	UNDERDECK LIGHTING UNIT	1
L8	201+50	21' RT	UNDERDECK LIGHTING UNIT	1
L9	202+44	12' LT	UNDERDECK LIGHTING UNIT	1
L10	202+90	12' RT	UNDERDECK LIGHTING UNIT	1
TOTAL (CATEGORY 0010)				1,360
TOTAL (CATEGORY 0030)				2

SAWING

LOCATION	O/S	690.0150 ASPHALT	690.0250 CONCRETE	TOTAL
200+25	16' L/R	32	16	48
200+25	17' R	-	6	6
206+25	20' R	20	-	20
206+25	44' L	58	-	58
206+30	48' L	-	5	5
206+25	27' R	-	5	5
TOTALS		110	16	126

SHORELINE RIPRAP

LOCATION	QUANTITY
200+25 - 206+00 LT	314
200+25 - 206+00 RT	283
TOTALS	597

BENCHES

STA	TO	STA	SPV.0060.03 EACH
200+25	202+00	202+00	2
202+01	203+50	203+50	4
203+51	206+25	206+25	2
TOTAL (CATEGORY 0030)			8

STONE RETAINING WALL AND CURBING

STA	LOCATION	SPV.0185.01 STONE RETAINING WALL SF	SPV.0090.03 STONE CURBING LF
201+35	40' RT	-	15
201+75	40' LT	-	15
203+65	40' LT	-	15
204+25	40' RT	-	15
201+50	55' LT	80	-
202+15	50' LT	65	-
202+35	65' RT	120	-
203+15	50' LT	120	-
203+25	50' RT	75	-
204+50	50' LT	100	-
TOTAL (CATEGORY 0030)		560	60

LANDSCAPE SURFACE TREATMENTS

STA	TO	STA	SPV.0185.02 FLAGSTONE PAVING SF	SPV.0195.01 STONE SCREENINGS WITH BINDER TON	SPV.0090.01 ALUMINUM EDGING LF	405.1000 STAMPING COLORED CONCRETE CY
200+25	202+00	202+00	467	40	1750	-
202+01	203+50	203+50	-	-	25	-
203+51	206+25	206+25	603	50	1465	-
TOTAL (CATEGORY 0010)			0	0	0	25
TOTAL (CATEGORY 0030)			1070	90	3215	0

TREES

STA	TO	STA	632.0101.01 SIENNA GLEN MAPLE B&B, 2.5" CAL	632.0101.02 HERITAGE BIRCH B&B, CLUMP, 6-8' H.	632.0101.03 SKYLINE THORNLESS HONEYLOCUST B&B, 2.5" CAL	632.0101.04 WHITE OAK B&B, 2.5" CAL	632.0101.05 SWAMP WHITE OAK B&B, 2.5" CAL
200+25	202+44	202+44	4	6	7	3	4
202+94	206+25	206+25	3	6	13	2	9
TOTAL			7	12	20	5	13

CONSTRUCTION STAKING LANDSCAPE LAYOUT

SPV.0060.04 EACH	LOCATION PROJECT (7995-02-46)	SPV.0105.01 LS
1		1
1		1
2		1
TOTAL		4

TREE DROP

STA	LOCATION	SPV.0060.04 EACH
201+75	RT	1
203+25	LT	1
203+65	RT	2
TOTAL		4

CINIC PULBOX

LOCATION	SPV.0060.05 EACH	
200+12.0	48.0' LT	1
200+55.0	22.0' RT	1
203+05.0	23.4' RT	1
206+35.0	24.0' RT	1
TOTALS		4

CINIC CONDUIT 1 1/4 INCH

LOCATION	SPV.0060.04 LF
200+12 LT - 200+55 RT	80
205+55 RT - 206+35 RT	560
TOTALS	640

Addendum No. 01  
ID 7995-02-46  
Revised Sheet 28  
April 6, 2017



Proposal Schedule of Items

Proposal ID: 20170411033 Project(s): 7995-02-46

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1090	SPV.0060 Special 01. Underdeck Lighting Unit	2.000 EACH	_____.	_____.
1100	SPV.0060 Special 02. Decorative Lighting Unit	8.000 EACH	_____.	_____.
1110	SPV.0060 Special 03. Benches	8.000 EACH	_____.	_____.
1120	SPV.0060 Special 04. Tree Drop	4.000 EACH	_____.	_____.
1130	SPV.0060 Special 05. CINC Pull Box	4.000 EACH	_____.	_____.
1140	SPV.0085 Special 01. Native Seeding	12.000 LB	_____.	_____.
1150	SPV.0090 Special 01. Aluminum Edging	3,215.000 LF	_____.	_____.
1160	SPV.0090 Special 02. Concrete Curb and Gutter 24-Inch	1,235.000 LF	_____.	_____.
1170	SPV.0090 Special 03. Stone Curbing	60.000 LF	_____.	_____.
1180	SPV.0090 Special 04. CINC Conduit 1 1/4-Inch	640.000 LF	_____.	_____.
1190	SPV.0105 Special 01. Construction Staking Landscape Layout	LS	LUMP SUM	_____.
1200	SPV.0165 Special 01. Stone Retaining Wall	560.000 SF	_____.	_____.
1210	SPV.0165 Special 02. Flagstone Paving	1,070.000 SF	_____.	_____.
1220	SPV.0195 Special 01. Stone Screenings With Binder	90.000 TON	_____.	_____.

Section: 0001

Total: \_\_\_\_\_.

Total Bid: \_\_\_\_\_.

