



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

June 7, 2017

NOTICE TO ALL CONTRACTORS:

**Proposal #01: 1650-02-60, WISC 2017 313
Boscobel - Readstown
STH 60 to Bell Center Road
USH 61
Crawford County**

Letting of June 13, 2017

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0125	Removing Asphalt Surface Milling	Ton	45,389	-11,095	34,294

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
67	Revised misc. quantities for Removing Asphalt Surface Milling

Schedule of Items

Attached, dated June 7, 2017, are the revised Schedule of Items Page 1.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 67

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

EARTHWORK		EXCAVATION COMMON		BORROW		REMARKS	
CATEGORY	STATION TO	STATION	LOCATION	CY	CY	CY	
0010	458+13	-	461+63	M/L	103	2814	NEW TURN LANE AND EMBANKMENT
TOTAL 0010				103		2814	

MILLING ITEMS		REMOVING ASPHALTIC SURFACE MILLING		MILL AND RELAY		REMARKS	
CATEGORY	STATION TO	STATION	LOCATION	SY	SY	SY	
0010	0+00	-	5+50	NB & SB	0	2"	removal
	5+50	-	7+50	transition	992	avg 2"	removal / 6" relay
	7+50	-	61+00	mainline	22991	6"	relay
	61+00	-	63+00	transition	997	avg 2"	removal / 6" relay
	63+00	-	78+88	mainline	6907	3"	removal / 6" relay
	80+21	-	175+00	mainline	38029	3"	removal / 6" relay
	175+00	-	285+00	mainline	44245	3"	removal / 6" relay
	285+00	-	381+50	mainline	39017	3"	removal / 6" relay
	381+50	-	446+00	mainline	32047	3"	removal / 6" relay
	446+00	-	474+40	mainline	14412	3"	removal / 8" relay
	474+40	-	612+50	mainline	55912	3"	removal / 8" relay
	14+25	-	20+00	STH 60 west	0	2"	removal
	0+22	-	2+10	STH 60 east	0	4"	removal
TOTAL 0010				34294		255496	

GRADING SHAPING & FINISHING INTERSECTION (GRAY RD)		FOR INFORMATION ONLY		EXCAVATION/GUTSALVAGE FERTILIZER SEEDING MULCH		REMARKS	
CATEGORY	STATION TO	STATION	LOCATION	TOPSOIL TYPE B	MIXTURE NO. 20	TEMPORARY LB	
0010	14+25	'	STH 60' - 0+00	'	STH 60' - 78+88		M/L
	80+21	-	612+50				M/L
TOTAL 0010							211,0100

ABANDON CULVERT PIPE		SELECT CRUSHED		GEOGRID TYPE SR		REMARKS	
CATEGORY	STATION TO	STATION	LOCATION	TON	SY	SY	
0010	458+32	USH 61 /	CTH W 1	79			72" CMCP
TOTAL 0010				79			

Addendum No. 02
ID 1650-02-60
Revised Sheet 67
June 7, 2017

AGGREGATE & GEOGRID		BAD 3/4-Inch		BAD 1 1/4-Inch		REMARKS	
CATEGORY	STATION TO	STATION	LOCATION	TON	TON	TON	
0010	14+25	'	STH 60' - 458+12	RT & LT	612+50	2175	Mainline Shoulders new embankment base at geo grid replacement area Not Distributed
	458+12	-	470+27	CTH W Turn Ln	211		
	Varies	-	Varies	Not Distributed	2500		
TOTAL 0010				2175	2711	5000	

MISCELLANEOUS QUANTITIES		COUNTY: CRAWFORD		HWY: USH 61		PROJECT NO: 1650-02-60	
CATEGORY	STATION TO	STATION	LOCATION	TON	TON	TON	
0010	14+25	'	STH 60' - 0+00	STH 60' - 78+88	80+21	612+50	
TOTAL 0010				312,0110	305,0120	312,0110	



Proposal Schedule of Items

Proposal ID: 20170613001 Project(s): 1650-02-60

Federal ID(s): WISC 2017313

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0010	204.0105 Removing Pavement Butt Joints	21.000 SY	_____.	_____.
0020	204.0110 Removing Asphaltic Surface	7,286.000 SY	_____.	_____.
0030	204.0125 Removing Asphaltic Surface Milling	34,294.000 TON	_____.	_____.
0040	204.0130 Removing Curb	5.000 LF	_____.	_____.
0050	204.0150 Removing Curb & Gutter	218.000 LF	_____.	_____.
0060	204.0165 Removing Guardrail	14,773.000 LF	_____.	_____.
0070	204.0170 Removing Fence	300.000 LF	_____.	_____.
0080	204.0185 Removing Masonry	4.000 CY	_____.	_____.
0090	204.0270 Abandoning Culvert Pipes	1.000 EACH	_____.	_____.
0100	205.0100 Excavation Common	93.000 CY	_____.	_____.
0110	205.9015.S Grading Shaping and Finishing Intersection (location) 01. GRAY RD	LS	LUMP SUM	_____.
0120	208.0100 Borrow	2,709.000 CY	_____.	_____.
0130	209.0200.S Backfill Controlled Low Strength	79.000 CY	_____.	_____.
0140	211.0100 Prepare Foundation for Asphaltic Paving (project) 01.1650-02-60	LS	LUMP SUM	_____.
0150	213.0100 Finishing Roadway (project) 01.1650-02-60	1.000 EACH	_____.	_____.
0160	305.0110 Base Aggregate Dense 3/4-Inch	2,175.000 TON	_____.	_____.

