



Wisconsin Department of Transportation

November 30, 2017

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #13: 2723-00-71, WISC 2018 010
Moorland Road
Woods Road to Janesville Road
Local Street
Waukesha County

Letting of December 12, 2017

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
36	LED Roadway Luminaire, Item SPV.0060.0012
43	Outlet Structure, SPV.0060.0088

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
74	Storm Sewer – Construction Details (Outlet Structure revised concrete base elevation)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

2723-00-71

November 30, 2017

Special Provisions

36. LED Roadway Luminaire, Item SPV.0060.0012.

*Replace the last paragraph under section titled **B Materials** with the following:*

Acceptable Luminaries

- Philips Lumec GPLM-130W98LED4K-ES-LE2 or latest generation
- Cree LEDway STR-LWY-2ME-HT-1-F-UL-A-40K-PD-SC or latest generation
- Approved equal

*Delete the last paragraph under section titled **C Construction**.*

43. Outlet Structure, SPV.0060.0088.

*Replace the first paragraph under section titled **A Description** with the following:*

Furnish and install detention basin Outlet Structure in accordance to the pertinent provisions of standard spec 611, as shown on the plans and as hereinafter provided. Furnish and install trash rack on the Outlet Structure. Furnish and install trash rack in accordance to the pertinent provisions of standard spec 506 and 513, as shown on the plans and as hereinafter provided. Provide orifice holes and anti-seep collars as shown on the plan.

*Replace the last paragraph under section titled **E Payment** with the following:*

Payment is full compensation for providing and placing all materials, including all masonry, steel and pipe connections, and other fittings; for furnishing and installing trash rack; for furnishing and installing orifice holes and anti-seep collars; for furnishing all excavating, backfilling, disposing of surplus material, and for cleaning out and restoring the work site.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 74.

END OF ADDENDUM

