



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

December 7, 2017

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #17: 4997-00-64, WISC 2018 016
C Sturgeon Bay, CTH C
STH 42/57 – West Elm St
CTH C
Door County**

Letting of December 12, 2017

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
13	Removing Asphaltic Pavement Milling, Item 204.0120

Deleted Special Provisions	
Article No.	Description
8	Municipality Acceptance of Sanitary Sewer and Water Main Construction
16	Reheating HMA Pavement Longitudinal Joints, Item 460.4110.S

Schedule of Items:

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
460.4110.S	Reheating HMA Pavement Longitudinal Joints	LF	9,530	-9,530	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
66	Removed item 460.4110.S from the "Pavement Items" MQ table.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

4997-00-64

December 7, 2017

Special Provisions

8. DELETED.

13. Removing Asphaltic Pavement Milling, Item 204.0120.

Replace entire article and title with the following:

13. Removing Asphaltic Surface Milling, Item 204.0120.

Removing Asphaltic Surface Milling shall conform to standard spec 204 except as follows:

1. Contact John Kolodziej, PE, Door County Highway Commissioner at (920) 746-2507 a minimum of 5 days prior to beginning working operations to coordinate trucking schedule.
2. Removing Asphaltic Surface Milling shall consist of milling the pavement and loading the millings into Door County trucks for hauling. No hauling is included with this item.
3. Asphaltic millings shall become the property of Door County.

16. DELETED.

Schedule of Items

Attached, dated December 7, 2017, are the revised Schedule of Items Pages 1 – 8.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 66

END OF ADDENDUM



Proposal Schedule of Items

Proposal ID: 20171212017 Project(s): 4997-00-64

Federal ID(s): WISC 2018016

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	47.000 STA	_____.	_____.
0004	201.0205 Grubbing	47.000 STA	_____.	_____.
0006	203.0100 Removing Small Pipe Culverts	8.000 EACH	_____.	_____.
0008	204.0120 Removing Asphaltic Surface Milling	20,940.000 SY	_____.	_____.
0010	204.0150 Removing Curb & Gutter	4,977.000 LF	_____.	_____.
0012	204.0155 Removing Concrete Sidewalk	48.000 SY	_____.	_____.
0014	204.0210 Removing Manholes	5.000 EACH	_____.	_____.
0016	204.0220 Removing Inlets	1.000 EACH	_____.	_____.
0018	204.0245 Removing Storm Sewer (size) 01. 12-inch	678.000 LF	_____.	_____.
0020	204.0250 Abandoning Manholes	2.000 EACH	_____.	_____.
0022	205.0100 Excavation Common	13,478.000 CY	_____.	_____.
0024	211.0100 Prepare Foundation for Asphaltic Paving (project) 01. 4997-00-64	LS	LUMP SUM	_____.
0026	213.0100 Finishing Roadway (project) 01. 4997-00-64	1.000 EACH	_____.	_____.
0028	305.0110 Base Aggregate Dense 3/4-Inch	1,892.000 TON	_____.	_____.
0030	305.0120 Base Aggregate Dense 1 1/4-Inch	14,300.000 TON	_____.	_____.
0032	416.0160 Concrete Driveway 6-Inch	811.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212017 Project(s): 4997-00-64

Federal ID(s): WISC 2018016

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	440.4410 Incentive IRI Ride	3,881.820 DOL	1.00000	3,881.82
0036	455.0605 Tack Coat	1,664.000 GAL	_____	_____
0038	460.2000 Incentive Density HMA Pavement	3,000.000 DOL	1.00000	3,000.00
0042	460.5223 HMA Pavement 3 LT 58-28 S	2,260.000 TON	_____	_____
0044	460.5224 HMA Pavement 4 LT 58-28 S	2,416.000 TON	_____	_____
0046	465.0105 Asphaltic Surface	348.000 TON	_____	_____
0048	465.0120 Asphaltic Surface Driveways and Field Entrances	312.000 TON	_____	_____
0050	520.8000 Concrete Collars for Pipe	5.000 EACH	_____	_____
0052	521.2005.S Surface Drain Pipe Corrugated Metal Slotted (inch) 01. 12-Inch	85.000 LF	_____	_____
0054	601.0600 Concrete Curb Pedestrian	10.000 LF	_____	_____
0056	602.0410 Concrete Sidewalk 5-Inch	55,365.000 SF	_____	_____
0058	602.0515 Curb Ramp Detectable Warning Field Natural Patina	275.000 SF	_____	_____
0060	608.0005 Storm Sewer Rock Excavation	585.000 CY	_____	_____
0062	608.0312 Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	684.000 LF	_____	_____
0064	608.0315 Storm Sewer Pipe Reinforced Concrete Class III 15-Inch	238.000 LF	_____	_____



Proposal Schedule of Items

Proposal ID: 20171212017 Project(s): 4997-00-64

Federal ID(s): WISC 2018016

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	608.0318 Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	149.000 LF	_____.	_____.
0068	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	1,586.000 LF	_____.	_____.
0070	608.0330 Storm Sewer Pipe Reinforced Concrete Class III 30-Inch	105.000 LF	_____.	_____.
0072	608.0336 Storm Sewer Pipe Reinforced Concrete Class III 36-Inch	3,264.000 LF	_____.	_____.
0074	608.0342 Storm Sewer Pipe Reinforced Concrete Class III 42-Inch	527.000 LF	_____.	_____.
0076	608.0424 Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	296.000 LF	_____.	_____.
0078	611.0530 Manhole Covers Type J	30.000 EACH	_____.	_____.
0080	611.0612 Inlet Covers Type C	1.000 EACH	_____.	_____.
0082	611.0624 Inlet Covers Type H	48.000 EACH	_____.	_____.
0084	611.0642 Inlet Covers Type MS	4.000 EACH	_____.	_____.
0086	611.1230 Catch Basins 2x3-FT	43.000 EACH	_____.	_____.
0088	611.2004 Manholes 4-FT Diameter	11.000 EACH	_____.	_____.
0090	611.2005 Manholes 5-FT Diameter	14.000 EACH	_____.	_____.
0092	611.2006 Manholes 6-FT Diameter	7.000 EACH	_____.	_____.
0094	611.2007 Manholes 7-FT Diameter	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212017 Project(s): 4997-00-64

Federal ID(s): WISC 2018016

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	611.2008 Manholes 8-FT Diameter	1.000 EACH	_____.	_____.
0098	611.3230 Inlets 2x3-FT	6.000 EACH	_____.	_____.
0100	611.3901 Inlets Median 1 Grate	1.000 EACH	_____.	_____.
0102	611.3902 Inlets Median 2 Grate	3.000 EACH	_____.	_____.
0104	612.0902.S Insulation Board Polystyrene (inch) 01. 2-Inch	2.000 SY	_____.	_____.
0106	618.0100 Maintenance And Repair of Haul Roads (project) 01. 4997-00-64	1.000 EACH	_____.	_____.
0108	619.1000 Mobilization	1.000 EACH	_____.	_____.
0110	623.0200 Dust Control Surface Treatment	4,500.000 SY	_____.	_____.
0112	624.0100 Water	40.000 MGAL	_____.	_____.
0114	625.0100 Topsoil	11,500.000 SY	_____.	_____.
0116	627.0200 Mulching	7,200.000 SY	_____.	_____.
0118	628.1504 Silt Fence	4,000.000 LF	_____.	_____.
0120	628.1520 Silt Fence Maintenance	4,000.000 LF	_____.	_____.
0122	628.1905 Mobilizations Erosion Control	4.000 EACH	_____.	_____.
0124	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH	_____.	_____.
0126	628.2006 Erosion Mat Urban Class I Type A	4,300.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212017 Project(s): 4997-00-64

Federal ID(s): WISC 2018016

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0128	628.6005 Turbidity Barriers	50.000 SY	_____.	_____.
0130	628.7005 Inlet Protection Type A	60.000 EACH	_____.	_____.
0132	628.7010 Inlet Protection Type B	5.000 EACH	_____.	_____.
0134	628.7015 Inlet Protection Type C	64.000 EACH	_____.	_____.
0136	628.7020 Inlet Protection Type D	2.000 EACH	_____.	_____.
0138	628.7555 Culvert Pipe Checks	20.000 EACH	_____.	_____.
0140	628.7570 Rock Bags	50.000 EACH	_____.	_____.
0142	629.0210 Fertilizer Type B	8.000 CWT	_____.	_____.
0144	630.0140 Seeding Mixture No. 40	220.000 LB	_____.	_____.
0146	634.0614 Posts Wood 4x6-Inch X 14-FT	40.000 EACH	_____.	_____.
0148	634.0616 Posts Wood 4x6-Inch X 16-FT	9.000 EACH	_____.	_____.
0150	634.0620 Posts Wood 4x6-Inch X 20-FT	1.000 EACH	_____.	_____.
0152	637.0620 Sign Flags Permanent Type II	2.000 EACH	_____.	_____.
0154	637.2210 Signs Type II Reflective H	244.980 SF	_____.	_____.
0156	637.2230 Signs Type II Reflective F	4.000 SF	_____.	_____.
0158	638.2602 Removing Signs Type II	40.000 EACH	_____.	_____.
0160	638.3000 Removing Small Sign Supports	26.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212017 Project(s): 4997-00-64

Federal ID(s): WISC 2018016

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0162	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0164	643.0300 Traffic Control Drums	9,150.000 DAY	_____.	_____.
0166	643.0420 Traffic Control Barricades Type III	10,050.000 DAY	_____.	_____.
0168	643.0705 Traffic Control Warning Lights Type A	20,050.000 DAY	_____.	_____.
0170	643.0715 Traffic Control Warning Lights Type C	3,700.000 DAY	_____.	_____.
0172	643.0900 Traffic Control Signs	9,700.000 DAY	_____.	_____.
0174	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0176	646.1020 Marking Line Epoxy 4-Inch	19,274.000 LF	_____.	_____.
0178	646.3020 Marking Line Epoxy 8-Inch	510.000 LF	_____.	_____.
0180	646.5020 Marking Arrow Epoxy	36.000 EACH	_____.	_____.
0182	646.5120 Marking Word Epoxy	3.000 EACH	_____.	_____.
0184	646.5220 Marking Symbol Epoxy	31.000 EACH	_____.	_____.
0186	646.6020 Marking Stop Line Epoxy 12-Inch	159.000 LF	_____.	_____.
0188	646.6120 Marking Stop Line Epoxy 18-Inch	57.000 LF	_____.	_____.
0190	646.7120 Marking Diagonal Epoxy 12-Inch	30.000 LF	_____.	_____.
0192	646.7405 Marking Crosswalk Paint Transverse Line 6-Inch	1,239.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212017 Project(s): 4997-00-64

Federal ID(s): WISC 2018016

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0194	650.4000 Construction Staking Storm Sewer	87.000 EACH	_____.	_____.
0196	650.4500 Construction Staking Subgrade	3,852.000 LF	_____.	_____.
0198	650.5500 Construction Staking Curb Gutter and Curb & Gutter	8,628.000 LF	_____.	_____.
0200	650.8000 Construction Staking Resurfacing Reference	1,810.000 LF	_____.	_____.
0202	650.9910 Construction Staking Supplemental Control (project) 01. 4997-00-64	LS	LUMP SUM	_____.
0204	650.9920 Construction Staking Slope Stakes	5,302.000 LF	_____.	_____.
0206	690.0150 Sawing Asphalt	6,815.000 LF	_____.	_____.
0208	690.0250 Sawing Concrete	227.000 LF	_____.	_____.
0210	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,000.000 HRS	5.00000	10,000.00
0212	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,320.000 HRS	5.00000	6,600.00
0214	SPV.0035 Special 01. Abandon Storm Sewer	26.000 CY	_____.	_____.
0216	SPV.0060 Special 01. Reconstructing Sanitary Manholes	2.000 EACH	_____.	_____.
0218	SPV.0060 Special 02. Adjusting Curb Stop Risers	62.000 EACH	_____.	_____.
0220	SPV.0060 Special 03. Adjusting Valve Boxes	55.000 EACH	_____.	_____.
0222	SPV.0060 Special 04. Adjusting Sanitary Manholes	12.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212017 Project(s): 4997-00-64

Federal ID(s): WISC 2018016

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0224	SPV.0060 Special 05. Curb Stops	10.000 EACH	_____.	_____.
0226	SPV.0090 Special 01. Concrete Curb & Gutter 32-Inch Type D Special	8,628.000 LF	_____.	_____.
0228	SPV.0090 Special 02. Storm Sewer Pipe PVC 4-Inch	56.000 LF	_____.	_____.
0230	SPV.0090 Special 03. Water Service 1-Inch	914.000 LF	_____.	_____.
0232	SPV.0090 Special 04. Sanitary Lateral 6-Inch	1,027.000 LF	_____.	_____.
0234	SPV.0090 Special 05. Storm Sewer Pipe PVC 10-Inch	4.000 LF	_____.	_____.
0236	SPV.0105 Special 01. Removing and Replacing Retaining Wall	LS	LUMP SUM	_____.
0238	SPV.0105 Special 02. Removing and Reinstalling Guardrail	LS	LUMP SUM	_____.
0240	SPV.0105 Special 03. Storm Sewer Outfall	LS	LUMP SUM	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.