



# Wisconsin Department of Transportation

November 30, 2017

## Division of Transportation Systems Development

Bureau of Project Development  
4802 Sheboygan Avenue, Rm 601  
P O Box 7916  
Madison, WI 53707-7916

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #22: 6986-01-70, WISC 2018 021**  
**STH 73 – Spring Lake**  
**STH 73 to CTH Z**  
**CTH F**  
**Waushara County**

### Letting of December 12, 2017

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Added Special Provisions	
Article No.	Description
22	Temporary Portable Rumble Strips, Item 643.0310.S

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0310.S	Temporary Portable Rumble Strips	LS	0	1	1

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
27	Miscellaneous Quantities (Added item for temporary portable rumble strips)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**6986-01-70**

**November 30, 2017**

**Special Provisions**

**22. Temporary Portable Rumble Strips, Item 643.0310.S.**

**A Description**

This special provision describes providing, relocating, maintaining, and removing temporary portable rumble strips.

**B Materials**

Furnish RoadQuake2 or Roadquake2F temporary portable rumble strips, by Plastic Safety Systems. Do not use alternate products or methods without preapproval by the Bureau of Traffic Operations.

**C Construction**

**C.1 Placement**

Provide rumble strips where the plans show or the engineer directs as follows:

1. Before placing rumble strips, clean the roadway of sand and other materials that may cause slippage.
2. Place one end of the rumble strips 6 inches from the roadway centerline. Extend the strips perpendicular to the direction of travel. Ensure strips lay flat on the roadway surface.
3. Only one series of rumble strips, placed before the first work zone, is required per direction of travel for multiple work zones spaced 1 mile or less apart. Work zones spaced greater than 1 mile apart require a separate series of rumble strips.

**C.2 Maintenance**

Maintain rumble strips as follows:

1. If rumble strips slide, become out of alignment, or are no longer in the wheel path of approaching vehicles during the work period, thoroughly clean both sides of the rumble strips and reset on a clean roadway.
2. Repair or replace damaged rumble strips immediately.

**D Measurement**

The department will measure temporary portable rumble strips as a single lump sum unit of work acceptably completed.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
643.0310.S	Temporary Portable Rumble Strips	LS

Payment is full compensation for providing, relocating, maintaining or replacing, and removing temporary portable rumble strips.  
stp-643-020 (20161130)

**Schedule of Items**

Attached, dated November 30, 2017, are the revised Schedule of Items Page 5.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 27.

END OF ADDENDUM

TRAFFIC CONTROL SUMMARY

LOCATION	APPROXIMATE SERVICE DAYS		643.0420 BARRICADES TYPE III		643.0900 SIGNS		REMARKS
	NO. IN SERVICE	DAYS	NO. IN SERVICE	DAYS	NO. IN SERVICE	DAYS	
CTH F / STH 73	60	-	-	-	5	300	START OF PROJECT - TYPICAL ADVANCE WARNING SIGNING WITH END ROAD WORK AND ROAD WORK NEXT 5 MILES
CTH F / SILVER OAKS LANE	60	-	-	-	1	60	ROAD WORK AHEAD
CTH F / 20TH DRIVE	60	-	-	-	1	60	ROAD WORK AHEAD
CTH F / JANNETTE ORCLE (N)	60	-	-	-	1	60	ROAD WORK AHEAD
CTH F / JANNETTE ORCLE (S)	60	-	-	-	1	60	ROAD WORK AHEAD
CTH F / CREE DRIVE	60	-	-	-	1	60	ROAD WORK AHEAD
CTH F / WOODHAVEN BLVD	60	-	-	-	1	60	ROAD WORK AHEAD
CTH F / 21ST AVENUE	60	-	-	-	1	60	ROAD WORK AHEAD
CTH F / 22ND AVENUE	60	-	-	-	1	60	ROAD WORK AHEAD
CTH F / CREE ROAD	60	-	-	-	1	60	ROAD WORK AHEAD
CTH C / N OF CTH Z	60	-	-	-	5	300	END OF PROJECT - TYPICAL ADVANCE WARNING SIGNING WITH END ROAD WORK AND ROAD WORK NEXT 5 MILES
20TH DRIVE / CTH F	15	5	75	3	45		SEE STANDARD DETAIL FOR BARRICADES AND SIGNS FOR SIDEROAD CLOSURES
20TH DRIVE / N OF CTH F	15	6	90	7	105		WEST APPROACH - SEE STANDARD DETAIL FOR BARRICADES AND SIGNS FOR MAINLINE CLOSURE. DETAILS C & D
20TH DRIVE / CREE AVE	15	6	90	7	105		EAST APPROACH - SEE STANDARD DETAIL FOR BARRICADES AND SIGNS FOR MAINLINE CLOSURES. DETAILS C & D
CTH F	20	-	-	-	12	240	LOW SHOULDER AND UNEVEN LANES SIGNING
CTH F	30	-	-	-	12	360	NO PASSING ZONE SIGNING
CTH F	15	-	-	-	8	120	NO CENTER STRIPE (PULVERIZING SECTION)
TOTALS			255			2,115	

MARKING LINE

STATION	TO	STATION	LOCATION	646.1020	646.4520	649.0120
100+88	-	337+00	CTH F	46,600	30,100	600
TOTAL				46,600	30,100	600

TEMPORARY PORTABLE RUMBLE STRIPS

STATION	TO	STATION	LOCATION	643.0310.S
100+88	-	337+00	CTH F	1
TOTAL				1

NOTE: USE AS REQUIRED BY STANDARD DETAIL "TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION"

LOCATING NO-PASSING ZONES

STATION	TO	STATION	LOCATION	648.0100
100+88	-	337+00	CTH F	4.5
TOTAL				4.5

Addendum No. 01  
ID 6986-01-70  
Revised Sheet 27  
November 30, 2017

ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE STATED



Proposal Schedule of Items

Proposal ID: 20171212022 Project(s): 6986-01-70

Federal ID(s): WISC 2018021

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0128	SPV.0060 Special 01. Grading, Shaping, and Topsoiling for Cross Drain Restoration	6.000 EACH	_____.	_____.
0130	643.0310.S Temporary Portable Rumble Strips	1.000 LS	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.