



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4802 Sheboygan Avenue, Rm 601  
P O Box 7916  
Madison, WI 53707-7916

December 6, 2017

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #27: 8120-07-73**  
**McKinley - Rice Lake**  
**C-03-0002, C-03-0003, C-03-0004**  
**STH 48**  
**Barron County**

### Letting of December 12, 2017

This is Addendum No. 02, which provides for the following:

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.1000	Traffic Control Signs Fixed Message	SF	0	130.00	130.00

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
38	Inserted quantity table for bid item 643.1000

#### **Schedule of Items**

Attached, dated December 7, 2017, are the revised Schedule of Items Page 7.

#### **Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 38

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

TRAFFIC CONTROL SIGNS FIXED MESSAGE

CATEGORY	GROUP #	DETAILS	STAGE	SIZE	MESSAGE	SF	LOCATION
0010	DT4	L2	S1, S2	90"X36"	RICE LAKE USE HWY 48 EAST DETOUR	22.50	STH 48 EB
0010	DT26	L3	S1, S2	48"X12"	RICE LAKE (LA)	4.00	USH 8 EB
0010	DT28	L3	S1, S2	54"X12"	CUMBERLAND (RA)	4.50	USH 8 WB
0010	DT39	L4	S1, S2	90"X36"	CUMBERLAND USE HWY 48 WEST DETOUR	22.50	US 53 SB
0010	DT53	L5	S1, S2	90"X36"	CUMBERLAND EXIT 135	22.50	US 53 SB
0010	DT55	L5	S1, S2	54"X12"	CUMBERLAND (RA)	4.50	US 53S/US 8 EXIT RAMP
0010	DT65	L5	S1, S2	54"X12"	CUMBERLAND (UA)	4.50	US 8 WB
0010	DT67	L5	S1, S2	90"X36"	CUMBERLAND USE HWY 48 WEST DETOUR	22.50	US 53 NB
0010	DT70	L5	S1, S2	90"X36"	CUMBERLAND EXIT 135	22.50	US 53 NB
TOTAL 0010						130.00	

643.1000

GEOTEXTILE TYPE R

CATEGORY	STATION	LOCATION	SY	REMARKS
0010	562+70	B-03-0204 WING 1	7	RI PRAP FLUME
0010	562+70	B-03-0204 WING 2	10	RI PRAP FLUME
TOTAL 0010				17

645.0130

TRAFFIC CONTROL POIS

CATEGORY	LOCATION	DAY
0010	EB STH 48, AT CLOSURE LOCATION ON WEST END OF STRUCTURE C-03-0002 WORK ZONE	15
0010	WB STH 48, AT CLOSURE LOCATION ON EAST END OF STRUCTURE C-03-0004 WORK ZONE	15
TOTAL 0010		30

643.1050

MARKING LINE EPOXY 4-INCH

CATEGORY	STATION TO	STATION	LOCATION	WHI TE	YELLOW
0010	529+67	531+75	C-03-0060	416	416
0010	559+48	566+60	B-03-0204	1424	890
0010	575+25	577+80	C-03-0061	510	64
0010	UNDI STRI BUTED			300	
TOTAL 0010				4020	

646.1020

Addendum No. 02  
 ID 8120-07-73  
 Revised Sheet 38  
 December 7, 2017

CONSTRUCTION STAKING SUBGRADE

CATEGORY	STATION TO	STATION	LOCATION	LF
0010	530+35	531+24	C-03-0060	89
0010	562+46	562+91	B-03-0204	45
0010	563+28	563+74	B-03-0204	46
0010	575+70	576+80	C-03-0061	110
TOTAL 0010				290

650.4500

CONSTRUCTION STAKING BASE

CATEGORY	STATION TO	STATION	LOCATION	LF
0010	530+35	531+24	C-03-0060	89
0010	562+46	562+91	B-03-0204	45
0010	563+28	563+74	B-03-0204	46
0010	575+70	576+80	C-03-0061	110
TOTAL 0010				290

650.5000



Proposal Schedule of Items

Proposal ID: 20171212027 Project(s): 8120-07-73

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0190	643.1000 Traffic Control Signs Fixed Message	130.000 SF	_____.	_____.
	Section: 0001		Total:	_____.
			Total Bid:	_____.

