



Wisconsin Department of Transportation

March 6, 2018

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #12: 1228-16-71, WISC 2018 142
North South Freeway
Green Tree Rd Bridge B-40-0149
IH 043
Milwaukee County

Letting of March 13, 2018

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
4	Traffic
7	Utilities
51	Tieback Anchors, Item SPV.0060.02; Tieback Anchors Performance Tests, Item SPV.0060.03; Tieback Anchors Extended Creep Tests, Item SPV.0060.04.
64	Structure Modification MMSD DC0406, Item SPV.0105.02

Added Special Provisions	
Article No.	Description
69	Vibration Monitoring, Item SPV.0135.01
70	Backfill Controlled Low Strength, Item 209.0200.S
71	Slope Paving Crushed Aggregate Special, Item SPV.0180.02.
72	Removing Electrical Wires from Conduit, Item 204.9090.S
73	Removing Nicolet Ped Tunnel Entrances, Item 204.9105.S
74	Flowable Fill, Item SPV.0035.01

Deleted Special Provisions	
Article No.	Description
44	QMP Base Aggregate Dense 1 1/4-Inch Compaction, Item 371.1000.S

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0170	Removing Fence	LF	490	107	597
204.0210	Removing Manholes	EACH	4	1	5
204.0220	Removing Inlets	EACH	16	1	17
205.0100	Excavation Common	CY	16,082	50	16,132
208.0100	Borrow	CY	3,087	220	3,307
305.0120	Base Aggregate Dense 1-1/4-Inch	TON	9,305	144	9,449
460.6223	HMA Pavement 3MT 58-28 S	TON	2,305	2	2,307
460.6224	HMA Pavement 4MT 58-28 S	TON	1,556	2	1,558
512.0500	Piling Sheet Steel Permanent Delivered	SF	16,620	420	17,040
512.0600	Piling Sheet Steel Permanent Driven	SF	16,620	420	17,040
611.0420	Reconstruct Manhole	EACH	2	2	4
611.0530	Manhole Covers Type J	EACH	3	-1	2
611.0535	Manhole Covers Type J-Special	EACH	7	1	8
611.2004	Manholes 4-FT Diameter	EACH	2	4	6
611.3225	Inlets 2x2.5-FT	EACH	13	-3	10
611.3230	Inlets 2x3-FT	EACH	6	-1	5
611.9900.S	Drain Slotted Vane	EACH	6	-4	2
616.0206	Fence Chain Link 6-FT	LF	940	45	985
616.0700.S	Fence Safety	LF	15	350	365
628.2002	Erosion Mat Class 1 Type A	SY	3,396	620	4,016
628.7005	Inlet Protection Type A	EACH	38	-10	28
630.0120	Seeding Mixture No 20	LBS	268	17	285
690.0250	Sawing Concrete	LF	201	154	355

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
201.0120	Clearing	ID	0	24	24
201.0220	Grubbing	ID	0	24	24
204.0155	Removing Sidewalk	SY	0	700	700
204.0280	Sealing Pipes	EACH	0	3	3
204.9090.S.01	Removing Electrical Wires from Conduit	LF	0	250	250
204.9105.S.01	Removing Nicolet Ped Tunnel Entrances	LS	0	1	1
209.0200.S	Backfill Controlled Low Strength	CY	0	22	22
416.1715	Concrete Pavement Repair SHES	SY	0	33	33
SPV.0035.01	Flowable Fill	CY	0	380	380
SPV.0135.01	Vibration Monitoring	MON	0	7	7
SPV.0180.02	Slope Paving Crushed Aggregate Special	SY	0	770	770

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
371.1000.S	QMP Base Aggregate Dense 1-1/4-Inch Compaction	TON	9,305	-9,305	0
604.0500	Slope Paving Crushed Aggregate	SY	770	-770	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
08	Typical Section: NB 43 inside shoulder width
09	Construction Details: Added note regarding the underdrain inlet cores
10	Construction Details: Added detail for storm pipe crossing NB 43
17	Removals: NB 43 inside shoulder removal limits
19	Removals: NB 43 inside shoulder removal limits
28	Plan Details: NB 43 inside shoulder width, pavement material NB 43 pipe crossing
35	Paving Grades: NB 43 inside shoulder
36	Paving Grades: NB 43 inside shoulder
40	Curb Ramp Details: Fixing elevation error
41	Curb Ramp Details:
48	Erosion Control: Eliminated type A inlet protection in various locations
50	Erosion Control: Eliminated type A inlet protection in various locations
51	Erosion Control: Eliminated type A inlet protection in various locations
54	Erosion Control: Eliminated type A inlet protection in various locations
55	Erosion Control: Eliminated type A inlet protection in various locations
58	Storm Sewer: Various changes the plans and/or profiles
59	Storm Sewer: Various changes the plans and/or profiles
60	Storm Sewer: Various changes the plans and/or profiles
61	Storm Sewer: Various changes the plans and/or profiles
63	Storm Sewer: Various changes the plans and/or profiles
64	Storm Sewer: Various changes the plans and/or profiles
65	Storm Sewer: Various changes the plans and/or profiles
66	Storm Sewer: Various changes the plans and/or profiles
102	Traffic Control: Updated exhibit to reflect wider construction zone in the median shoulder
109	Traffic Control St1A: Traffic configuration shifted east to allow for more workzone near median
112	Traffic Control St1A: Details regarding the abandonment of the pedestrian crossing
114	Traffic Control St1A: Traffic configuration shifted east to allow for more workzone near median
115	Traffic Control St1A: Traffic configuration shifted east to allow for more workzone near median
164	Misc Quantities: Removing sidewalk table added
165	Misc Quantities: Common excavation totals updated
166	Misc Quantities: Base aggregate dense totals updated
167	Misc Quantities: Concrete items added for the pipe crossing IH-43
168	Misc Quantities: Asphalt totals updated for the NB 43 inside shoulder
175	Misc Quantities: Inlet protection type A eliminated at various locations
178	Misc Quantities: Column added for drain slotted vanes
181	Misc Quantities: Vibration monitoring added
183	Misc Quantities: Storm sewer structures, various updates
184	Misc Quantities: Storm sewer structures, various updates
185	Misc Quantities: Storm sewer structures, various updates
186	Misc Quantities: Storm sewer structures, various updates
187	Misc Quantities: Storm sewer pipes, pipe slope updates
355	Structure Plans: Change to epoxy slope paving
357	Structure Plans: Change to epoxy slope paving
384	Structure Plans: Change to epoxy slope paving
408	Earthwork Tables: Update to I-43 NB median shoulder, additional cut
440	Cross Sections – IH43: Update to the I-43 NB median shoulder

441	Cross Sections – IH43: Update to the I-43 NB median shoulder
442	Cross Sections – IH43: Update to the I-43 NB median shoulder
443	Cross Sections – IH43: Update to the I-43 NB median shoulder

Added Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of why sheet was added)
15A	Construction Details: Abandon existing pedestrian culvert crossing
15B	Construction Details: Abandon existing pedestrian culvert crossing
15C	Construction Details: Abandon existing pedestrian culvert crossing
188A	Misc. Quantities: Added quantity tables for the pedestrian crossing abandonment

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1228-16-71

March 6, 2018

Special Provisions

3. Prosecution and Progress.

*Add the following after paragraph one under section titled **Anticipated Schedule**:*

Do not begin work to the pedestrian culvert crossing abandonment prior to a minimum of 2 (two) weeks after construction activities have begun to allow traffic to normalize on Jean Nicolet Road.

*Replace entire section titled **Definitions** with the following:*

Definitions

Lane:

A lane is defined as 12-feet wide unless otherwise shown on the plans.

Short Term Closure:

A roadway closure that is a maximum of 3 calendar days

Peak Travel Periods on Southbound I-43:

- 6:00 AM to 9:00 PM Monday, Tuesday, Wednesday, and Thursday
- 6:00 AM to 12:00 PM Friday
- 7:00 AM to 9:00 PM Saturday
- 7:00 AM to 10:00 PM Sunday

Peak Travel Periods on Northbound I-43:

- 6:00 AM to 10:00 PM Monday, Tuesday, Wednesday, and Thursday
- 6:00 AM to 12:00 PM Friday
- 7:00 AM to 9:00 PM Saturday
- 7:00 AM to 10:00 PM Sunday

Available Lane Closures Northbound I-43:

- 10:00 PM to 6:00 AM (Sunday PM to Monday AM, Monday PM to Tuesday AM, Tuesday PM to Wednesday AM, Wednesday PM to Thursday AM, Thursday PM to Friday AM)
- 12:00 AM to 7:00 AM (Friday Midnight to Saturday AM)
- 9:00 PM to 7:00 AM (Saturday PM to Sunday AM)

Available Lane Closures Southbound I-43:

- 9:00 PM to 6:00 AM (Sunday PM to Monday AM, Monday PM to Tuesday AM, Tuesday PM to Wednesday AM, Wednesday PM to Thursday AM, Thursday PM to Friday AM)
- 12:00 AM to 7:00 AM (Friday Midnight to Saturday AM)
- 9:00 PM to 7:00 AM (Saturday PM to Sunday AM)

Allowable Full Roadway Closure Northbound and Southbound I-43:

- 10:00 PM to 5:00 AM (Sunday PM to Monday AM, Monday PM to Tuesday AM, Tuesday PM to Wednesday AM, Wednesday PM to Thursday AM, Thursday PM to Friday AM)
- 12:00 AM to 7:00 AM (Friday Midnight to Saturday AM, Saturday Midnight to Sunday AM)

Extended Full Roadway Closure Northbound and Southbound I-43:

- 11:00 PM to 9:00 AM (Friday PM to Saturday AM or Saturday PM to Sunday AM)

*Add the following after paragraph two under section titled **Interim Liquidated Damages:***

Complete all work and coordination measures necessary to complete the abandonment of existing pedestrian culvert crossing C-40-020 prior to 12:01 AM May 21, 2018.

If the contractor fails to complete all work and coordination measures necessary to complete the abandonment of existing pedestrian culvert crossing C-40-020 by 12:01 AM May 21st, 2018, the department will assess the contractor \$2,000 in interim liquidated damages for each calendar day that the pedestrian culvert abandonment is not completed. An entire calendar day will be charged for any period of time within a calendar day that the work to complete the pedestrian culvert abandonment is not complete for the remainder of the contract.

4. Traffic.

*Replace entire section titled **F.1 IH 43 Mainline and SB Good Hope Onramp** with the following:*

F.1 IH 43 Mainline and SB Good Hope Onramp

Full freeway closures will be permitted during time frames as discussed within the Procession and Progress as defined within paragraph labeled "Allowable Full Roadway Closure Northbound and Southbound I-43."

- Four nighttime full closures allowed for NB I-43 during Stage 1A for the installation of a storm sewer pipe within the NB I-43 inside shoulder.
- Two nighttime full closures allowed for I-43 during Stage 2A for removal of existing bridge and retaining wall. These closures may include both NB I-43 and SB I-43 during the same nighttime closure.
- Six nighttime full closures allowed for NB I-43 during Stage 2B and/or Stage 3 to set girders, deck forming, deck slab, and sidewalks.
- Six nighttime full closures allowed for SB I-43 during Stage 2B and/or Stage 3 to set girders, deck forming, deck slab, and sidewalks.

Single lane freeway closures will be allowed during all stages during time frames as discussed within the Procession and Progress as defined within paragraph labeled "Available Lane Closures Northbound I-43" and "Available Lane Closures Southbound I-43."

Southbound Good Hope onramp will be fully closed for 90 days as specified within the Prosecution and Progress. Additional closures outside of this window will not be allowed.

Extended full freeway closures will be permitted on a limited basis during time frames as discussed within the Procession and Progress as defined within paragraph labeled "Extended Full Roadway Closure Northbound and Southbound I-43."

- One extended full closure allowed during Stage 1A to install storm sewer crossing NB I-43 travel lanes.
- One extended full closures allowed during Stage 2A to remove the existing Green Tree bridge and SB IH-43 retaining wall. Closure may include both NB and SB directions of I-43.

7. Utilities

Replace the fifth bullet item under section titled **WE Energies – Electric** with the following:

- An existing overhead electric line beginning at a pole at Station 35GT+38, 47'LT and running easterly to a pole at Station 37GT+02, 44'LT where it turns and runs northeasterly to a pole at Station 37GT+82, 102'LT. From there it turns east-southeasterly, crossing IH 43 at Station 1132+66, to a pole at Station 39GT+93, 68'LT and continuing to a pole at Station 41GT+28, 47' LT and continuing to a pole at Station 41GT+50, 42'LT. From there it turns and runs easterly to a pole at Station 42GT+19, 43'LT and continuing to a pole at Station 42GT+63, 41'LT and continuing to beyond the project limits. This line will remain in place without adjustment. When driving sheeting for retaining wall R-40-641 near the pole at Station 39GT+93, 68'LT, We Energies will de-energize the overhead line from this pole running westerly to Station 37GT+82, 102'LT and easterly to Station 41GT+29, 46'LT only for a maximum period of 2 weeks. We Energies reserves the right to re-energize this overhead line in case of emergency. Contact Ken Franecki (414-944-5531 office / 262-939-1039 cell) of We Energies 7 days in advance to coordinate the outages for this overhead line.

44. DELETED.

51. Tieback Anchors, Item SPV.0060.02; Tieback Anchors Performance Tests, Item SPV.0060.03; Tieback Anchors Extended Creep Tests, Item SPV.0060.04.

Replace A.1(3) with the following:

- (3) The contractor has the option to provide an alternate permanent earth anchor system with the approval of the department. The contractor shall then be responsible for selecting the permanent earth anchor type, method of installation, and for determining the bond length and anchor diameter that shall develop the factored design loads indicated on the plans. The analysis, design, construction and testing of the post tiebacks shall conform to the AASHTO LRFD Bridge Design Specifications Seventh Edition with 2015 and 2016 Interims and the AASHTO LRFD Bridge Construction Specifications 4th Edition, 2017.

Replace section C.3.2(4) with the following:

(4) Performance Test Schedule

<u>Load</u>
AL
0.25 FDL*
AL
0.25 FDL
0.50 FDL*
AL
0.25 FDL
0.50 FDL
0.75 FDL*
AL
0.25 FDL
0.50 FDL
0.75 FDL
1.00 FDL*
AL

0.25 FDL
0.50 FDL
0.75 FDL
1.00 FDL
1.20 FDL*
AL
0.25 FDL
0.50 FDL
0.75 FDL
1.00 FDL
1.20 FDL
1.33 FDL* (Max. test load)
Reduce to lock-off load – 0.60 FDL

Where, AL = Alignment Load
 FDL = Factored Design Load for Tieback
 * = Graph required

Replace section C.3.3(3) with the following:

(3) Proof Test Schedule

<u>Load</u>
AL
0.25 FDL
0.50 FDL
0.75 FDL
1.00 FDL
1.20 FDL
1.33 FDL (Max. test load)
Reduce to lock-off load – 0.60 FDL

Where, AL = Alignment Load
 FDL = Factored Design Load for Tieback

Replace section C.3.4(4) with the following:

(4) Extended Creep Test Schedule

<u>Load</u>	<u>Observation Period (min.)</u>
AL	
0.25 FDL	10
0.50 FDL	30
0.75 FDL	30
1.00 FDL	45
1.20 FDL	60
1.33 FDL	300

- Where, AL = Alignment Load

FDL = Factored Design Load for Tieback

- Reduce to lock-off load – 0.60 FDL

64. Structure Modification MMSD DC0406, Item SPV.0105.02

*Replace paragraph two under section titled **B Materials** with the following:*

Furnish grade A, A-FA, A-S, A-T, A-IS, A-IP, or A-IT concrete conforming to 501 as modified in 716. Provide QMP for class III ancillary concrete as specified in 716. The concrete for shall have a 28-day compressive strength of at least 4,500 psi.

69. Vibration Monitoring, Item SPV. 0135.01.

A Description

This special provision describes developing a vibration monitoring plan, deploying seismographs for continuous monitoring and recording, documentation, and reporting.

B (Vacant)

C Construction

C.1 General

Vibration Monitoring establishes vibration recordings at the closest affected locations beginning the first day of operations for various vibration inducing activities identified herein and lasting the entire duration of said activities unless monitored readings are sufficiently below nuisance limits in Figure 1 and engineer determines that continued monitoring will be at the contractor's discretion without further payment.

C.2 Equipment

Utilize a seismograph meeting the requirements of Wisconsin Department of Safety and Professional Services SPS307.43. Utilize monitoring equipment with an instantaneous alert notification system that consists of a text message or an e-mail alert message automatically sent anytime the nuisance limits in Figure 1 are exceeded.

C.3 Preconstruction Survey

The engineer will conduct preconstruction surveys of structures that may be potentially affected by vibration prior to any work. The engineer will visually inspect and record all existing defects in the structures before construction. Photographs or video may be used to assist in documentation.

The contractor will conduct and document pre-construction surveys of any additional nearby buildings or structures not identified by the engineer at no additional cost. Submit a certified letter to the affected property owners, asking to make an appointment to view their building. Do the same for the post-construction inspection. The letter will indicate that if the property owner won't allow for inspections to the property, pre and post-construction, they have no right to file a claim after the project is complete. Provide results to engineer prior to construction. Any damage resulting from excessive vibration-causing operations or claims of damage during construction is the responsibility of the contractor to resolve.

C.4 Monitoring Plan

Submit a monitoring plan that includes the following:

- Location of each vibration-inducing activity to be monitored.
- Locations at which the approved seismographs will be placed.
- Anticipated vibration levels at the closest building(s) or other sensitive facility during the various activities.
- Anticipated monitoring duration for each monitoring location.
- Maximum allowable vibration limits.
- Mitigation plan to reduce potentially excessive vibration levels to acceptable limits.

Obtain the engineer's acceptance seven calendar days before any vibration-inducing activity for the project.

C.5 Monitoring and Recording

Monitor the following operations:

- Bridge and sign bridge pile driving or bridge demolition.
- Sheet pile installation and removal.
- MSE wall compaction.
- Asphalt compaction.
- Pavement breaking.
- All compaction activities utilizing large vibratory rollers.
- Any other activities that may cause vibration damage to adjacent buildings, structures, or utilities.
- Other operations as directed by the Engineer.

Ensure that a qualified person operates and continuously monitors the vibration monitoring equipment. If any vibration levels exceed the nuisance levels shown, immediately halt the vibration-inducing work, and notify the engineer.

Monitor between the construction vibration source and the closest structure or other sensitive facility subject to vibration damage, and as close as practical to the subject structure or facility. Monitor vibration levels in accordance to Figure 1 and SPS 307.43.

Compare the measured peak particle velocity and frequency data to the nuisance limits specified in Figure 1. Record peak particle velocity and frequency in three mutually perpendicular directions.




Figure 1: Amplitude of Vertical Vibrations

C.6 Reporting

Furnish a weekly bound report of data recorded at each location to the engineer by 4:00 PM CST every Friday. Additionally, provide a separate daily report documenting any work that was halted prior to the next vibration-causing workday. Include the following in both reports:

- Date vibration monitoring operations began for each location with an associated compilation of total days currently monitored at each site.
- Identification of vibration inducing activities monitored each day at each location.
- Serial number of vibration monitoring instrument used and record of latest calibration.
- Description of contractor's equipment.
- Name of qualified observer and interpreter.
- Distance and direction of recording station from vibration source.
- Surficial material type at recording station.
- Principal frequency and particle velocity in each component direction.
- Copy of records of seismograph readings, dated and signed by the person qualified to perform vibration monitoring.
- Contractor documentation of any operational changes necessary to reduce vibration levels below nuisance levels.

D Measurement

The department will measure Vibration Monitoring by months, or partial months where applicable, for each seismograph monitoring site acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV. 0135.01	Vibration Monitoring	MON

Payment of the item Vibration Monitoring is full compensation for providing, setting up and removal of recording unit, an approved vibration monitoring plan, continuous monitoring and recording vibrations, and reporting. No payment for Vibration Monitoring will be paid for without agreement on recommended locations.

70. Backfill Controlled Low Strength, Item 209.0200.S

A Description

This special provision describes furnishing and placing a controlled low strength material designed for use as backfill in trenches for culverts, sewers, utilities, or similar structures, as backfill behind bridges abutments, or as fill for the abandonment of culverts, pipes, or tanks.

B Materials

Provide controlled low strength backfill that consists of a designed cementitious mixture of natural or processed materials. Allowable materials include natural sand, natural gravel, produced sand, foundry sand, produced gravel, fly ash, Portland cement, and other broken or fragmented mineral materials. The designed mixture shall be self-leveling and shall be free of shrinkage after hardening. Design the mixture to reach a state of hardening such that it can support foot traffic in no more than 24 hours. Provide a mixture that also meets the following requirements.

<u>TEST</u>	<u>METHOD</u>	<u>VALUE</u>
Flow (inch)	ASTM D-6103	9 min
Compressive Strength (psi)	ASTM D-6024	20-40 @ 14 days 40-80 @ 28 days 80-120 @ 90 days

Chemical admixtures to control air content and setting time are allowable. Ten days before placement, furnish the engineer with a design mix detailing all components and their proportions in the mix. Also, provide documentation from the supplier of the industrial byproducts that the foundry sand and fly ash used in the mixture meet the requirements for Industrial Byproducts Categories 1, 2, 3, or 4 in NR 538 of the Wisconsin Administrative Code for use as a confined geotechnical fill.

C Construction

Place controlled low strength backfill at the locations and to the lines and grades as shown on the plan. Proportion and mix materials to produce a product of consistent texture and flow characteristics. The engineer may reject any materials exhibiting a substantial change in properties, appearance, or composition.

If the official Weather Bureau forecast for the construction site predicts temperatures at or below freezing within the next 24 hours after placement of controlled low strength backfill, protect the placed materials from freezing during that time period. If the temperature is not forecast to rise above

40° F for 72 hours after placement, the engineer may require protection from freezing for up to 72 hours.

No controlled low strength backfill shall be allowed to enter any stream, lake, or sewer system. The contractor shall be responsible for any clean up or remediation costs resulting from such occurrences.

D Measurement

The department will measure Backfill Controlled Low Strength in volume by the cubic yard of material placed and accepted. Such volume shall be computed from actual measurements of the dimensions of the area to be backfilled. In irregular or inaccessible areas, the engineer may allow volume to be determined by other appropriate methods.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
209.0200.S	Backfill Controlled Low Strength	CY

Payment is full compensation for designing the mix; supplying all materials; preparing the proportioned mix; hauling it to the construction site; placing the material; and protecting it from freezing.

stp-209-010 (20090901)

71. Slope Paving Crushed Aggregate Special, Item SPV.0180.02.

A Description

This special provision describes furnishing, crushing and placing aggregate for slope paving and applying an epoxy resin binder with the aggregate, as the plans show, conforming to the applicable provisions of standard spec 604, and as modified in this special provision.

B Materials

B.1 General

Use a low modulus, medium-viscosity, two-component epoxy resin binder.

Furnish evidence, to the satisfaction of the engineer, that the proposed product has been successfully used in a similar application.

Epoxy resin binder shall be clear to light amber when fully cured.

Use Wisconsin crushed aggregate limestone with 100 percent fractured faces and hues of tan, amber and gray conforming to the following nominal requirements:

SIEVE SIZE	PERCENT PASSING (by weight)
4-Inch	100
1-Inch	0-25

B.2 Minimum Requirements

Furnish epoxy resin binder material conforming to ASTM C-881 and AASHTO M-235 specifications and the following requirements:

Total water absorption, ASTM D-570

- 7 day, 1.3% (2 hour boil)

- 14 day, 0.232% (24 hour immersion)
- Viscosity: 2,500 cps

C. Construction

C.1 Base Preparation

A week prior to placing crushed aggregate, strip all vegetation and humus-bearing soil. Bring the grade to the required lines, elevations, and slopes shown on the plans. Remove twigs, cobbles, foreign material, and clods that cannot be broken down. Install and securely anchor weed barrier fabric in accordance with standard spec 632.

C.2 Application

Apply the epoxy resin binder material uniformly over the surface of the paving at a rate just sufficient to ensure penetration and binding of the particles in the upper 2 inches of the entire aggregate blanket conforming to the manufacturer's recommended rate and procedures. Use a two part sprayer with mixing completed at the nozzle to apply the binder. Avoid excessive application of epoxy resin binder and prevent material run-off. Protect the surface of adjacent structures, barriers, and pavement to prevent splattering or discoloration by epoxy resin binder, and within a timeframe acceptable to the engineer, remove all material accumulations at the foot of the slope paving.

Apply and mix epoxy resin binder under dry conditions only. Do not apply if rain is expected within 8 hours following epoxy resin application to crushed aggregate or as recommended by the manufacturer and approved by the engineer.

Ensure air and surface temperature is in the range between 50 and 90 F during, and for 24 hours following, application and mixing of the epoxy resin binder or as recommended by the manufacturer and approved by the engineer.

Protect installed crushed aggregate with epoxy resin binder from excessive dust exposure for the first 4 hours of curing.

C.3 Test Section

Before placing slope paving, prepare a test section utilizing the proposed aggregate and epoxy resin binder so the engineer will be able to assess the adequacy of the product and the application and mixing methods to yield the desired results. Test section to be 3-feet x 3-feet and a minimum of 4-inches thick. Notify the engineer at least 24 hours before preparing the test section to allow them time to arrange for witnessing the epoxy resin binder application and mixing with the aggregate. Cure test section according to product manufacturer's requirements before the engineer will accept the product for use on the final structures.

If the test section is not accepted, prepare another test section and repeat the process, using either a different aggregate or epoxy resin binder. Repeat this procedure until the engineer accepts the test section. Use the same aggregate and epoxy resin binder means and methods when installing the product under each structure that were used in preparing the accepted test section.

D Measurement

The department will measure Slope Paving Crushed Aggregate Special by the square yard in place acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.02	Slope Paving Crushed Aggregate Special	SY

Payment is full compensation for stripping and disposing of humus-bearing soil, for providing and installing weed barrier fabric, providing crushed aggregate; for providing the epoxy resin binder to the

aggregate; for preparing the subsurface; for cleaning all splatter of epoxy resin binder to adjacent structures, barriers, and pavement; and for making and disposing of the test section

72. Removing Electrical Wires from Conduit, Item 204.9090.S.01.

A Description

This special provision describes removing electrical wires from existing conduits and disposing of the resulting material as the plans show, conforming to standard spec 204, and as follows. The existing conduit shall remain in place. The electrical connection is between the Nicolet High School Storage Facility and the tunnel entrance on the east side. On the north side of the structure the wiring is fed into it. Not required to remove the wiring in the tunnel.

B (Vacant)

C Construction

No removal work will be permitted without approval from the Engineer.

All wires shall be removed from the existing embedded or underground conduits as the plans show and as the Engineer directs. Any necessary splices or disconnections shall be done as part of this pay item. Removed wires become the property of the contractor. Properly dispose of all material off the project site.

D Measurement

The Department will measure Removing Electrical Wires from Conduit by linear foot acceptably completed. The vertical length and wire slack shall be incidental.

E Payment

Add the following to standard spec 204.5:

ITEM NUMBER	DESCRIPTION	UNIT
204.9090.S.01	Removing Electrical Wires from Conduit	LF

SER-204.10 (20170405)

73. Removing Nicolet Ped Tunnel Entrances, Item 204.9105.S.01.

A Description

This special provision describes removing and disposing of the resulting material from the west and east entrances to the Nicolet Ped Tunnel conforming to standard spec 204, as shown on the plans, and as follows.

B (Vacant)

C Construction

Upon removing of the existing access control fence at the west entrance immediately place Safety Fence from the access control fence to the guardrail on either side of the West entrance, as shown on the plans, to establish and maintain the Eruv connection. Keep Safety Fence in place for the duration of construction until the new chain link fence is installed. Refer to 'Notice to Contractor, Maintenance of Eruv Boundary' article.

Work on the west entrance will only allowed during weekdays from 7:30 am to 2:00 pm.

Seal the floor drain pipes in the east and west end of the tunnel floor to prevent flowable fill from flowing into the storm sewer.

Contact the Nicolet High School facilities manager Brian Reiels 414-313-7546 for access to the Nicolet High School storage building to remove the circuit breaker to de-energize the tunnel lighting. Completely remove the electrical wire from the tunnel to the storage building. Conduit can be abandoned in place.

Contact the City of Glendale to turn off water to the fire hydrant near the east entrance during construction.

Saw cut the floor, sides and ceiling of the interior of the tunnel and the sides and top of the exterior of the tunnel as shown on the plans. Completely remove the entrances to the limits shown and dispose of all waste off the project.

Drive sheet piling at both entrances to the depth shown and seal the sheet piling to the tunnel to prevent flowable fill from escaping during filling operation.

Completely fill tunnel with flowable fill sealing the filling opening upon completion.

Contractor is responsible to obtain all permits and to contact and locate all Utilities.

D Measurement

The department will measure Removing Nicolet Ped Tunnel Entrances as a single lump sum unit acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
204.9105.S.01	Removing Nicolet Ped Tunnel Entrances	LS

Payment for Removing Nicolet Ped Tunnel Entrances is full compensation for breaking down, removing, closing and sealing the tunnel, for removal and de-energizing the electrical service, for utility coordination and locating, for all permits, and for hauling and disposing of material. Safety fence, removing electrical wires from conduit, sealing pipes, sheet piling, sawing concrete, and flowable fill will be measured and paid for under other contract bid items.

74. Flowable Fill, Item SPV.0035.01

A Description

This special provision furnishing and installing a cementitious slurry fill as follows.

B Materials

Provide flowable fill meeting the following specifications: 200 pounds cement, 3300 pounds sand, and 310 pounds water. Provide cement meeting the requirements of standard spec 501.2.1 for Type 1 Portland Cement, sand meeting the requirements of standard spec 501.2.5.3, and water meeting the requirements of standard spec 501.2.4.

C Construction

Completely fill the Nicolet Ped Tunnel with flowable fill.

D Measurement

The department will measure Flowable Fill by the cubic yard, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
-------------	-------------	------

SPV.0035.01

Flowable Fill

CY

Payment is full compensation for flowable fill material delivery and placing material.

Schedule of Items

Attached, dated March 6, 2018, are the revised Schedule of Items Pages 1 – 16.


Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 08, 09, 10, 17, 19, 28, 35, 36, 40, 41, 48, 50, 51, 54, 55, 58, 59, 60, 61, 63, 64, 65, 66, 102, 109, 112, 114, 115, 164, 165, 166, 167, 168, 175, 178, 181, 183, 184, 185, 186, 187, 355, 357, 384, 408, 440, 441, 442, 443

Added: 15A, 15B, 15C, and 188A.

END OF ADDENDUM




Addendum No. 01
 ID 1228-16-71
 Revised Sheet 8
 March 6, 2018

SHEET NOTES:
 R/L - POINT REFERRED TO ON PROFILE AND PIVOT POINT FOR SUPER ELEVATION
 FOR INFORMATION REGARDING RESTORATION REFER TO THE EROSION CONTROL PLANS AND FINISHING ITEMS WITHIN THE QUANTITY TABLES

*FOOTING EXTENDS 4 INCHES AS NOTED IN STANDARD DETAIL DRAWING. FOOTING INCIDENTAL TO PAYMENT OF CONCRETE BARRIER
 **MATCH ADJACENT CROSS SLOPE


Addendum No. 01
ID 1228-16-71
Revised Sheet 9
March 6, 2018



TOP VIEW

UNDERDRAIN DETAIL NOTES:


- (1) BOTTOM OF PIPE SHALL BE PLACED AT THE BOTTOM OF COARSE AGGREGATE NO. 1 MATERIAL.
- (2) BOTTOM OF COARSE AGGREGATE NO. 1 MATERIAL IS NOT NECESSARILY THE BOTTOM OF THE SLEET CRUSHED MATERIAL.
- (3) ELEVATIONS TO BE DETERMINED BY ENGINEER IN FIELD.
- (4) ALL UNDERDRAIN CORES INTO EXISTING OR PROPOSED PAVEMENT SHALL BE INCIDENTAL TO THE UNDERDRAIN TAY ITEM.



SECTION C-C


SECTION D-D

CROSS-SECTION VIEW
TYPICAL INLET CONFIGURATION
WITH UNDERDRAIN CORED
INTO WALL WITH NO PIPE



SECTION A-A

CROSS-SECTION VIEW
TYPICAL INLET CONFIGURATION
WITH UNDERDRAIN CORED
INTO WALL WITH CROSSPIPE ONLY
FOUND AT LOW POINTS
WITHOUT FLANKING INLETS



SECTION B-B

CROSS-SECTION VIEW
TYPICAL INLET IN SUMP
CONDITION WITH UNDERDRAIN
CORED INTO WALL WITH PIPE

SECTION E-E NOTES:

- (1) CORE HOLES SHALL PROVIDE FOR A MINIMUM OF 2" OF CONCRETE BETWEEN THE CUTOUT FOR A CONCRETE PIPE AND THE EDGE OF THE CORE HOLE.
- (2) CORE HOLES MAY HAVE 45° CLEARANCE FROM THE INSIDE WALLS OF A STRUCTURE.

SECTION A-A NOTES:

- (1) BOTTOM OF CORE PLACED A MINIMUM OF 6" ABOVE THE INVERT OF THE CROSS PIPE.
- (2) TOP OF CORE HOLES WILL BE A MINIMUM OF 6" ABOVE THE INVERT OF THE INLET STRUCTURES (BOTTOM OF RINGS).
- (3) DRAIN TIES SHALL NOT BE ALLOWED IN THE RING OF THE STRUCTURE OF INLETS

PIPE UNDERDRAIN DETAIL
NOT TO SCALE

PROJECT NO: 1228-16-71

HWY: IH-43


COUNTY: MILWAUKEE

CONSTRUCTION DETAILS


PLOT BY: ANDREW ROSEMER

PLOT SCALE: #*****

SHEET 09




ELEVATION VIEW



SECTION A-A

CURB AND GUTTER AT INLETS


Addendum No. 01
ID 1228-16-71
Revised Sheet 10
March 6, 2018






TRENCH BACKFILL DETAIL FOR NORMAL DEPTH PIPE CULVERTS AND STORM SEWER PIPE INSTALLATIONS

(FOR PIPS THAT ARE 2 FEET OR GREATER FROM THE SUBGRADE)



NOTES:
(1) NATIVE BACKFILL SHALL BE FREE OF LARGE LUMPS, CLDS, ORGANICS, OR ROCK.



TRENCH BACKFILL DETAIL FOR STORM SEWER PIPE CROSSING IH-43



Addendum No. 01
 ID 1228-16-71
 Added Sheet 15A
 March 6, 2018




Addendum No. 01
 ID 1228-16-71
 Added Sheet 15B
 March 6, 2018

REMOVE EVERYTHING LEFT (WEST) OF THE SAW CUT


REMOVE EVERYTHING RIGHT (EAST) OF THE SAW CUT

NOTE: OVERLAP SHEET PILE 1' ON BOTH SIDES OF THE TUNNEL OPENING

Addendum No. 01
 ID 1228-16-71
 Added Sheet 15C
 March 6, 2018



PROJECT NO: 1228-16-71	COUNTY: MILWAUKEE	ABANDON PEDESTRIAN TUNNEL	SHEET 15C	E
FILE NAME: N:\PDS\32012281601\PHH\BTS\NICOLET PED TUNNEL (2)DWG	Hwy: IH43	FLOT BY: DICMAN, JAKE J	PLOT NAME:	WIS007\CADD\5 SHEET 42
LAYOUT NAME: Pdn 1 IN 20 FT	FLot DATE: 2/28/2018 10:29 AM	PLOT SCALE: Custom		



Addendum No. 01
 ID 1228-16-71
 Revised Sheet 17
 March 6, 2018

PROJECT NO: 1228-16-71 HWY: IH-43 COUNTY: MILWAUKEE REMOVAL PLAN SHEET 17 E


FILE NAME: F:\DESIGN\PLANS\122801\SHREESPAVN\122801\MILWAUKEE\GREEN TREE\02101_BMDWG PLOT DATE: 2/27/2018 8:30 AM PLOT BY: ANDREW ROSEMBER PLOT NAME: #***** PLOTS SCALE: WISDOT/CADIS SHEET 02

LEGEND

- EXISTING TREE TO REMAIN. PROTECT TREE WITH SAFETY FENCE.
- EXISTING TREE TO REMAIN. PROTECT TREE WITH SAFETY FENCE. CONTRACTOR TO GRADE AROUND BASE OF TREE AND AVOID PLACING FILL DIRECTLY AT THE BASE.
- SLOPE INTERCEPTS
- REMOVE FENCE
- REMOVE STORM SEWER
- REMOVE STORM SEWER NILET
- REMOVE STORM SEWER MANHOLE
- CLEAR AND GRUB
- REMOVE PAVEMENT
- REMOVE GUARDRAIL / EAT
- REMOVE CURB AND GUTTER
- REMOVE CONCRETE BARRIER
- SAWING PAVEMENT

NOTES:

- ALL EXISTING ASPHALT REMOVAL WILL BE PAID FOR AS COMMON EXCAVATION



NOTES:
 1. ALL EXISTING ASPHALT REMOVAL WILL BE PAID FOR AS COMMON EXCAVATION


- LEGEND**
- x—x— REMOVING FENCE
 - SS— REMOVING STORM SEWER
 - ⊕ REMOVING STORM SEWER INLET
 - ⊙ REMOVING STORM SEWER MANHOLE
 - CLEAR AND CURB
 - ▨ REMOVING PAVEMENT
 - ▧ REMOVING GUARDRAIL / BAY
 - ▩ REMOVING CURB AND GUTTER
 - ▬ REMOVING CONCRETE BARRIER
 - ▬ XX XX XX XX XX REMOVING SAWING PAVEMENT

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 19
 March 6, 2018


ASPHALT PAID FOR AS COMMON EXCAVATION



Addendum No. 01
 ID 1228-16-71
 Revised Sheet 28
 March 6, 2018




PROJECT NO: 1228-16-71
HWY: IH-43
COUNTY: MILWAUKEE
PLAN DETAILS:
DATE: 2/27/2018 7:31 PM
DESIGNER: ANDREW ROSEMBER
SCALE: 1"=40'-0"
SHEET: 28
DATE: 1/18/2018
FILE NAME: F:\DISIGN\PLANS\1228-16-71\SHRETS\PLAN\1228-16-71_MILWAUKEE_GREEN_TREE\021.S28_P0.DWG
PLANT NAME: 021206.plt
WSPRO/CADIS SHEET #:




Addendum No. 01
 ID 1228-16-71
 Revised Sheet 35
 March 6, 2018



Addendum No. 01
ID 1228-16-71
Revised Sheet 36
March 6, 2018




PROJECT NO: 1228-16-71	COUNTY: MILWAUKEE	SHEET 36	E
HWY: IH-43	PAVING GRADES	1 IN=40 FT	WISDOT/CADIS SHEET 42
FILE NAME: F:\DISIGN\PLANS\122801\122801\122801\MILWAUKEE\GREEN TREE\02190_PC.DWG	PLOT BY: ANDREW ROSEMBER	PLOT NAME:	
LAYOUT NAME: 021308pg	PLOT DATE: 2/27/08 10:17 PM		




34CT

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 40
 March 6, 2018




ELM TREE ROAD



Addendum No. 01
 ID 1228-16-71
 Revised Sheet 41
 March 6, 2018

PROJECT NO: 1228-16-71	COUNTY: MILWAUKEE	SHEET: 41	E
HWY: IH-43	FLOTBY: ANDREW ROSEMEER	1 IN=10 FT	WISDOT/CADDIS SHEET 42
FILENAME: F:\DESIGN\PLANS\12280401\SHREESPAN\12280401_MILWAUKEE_GREEN_TREE\01_CRD.DWG	FLOT DATE: 2/27/2018 10:21 PM	1 IN=10 FT	
LAYOUT NAME: 021.02.dwg			




Addendum No. 01
 ID 1228-16-71
 Revised Sheet 48
 March 6, 2018

- NOTES**
- 1) EROSION CONTROL FEATURES AS SHOWN ON THE PLANS ARE SUGGESTED LOCATIONS. EXACT LOCATIONS WILL BE DETERMINED BY THE ENGINEER IN THE FIELD.
 - 2) AREAS BETWEEN THE BACK OF CURB AND SLOPE INTERCEPTS REQUIRE TOPSOIL (OR SALVAGED TOPSOIL), FERTILIZER, SEED, AND EROSION MAT OR MULCH.
 - 3) ALL AREAS ARE TO BE RESTORED WITH DOT SEEDING MIXTURE NO. 20. IF A DISTURBED LOCATION WILL NOT BE PERMANENTLY SEEDING AND RESTORED WITHIN 14 CALENDAR DAYS, THE CONTRACTOR SHALL USE TEMPORARY SEED.
 - 4) WHEN INLET PROTECTION TYPE A, TYPE B, C, OR D ARE INDICATED AT THE SAME LOCATION, USE TYPE A PRIOR TO THE PLACEMENT OF CURB AND CUTTER AND USE TYPE B, C, OR D AFTER THE INLET CASTINGS ARE IN PLACE.

LEGEND

	SILT FENCE		INLET PROTECTION FROM PREVIOUS STAGE
	EROSION MAT CLASS I TYPE A		TEMPORARY DITCH CHECKS
	EROSION MAT CLASS II TYPE B		SURFACE WATER FLOW ARROW
	EROSION MAT URBAN CLASS I TYPE A		SLOPE INTERCEPT
	INLET PROTECTION TYPE A		SILT FENCE RELIEF
	INLET PROTECTION TYPE D		SILT FENCE FROM PREVIOUS STAGE

Addendum No. 01
ID 1228-16-71
Revised Sheet 50
March 6, 2018



NOTES

- 1) EROSION CONTROL FEATURES AS SHOWN ON THE PLANS ON THE PLANS ARE SUGGESTED LOCATIONS - EXACT LOCATIONS WILL BE DETERMINED BY THE ENGINEER IN THE FIELD.
- 2) AREAS BETWEEN THE BACK OF CURB AND SLOPE INTERCEPTS REQUIRE TOPSOIL (OR SALVAGED TOPSOIL), FERTILIZER, SEED, AND EROSION MAT OR MULCH.
- 3) ALL AREAS ARE TO BE RESTORED WITH DOT SEEDING MIXTURE NO. 20. IF A DISTURBED LOCATION WILL NOT BE PERMANENTLY SEEDING AND RESTORED WITHIN 14 CALENDAR DAYS, THE CONTRACTOR SHALL USE TEMPORARY SEED.
- 4) WHEN INLET PROTECTION TYPE A & TYPE B, C OR D ARE INDICATED AT THE SAME LOCATION, USE TYPE A PRIOR TO THE PLACEMENT OF CURB AND GUTTER AND USE TYPE B, C OR D AFTER THE INLET CASTINGS ARE IN PLACE.

LEGEND

- | | | | | | |
|--|--------------------------------------|--|----------------------------------|--|--------------------------------|
| | SILT FENCE | | EROSION MAT CLASS I TYPE A | | INLET PROTECTION TYPE A |
| | EROSION MAT CLASS II TYPE B | | EROSION MAT URBAN CLASS I TYPE A | | INLET PROTECTION TYPE B |
| | SLOPE INTERCEPT | | SILT FENCE RELIEF | | SILT FENCE FROM PREVIOUS STAGE |
| | INLET PROTECTION FROM PREVIOUS STAGE | | TEMPORARY DITCH CHECKS | | SURFACE WATER FLOW ARROW |
| | SFR | | | | |

PROJECT NO: 1228-16-71

HWY: IH-43

COUNTY: MILWAUKEE

PLOT DATE: 2/27/2018 6:56 AM

EROSION CONTROL - STAGE 2A

PLOT BY: ANDREW ROSEMBERG

PLOT SCALE: 1 IN=40 FT

SHEET 50


E

WISDOT/CADDIS SHEET 42

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 51
 March 6, 2018

NOTES


- 1) EROSION CONTROL FEATURES AS SHOWN ON THE PLANS ARE SUGGESTED LOCATIONS. EXACT LOCATIONS WILL BE DETERMINED BY THE ENGINEER IN THE FIELD.
- 2) AREAS BETWEEN THE BACK OF CURB AND SLOPE INTERCEPTS REQUIRE MULCH (OR SALVAGED TOPSOIL), FERTILIZER, SEED, AND EROSION MAT OR MATS.
- 3) ALL AREAS ARE TO BE RESTORED WITH DOT SHEDDING MIXTURE NO. 20. IF A DISTURBED LOCATION WILL NOT BE PERMANENTLY SEEDING AND RESTORED WITHIN 14 CALENDAR DAYS, THE CONTRACTOR SHALL USE TEMPORARY SEED.
- 4) WHEN INLET PROTECTION TYPE A & TYPE B, C, OR D ARE INDICATED AT THE SAME LOCATION, USE TYPE A PRIOR TO THE PLACEMENT OF CURB AND GUTTER AND USE TYPE B, C, OR D AFTER THE INLET CASTINGS ARE IN PLACE.



LEGEND

	SILT FENCE		INLET PROTECTION FROM PREVIOUS STAGE
	EROSION MAT CLASS I TYPE A		TEMPORARY DITCH CHECKS
	EROSION MAT CLASS I TYPE B		SURFACE WATER FLOW ARROW
	EROSION MAT URBAN CLASS I TYPE A		SLOPE INTERCEPT
	INLET PROTECTION TYPE A		SILT FENCE RELIEF
	INLET PROTECTION TYPE D		SILT FENCE FROM PREVIOUS STAGE

Addendum No. 01
ID 1228-16-71
Revised Sheet 54
March 6, 2018



- NOTES**
- 1) EROSION CONTROL FEATURES AS SHOWN ON THE PLANS ARE SUGGESTED LOCATIONS. EXACT LOCATIONS WILL BE DETERMINED BY THE ENGINEER IN THE FIELD.
 - 2) AREAS BETWEEN THE BACK OF CURB AND SLOPE INTERCEPTS REQUIRE TOPSOIL (OR SAVAGED TOPSOIL), FERTILIZER, SEED, AND EROSION MAT OR MULCH.
 - 3) RESTORATION AREAS BETWEEN THE SIDEWALK AND BACK OF CURB SHALL BE SEEDING WITH DOT SEEDING MIXTURE NO. 40. AREAS BETWEEN THE BACK OF SIDEWALK AND SLOPE INTERCEPTS SHALL BE SEEDING WITH DOT SEEDING MIXTURE NO. 10.
 - 4) WHEN INLET PROTECTION TYPE A & TYPE B, C OR D ARE INDICATED AT THE SAME LOCATION, USE TYPE A PRIOR TO THE PLACEMENT OF CURB AND CUTTER AND USE TYPE B, C, OR D AFTER THE INLET CASTINGS ARE IN PLACE.

LEGEND


	SILT FENCE		INLET PROTECTION TYPE A
	EROSION MAT CLASS I TYPE A		INLET PROTECTION TYPE B
	EROSION MAT CLASS II TYPE B		INLET PROTECTION TYPE C
	EROSION MAT URBAN CLASS I TYPE A		INLET PROTECTION TYPE D
	SLOPE INTERCEPT		SILT FENCE RELIEF
	SILT FENCE RELIEF		SILT FENCE FROM PREVIOUS STAGE
	TEMPORARY DITCH CHECKS		SURFACE WATER FLOW ARROW
	INLET PROTECTION FROM PREVIOUS STAGE		

Addendum No. 01
ID 1228-16-71
Revised Sheet 55
March 6, 2018



NOTES

- 1) EROSION CONTROL FEATURES AS SHOWN ON THE PLANS ARE SUGGESTED LOCATIONS. EXACT LOCATIONS WILL BE DETERMINED BY THE ENGINEER IN THE FIELD.
- 2) AREAS BETWEEN THE BACK OF CURB AND SLOPE INTERCEPTS REQUIRE TOPSOIL (OR SAUVAGED TOPSOIL), FERTILIZER, SEED, AND EROSION MAT OR MULCH.
- 3) RESTORATION AREAS BETWEEN THE SIDEWALK AND BACK OF CURB SHALL BE SEEDED WITH DOT SEEDING MIXTURE NO. 40. AREAS BETWEEN THE BACK OF SIDEWALK AND SLOPE INTERCEPTS SHALL BE SEEDED WITH DOT SEEDING MIXTURE NO. 10.
- 4) WHEN INLET PROTECTION TYPE A & TYPE B, C, OR D ARE INDICATED AT THE SAME LOCATION, USE TYPE A PRIOR TO THE PLACEMENT OF CURB AND GUTTER AND USE TYPE B, C, OR D AFTER THE INLET CASTINGS ARE IN PLACE.




LEGEND



	SILT FENCE		INLET PROTECTION FROM PREVIOUS STAGE
	EROSION MAT CLASS I TYPE A		TEMPORARY DITCH CHECKS
	EROSION MAT CLASS II TYPE B		SURFACE WATER FLOW ARROW
	EROSION MAT URBAN CLASS I TYPE A		SLOPE INTERCEPT
	INLET PROTECTION TYPE A		SILT FENCE RELIEF
	INLET PROTECTION TYPE D		SILT FENCE FROM PREVIOUS STAGE



PROJECT NO: 1228-16-71 HWY: IH-43 COUNTY: MILWAUKEE EROSION CONTROL - STAGE 2B SHEET 55 E

FILE NAME: F:\DESIGN\PLANS\122801\SHRETS\PLAN\122801\MILWAUKEE_GREEN_TREE\022802_EC_STPB.DWG PLOT DATE: 2/27/2018 7:52 AM PLOT BY: ANDREW ROSEMBER PLOT NAME: PLOT SCALE: 1 IN=40 FT VISO/07/CADDIS SHEET 42





Addendum No. 01
 ID 1228-16-71
 Revised Sheet 58
 March 6, 2018







Addendum No. 01
ID 1228-16-71
Revised Sheet 59
March 6, 2018





Addendum No. 01
 ID 1228-16-71
 Revised Sheet 60
 March 6, 2018







Addendum No. 01
 ID 1228-16-71
 Revised Sheet 61
 March 6, 2018




Addendum No. 01
 ID 1228-16-71
 Revised Sheet 63
 March 6, 2018




NOTE: ADDITIONAL PROFILES ON NEXT SHEET





Addendum No. 01
 ID 1228-16-71
 Revised Sheet 64
 March 6, 2018




Addendum No. 01
ID 1228-16-71
Revised Sheet 65
March 6, 2018







Addendum No. 01
 ID 1228-16-71
 Revised Sheet 66
 March 6, 2018




STAGE 1A - PHASE 1




STAGE 1A - PHASE 2



STAGE 1A - PHASE 3



STAGE 1B & STAGE 2A



STAGE 2B / STAGE 3

Addendum No. 01
ID 1228-16-71
Revised Sheet 102
March 6, 2018

NOTES:


- 1) INFORMATION ABOVE IS BASED ON STAGING PLAN AS SHOWN AND AS DISCUSSED IN THE PROSECUTION AND PROGRESS. ANY DEVIATIONS TO THE STAGING PLAN OR PROSECUTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. STAGING PLAN SHALL BE THE ENGINEER TO BE FOLLOWED. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND LOCATIONS. APPROPRIATE STEPS TO UPDATE THIS DETAIL AS NEEDED.
- 2) OFFSETS MAY VARY SLIGHTLY AND NEED TO BE FIELD VERIFIED PRIOR TO ANY CONSTRUCTION ACTIVITIES.
- 3) REFER TO THE GENERAL NOTES FOR INSTRUCTIONS RELATED TO EXISTING UTILITIES.
- 4) REMOVE BARRIER AS NEEDED TO CONSTRUCT STORM PIPE BETWEEN MM206 AND MM207.

NB IH-43 MEDIAN CONSTRUCTION DETAILS

PROJECT NO: 1228-16-71	COUNTY: MILWAUKEE	TRAFFIC CONTROL DETAILS	SHEET 102	E
FILE NAME: F:\DESIGN\PLANS\122801\SHREESPAVN\12280401_MILWAUKEE_GREEN_TREX\025190_TU.DWG	LOT DATE: 2/27/2018 4:48 PM	PLOT BY: ANDREW ROSEMBER	1 IN=10 FT	WISDOT/CADDIS SHEET 42
LAYOUT NAME: 025190_1c				


Addendum No. 01
 ID 1228-16-71
 Revised Sheet 109
 March 6, 2018

- LEGEND**
- WORK AREA
 - TRAFFIC CONTROL DRUM
 - TRAFFIC CONTROL DRUM WITH TYPE C STEADY BURN LIGHT
 - DIRECTION OF TRAFFIC
 - TYPE III BARRICADE
 - SIGN ON PERMANENT SUPPORT
 - SIGN ON TEMPORARY SUPPORT
 - TEMPORARY RAISED PAVEMENT MARKINGS
 - TEMPORARY PAVEMENT MARKING REMOVABLE TAPE WHITE, 4-INCH
 - TEMPORARY PAVEMENT MARKING REMOVABLE TAPE YELLOW, 4-INCH
 - TEMPORARY PAVEMENT MARKING REMOVABLE TAPE WHITE, 4-INCH (3' LINE & SKIP)



NOTES


- 1) REMOVE EXISTING MEDIAN CONCRETE BARRIER TO CONSTRUCT STORM DRAINAGE. REMOVE EXISTING CONCRETE BARRIER TO REPLACE THE REMOVED PERMANENT BARRIER. FASTEN TEMPORARY THREE BEAM PIECES BETWEEN THE FIXED CONCRETE BARRIER AND THE TEMPORARY PRECAST CONCRETE BARRIER. FINAL CONCRETE BARRIER WILL BE CONSTRUCTED IN STAGE 3
- 2) NIGHTTIME SINGLE LANE CLOSURE ALLOWED DURING TIMES AS SPECIFIED WITHIN THE SPECIAL PROVISIONS.



Addendum No. 01
ID 1228-16-71
Revised Sheet 112
March 6, 2018

PROJECT NO: 1228-16-71	HWY: IH-43	COUNTY: MILWAUKEE	TRAFFIC CONTROL - STAGE 1A	SHEET 112	E
FILENAME: F:\DISIGN\TAS\122801\SHRESPAN\122801\MILWAUKEE\GREEN\REV\09101_STAD.DWG LAYOUT NAME: 08105_STA PLOT DATE: 2/27/2018 6:52 PM PLOTBY: ANDREW ROSEMER PLOT NAME: 11R40PT PLOT SCALE: 11R40PT WISDOT/CADDIS SHEET 42					

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 114
 March 6, 2018




NOTES

- 1) REMOVE EXISTING MEDIAN CONCRETE BARRIER TO CONSTRUCT STORM SEWER. AT THE END OF STAGE 1A MOVE THE TEMPORARY PRECAST CONCRETE BARRIER TO REPLACE THE REMOVED PERMANENT BARRIER. AT THE END OF STAGE 1B MOVE THE TEMPORARY PRECAST CONCRETE BARRIER AND THE TEMPORARY PRECAST CONCRETE BARRIER. FINAL CONCRETE BARRIER WILL BE CONSTRUCTED IN STAGE 3
- 2) FULL NIGHTTIME CLOSURE TO NB I-43 REQUIRED TO CONSTRUCT STORM SEWER.
- 3) NIGHTTIME SINGLE LANE CLOSURE ALLOWED DURING TIMES AS SPECIFIED WITHIN THE SPECIAL PROVISIONS.
- 4) REMOVE AND REPLACE GUARDRAIL PER SECTION OF THE SPECS. IF REPLACEMENT OF THE POSTS AND GUARDRAIL CANNOT OCCUR FOLLOWING NIGHT CLOSURE OF I-43, UTILIZE TEMPORARY THRIE BEAM.

LEGEND

- WORK AREA
- TRAFFIC CONTROL DRUM
- TRAFFIC CONTROL DRUM WITH TYPE C STEADY BURN LIGHT
- DIRECTION OF TRAFFIC
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- SIGN ON PERMANENT SUPPORT
- SIGN ON TEMPORARY SUPPORT
- CRASH CUSHION TEMPORARY
- TEMPORARY RAISED PAVEMENT MARKINGS
- TEMPORARY PAVEMENT MARKING REMOVABLE TAPE WHITE, 4-INCH
- TEMPORARY PAVEMENT MARKING REMOVABLE TAPE YELLOW, 4-INCH

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 115
 March 6, 2018



- LEGEND**
- WORK AREA
 - TRAFFIC CONTROL DRUM
 - TRAFFIC CONTROL DRUM WITH TYPE C STEADY BURN LIGHT
 - DIRECTION OF TRAFFIC
 - TYPE III BARRICADE
 - TYPE III BARRICADE WITH ATTACHED SIGN
 - SIGN ON TEMPORARY SUPPORT
 - TEMPORARY RAISED PAVEMENT MARKINGS
 - TEMPORARY PAVEMENT MARKING REMOVABLE TAPE WHITE, 4-INCH
 - TEMPORARY PAVEMENT MARKING REMOVABLE TAPE YELLOW, 4-INCH
 - TEMPORARY PAVEMENT MARKING REMOVABLE TAPE WHITE, 4-INCH (3 LINE 9 SKIP)

PROJECT NO: 1228-16-71	HWY: IH-43	COUNTY: MILWAUKEE	TRAFFIC CONTROL - STAGE 1A
<small>FILE NAME: F:\DISIGN\PLANS\1228001\SHRETS\PAV1\12280401_MILWAUKEE_GREEN_TREE\028_101_STAD.DWG LAYOUT NAME: 028_108_STA</small>			
<small>DATE: 2/23/2018 8:59 AM</small>		<small>PLOT BY: ANDREW ROSEMEYER</small>	
<small>PLOT DATE:</small>		<small>PLOT NAME:</small>	
<small>PLOT SCALE: 1"=40'</small>		<small>PLOT DATE:</small>	
SHEET 115		E	

REMOVING STORM SEWER

ROADWAY	FROM		TO		204.0245		204.0245	
	STATION	OFFSET	STATION	OFFSET	REMOVING STORM SEWER	12-INCH LF	REMOVING STORM SEWER	15-INCH LF
PROJECT 1228-16-71								
GOOD HOPE SB ON RAMP	115GHC+96	19.5' LT	115GHC+96	5' RT	25	--	--	--
	114GHC+81	55.0' RT	115GHC+96	5' RT	130	--	--	--
GREEN TREE ROAD	33GT+89	18.8' RT	34GT+06	13.2' RT	--	42	--	--
	40GT+00	36.7' LT	40GT+10	21.8' RT	--	59	--	--
JEAN NICOLET ROAD	12JNH+54	28.6' RT	12JNH+78	4.8' RT	34	--	--	--
I-43	1130+93	6.6' LT	1132+33	10.0' LT	--	139	--	--
	1132+16	120.9' RT	1132+62.5	46.8' RT	--	110	--	--
	1132+33	10.0' LT	1133+15	5.8' LT	--	90	--	--
	1132+54	5.2' LT	1132+54	3.4' RT	--	9	--	--
PROJECT 1228-16-71 TOTAL					189	359		90

Addendum No. 01
ID 1228-16-71
Revised Sheet 164
March 6, 2018

REMOVING FENCE

ROADWAY	FROM		TO		204.0170	
	STATION	OFFSET	STATION	OFFSET	REMOVING FENCE	LF
PROJECT 1228-16-71						
GOOD HOPE SB ON RAMP	98GHC+75	18.6' LT	101GHC+88	3.9' LT	315	
GREEN TREE ROAD	37GT+44	41' LT	38GT+39	31.3' LT	97	
I-43	1131+94	87.2' RT	1132+67	102.4' RT	78	
PROJECT 1228-16-71 TOTAL					490	

FINISHING ROADWAY

ROADWAY	EACH
PROJECT 1228-16-71	1
PROJECT 1228-16-71 TOTAL	1

ALL ITEMS CATEGORY 0010

SHEET: 164

MISCELLANEOUS QUANTITIES

COUNTY: MILWAUKEE

HWY: IH-43

PROJECT NO: 1228-16-71

FILE NAME: F:\Design\Plans\12280401\SheetPlan\12280401_MilwaukeeGreen_Tripes.PDF

PLOT DATE: 2/27/2018 10:50:58 PM

PLOT BY: HNTB Corp

PLOT NAME: 00201_mq2

PLOT SCALE: 1:1

REMOVING DRAIN ITEMS

ROADWAY	FROM		EACH		204.0220	
	STATION	OFFSET	REMOVING MANHOLES	REMOVING NIETS	EACH	EACH
PROJECT 1228-16-71						
GOOD HOPE SB ON RAMP	102GHC+91	16.2' LT	--	1	1	
	106GHC+57	2.8' RT	--	1	1	
	107GHC+07	2.6' RT	--	1	1	
	108GHC+92	1.1' LT	--	1	1	
	111GHC+93	4.4' LT	--	1	1	
	113GHC+01	15.6' RT	--	1	1	
	115GHC+98	20.3' LT	--	1	1	
	115GHC+97	4.8' LT	--	1	1	
GREEN TREE ROAD	34GT+00	13' RT	--	1	1	
	34GT+06	13' LT	--	1	1	
	40GT+10	21.1' RT	--	1	1	
	40GT+00	37.2' LT	1	--	--	
	40GT+03	20.6' LT	--	1	1	
I-43	1131+54	4' RT	--	1	1	
	1131+55	5.5' LT	--	1	1	
	1132+33	10.1' LT	1	--	--	
	1132+64	0.4' LT	1	--	--	
	1133+15	5.6' LT	--	1	1	
JEAN NICOLET ROAD	12JNH+78	4.6' RT	--	1	1	
PROJECT 1228-16-71 TOTAL					3	16

REMOVING SIDEWALK

ROADWAY	STATION	OFFSET	SY
PROJECT 1228-16-71			
GREEN TREE ROAD	31GT+00	- 38GT+40 LT	411
	39GT+85	- 41GT+50 LT	110
	39GT+85	- 42GT+85 RT	167
PROJECT 1228-16-71 TOTAL			688

CATEGORY	DIVISION	LOCATION	FROM/TO STATION	COMMON EXCAVATION (CY) (1) (2)	EXCAVATION BELOW SUBGRADE (1)	FILL (CY)	MASS ORDINATE +/- (5)	BACKFILL STRUCTURE TYPE A (TON) 210:1500	BORROW 1.25 EX FACTOR (TON) 205.0100	EXCAVATION, HAULING, AND DISPOSAL OF CREOSOTE CONTAMINATED SOIL (TON) SPV.0195.01	COMMENTS
0010	1	GREEN TREE ROAD JEAN NICOLET ROAD	31GT+00 TO 37GT+89 8JN+42 TO 15JN+00	513 893	0 0	1,706 158	-1,193 735	0 0	2,132 197	0 0	
	DIVISION 1 SUBTOTAL										
	2,330										
0010	2	GREEN TREE ROAD	40GT+08 TO 42GT+85	446	0	190	256	0	237	0	
	DIVISION 2 SUBTOTAL										
0010	3	IH-43 GOOD HOPE ROAD SOUTHBOUND ENTRANCE RAMP CONTAMINATED SOIL ALONG IH-43	1120+45 TO 1133+19	2,341	234	10	2,331	0	12	0	
	96GH+50 TO 119+00		1,786	1,177	406	741	508	0	0	0	
	1131+27 TO 1132+59		-1,239	0	0	0	0	2,110	0	0	
	DIVISION 3 SUBTOTAL										
12,869											
PROJECT 1228-16-71 TOTAL											
16,132											
13,490											
3,087											
2,110											

- 1) EXCAVATION COMMON = CUT + EBS EXCAVATION. ITEM NUMBER 205.0100. EBS ASSUMES 10% OF THE COMMON EXCAVATION AT THE PARTICULAR STATION.
- 2) CUT VOLUME INCLUDES CONCRETE AND ASPHALTIC SURFACE MATERIAL.
- 3) EBS EXCAVATION TO BE BACKFILLED WITH SELECT CRUSHED MATERIAL UNLESS OTHERWISE NOTED IN PLANS.
- 4) ROADWAY EMBANKMENT = FILL.
- 5) MASS ORDINATE = CUT - FILL. THE MASS ORDINATE IS FOR INFORMATION PURPOSES ONLY AS COMMON EXCAVATION AND ROADWAY EMBANKMENT (BORROW) ARE NOT BALANCED FOR QUANTITY PURPOSES AND DOES NOT GUARANTEE THE QUALITY OF COMMON EXCAVATION, AND IF IT CAN BE REUSED ON SITE. ALL EBS MATERIAL IS ASSUMED TO BE WASTED OFF SITE.
- 6) EXCAVATED CREOSOTE CONTAMINATED SOILS ARE QUANTIFIED AS SHOWN WITH STATION RANGES AND ELEVATIONS DEPTHS SUPPLIED WITHIN THE SPECIALS. DISPOSAL IS PAID UNDER ITEM SPV.0195.01. CONVERSION FACTOR ESTIMATED AT 1.7 TONS PER CY.
- 7) DIVISION NUMBERING IS INDEPENDENT OF CONSTRUCTION STAGING NUMBERING.

Addendum No. 01
ID 1228-16-71
Revised Sheet 165
March 6, 2018

SUBSTRUCTURE

305.0110 305.0120 312.0110 312.0110 312.0110
 BASE AGGREGATE BASE AGGREGATE BREAKER SELECT
 DENSE 3/4" INCH DENSE 1 1/4" INCH RUN TON TON TON TON
 624.0100 624.0100 624.0100 624.0100
 WATER REINFORCEMENT
 M GAL SY

STATION FROM TO OFFSET COMMENTS
 ROADWAY FROM TO
 I-43 NB 1130+10 - 1132+40 RT 239 3.6
 I-43 NB 1130+10 - 1130+20 RT 144 0.0
 I-43 SB 1120+45 - 1129+59 LT 564 8.5
 9,449 12.0

STAGE 1A SUBTOTALS 3,861 5,704 173 59.4 260

STAGE 2A GOOD HOPE SB ON RAMP 96GHC+40 - 112GHC+00 LT/RT 2,233 33.5
 96GHC+40 - 112GHC+00 LT/RT -- --
 112GHC+00 - 119GHC+21 LT/RT 1,728 25.9 260 EBS
 112GHC+00 - 119GHC+21 LT/RT -- --
 112GHC+00 - 119GHC+21 LT/RT -- --
 3,861 5,704 173 59.4 260

STAGE 2B GREEN TREE ROAD 31GT+00 - 37GT+87 LT/RT 2,008 30.1
 31GT+00 - 37GT+82 LT 92 1.4
 32GT+52 - 32GT+62 LT 6 0.1
 32GT+84 - 33GT+08 RT 3 0.1
 32GT+85 - 32GT+96 LT 7 0.1
 33GT+04 - 33GT+12 RT 1 -- --
 33GT+44 - 33GT+54 LT 6 0.1
 33GT+47 - 33GT+58 RT 3 -- --
 33GT+51 - 34GT+01 RT 7 0.1
 36GT+52 - 36GT+69 RT 45 0.7
 36GT+78 - 36GT+88 LT 9 0.1
 37GT+17 - 37GT+49 RT 5 0.1
 8JUN+42 - 11JUN+00 RT 96 1.4
 11JUN+00 - 15JUN+35 LT/RT 1,076 16.1
 1130+84 - 1132+77 RT 29 0.4
 3,389 50.9

STAGE 3 GREEN TREE ROAD 39GT+98 - 42GT+34 LT 26 0.4
 40GT+03 - 42GT+85 LT/RT 833 12.5
 40GT+08 - 41GT+43 RT 26 0.4
 41GT+37 - 41GT+89 RT 43 0.6
 41GT+81 - 42GT+85 RT 17 0.3
 1130+95 1133+19 LT 33 3.1
 1,652 17.3

PROJECT 1228-16-71 TOTALS 37 5,704 173 140.0 260

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 166
 March 6, 2018

ALL ITEMS CATEGORY 0010

ROADWAY	STATION	OFFSET	CONCRETE PAVEMENT 10-INCH SY	CONCRETE DRIVEWAY 7-INCH SY	DRILLED TIE BARS EACH	REPAIR SHEES SY	CONCRETE SIDEWALK 5-INCH SF	SALVAGE AND REPLACE BRICK PAVERS SF	COMMENTS
415.0100 CONCRETE PAVEMENT 10-INCH SY	416.0170 CONCRETE DRIVEWAY 7-INCH SY	416.0610 DRILLED TIE BARS EACH	416.1715 CONCRETE PAVEMENT REPAIR SHEES SY	602.0410 CONCRETE SIDEWALK 5-INCH SF	SPV 0165.01 SALVAGE AND REPLACE BRICK PAVERS SF	209.0200.S BACKFILL CONTROLLED LOW STRENGTH CY			
1130+10 - 1130+20	RT								
STAGE 1A SUBTOTALS									
STAGE 2B									
GREEN TREE ROAD	31GT+00 - 32GT+52	LT					736		SIDEWALK LEFT
	32GT+49 - 32GT+65	LT	13						SIDEWALK LEFT
	32GT+62 - 32GT+85	LT		14			114		SIDEWALK LEFT
	32GT+82 - 32GT+99	LT		14			117		SIDEWALK RIGHT
	32GT+84 - 33GT+08	RT					240		SIDEWALK LEFT
	32GT+96 - 33GT+44	LT					50		RESIDENT PATH
	33GT+04 - 33GT+12	RT					50		RESIDENT PATH
	33GT+41 - 33GT+57	LT	13				50		RESIDENT PATH
	33GT+47 - 33GT+58	RT					290		SIDEWALK RIGHT
	33GT+51 - 34GT+01	RT					1,651		SIDEWALK LEFT
	33GT+54 - 36GT+78	LT							SIDEWALK LEFT
	36GT+75 - 36GT+91	LT	13				534		SIDEWALK LEFT
	36GT+88 - 37GT+82	LT					192		SIDEWALK RIGHT
	37GT+17 - 37GT+49	RT			65				UNDER BARRIER
	1130+64 - 1132+77	RT			65				
IH-43 NB			86	53	65		3,974		
STAGE 2B SUBTOTALS			86	53	65		3,974		
STAGE 3									
GREEN TREE ROAD	39GT+99 - 41GT+52	LT					1,064		SIDEWALK LEFT
	40GT+08 - 41GT+42	RT					1,064		SIDEWALK RIGHT
	41GT+81 - 42GT+85	RT					686		SIDEWALK RIGHT
	40GT+88	RT					43		
STAGE 3 SUBTOTALS							2,814		
PROJECT 1228-16-71 TOTALS			86	53	65	33	6,788	43	

Addendum No. 01
ID 1228-16-71
Revised Sheet 167
March 6, 2018

ALL ITEMS CATEGORY 0010

SHEET: 167

PROJECT NO: 1228-16-71

HWY: IH-43

COUNTY: MILWAUKEE

MISCELLANEOUS QUANTITIES

FILE NAME: F:\Design\Plans\12280401\SheetPlan\12280401_MilwaukeeGreen_Tiles.pdf

PLOT DATE: 2/27/2018 7:40:03 PM

PLOT BY: HNTB Corp

PLOT NAME: 003201.mpg

PLOT SCALE: 1:1

PROJECT NO: 1228-16-71

HWY: IH-43

COUNTY: MILWAUKEE

MISCELLANEOUS QUANTITIES

SHEET: 167

ASPHALT ITEMS

ROADWAY	STATION	OFFSET	PAVING TON	WEATHER GAL	TACK TON	HMA PAVEMENT 3 MI 58-28 S TON	HMA PAVEMENT 4 MI 58-28 S TON	ASPHALTC SURFACE DRIVEWAYS AND FIELD ENTRANCES TON	COLD PATCH TON
STAGE 1A									
I-43 NB	1130+10	RT	--	29	--	--	49	--	--
	1130+10	RT	--	--	73	--	--	--	--
I-43 SB	1120+45	LT	--	71	--	120	--	--	--
	1120+45	LT	--	--	180	--	--	--	--
STAGE 1A SUBTOTALS			100	253	169	--	--	--	--
STA GE 2A									
GOOD HOPE SB ON RAMP	96GHC+40	RT/LT	--	389	--	656	--	--	--
	96GHC+40	RT/LT	--	983	--	--	656	--	--
STAGE 2A SUBTOTALS			--	389	983	656	--	--	--
STA GE 2B									
GREEN TREE ROAD	31GT+00	RT/LT	--	207	--	349	--	--	--
	31GT+00	RT/LT	--	--	524	--	--	--	--
	32GT+52	LT	--	1	--	2	--	--	--
	32GT+85	LT	--	1	--	2	--	--	--
	33GT+44	LT	--	1	--	2	--	--	--
	36GT+52	RT	--	6	--	15	--	--	--
	36GT+78	LT	--	1	--	3	--	--	--
JEAN NICOLET ROAD	11JUN+00	RT/LT	--	106	--	178	--	--	--
	11JUN+00	RT/LT	--	--	267	--	--	--	--
STAGE 2B SUBTOTALS			--	323	791	527	24	--	--
STAGE 3 SUBTOTALS									
GREEN TREE ROAD	40GT+03	RT/LT	--	88	--	148	--	--	--
	40GT+03	RT/LT	222	--	222	--	13	--	--
	41GT+40	RT	--	5	--	--	20	--	--
HOTEL PARKING LOT	40GT+05	LT	20	--	--	16	--	--	--
I-43 NB	1131+25	RT	--	10	--	25	--	--	--
	1131+25	RT	25	--	--	22	--	--	--
I-43 SB	1130+95	LT	33	--	33	--	13	--	--
	1130+95	LT	300	116	280	206	47	--	--
STAGE 3 SUBTOTALS			300	928	2,307	1,558	10	20	20
UNDISTRIBUTED			--	--	--	--	--	--	--
PROJECT 1228-16-71 TOTALS			300	928	2,307	1,558	47	10	20

Addendum No. 01
ID 1228-16-71
Revised Sheet 168
March 6, 2018

ALL ITEMS CATEGORY 0010

INLET PROTECTION (CONT.)

ROADWAY	STATION	OFFSET	INLET PROTECTION TYPEA	EACH	628.7005	INLET PROTECTION TYPEB	EACH	628.7020	
GREEN TREE ROAD	40GT+04	21' LT							
	40GT+10	22' RT							
	40GT+25	21' LT	1						
	41GT+60	21' LT							
	41GT+60	21' RT							
	1130+49	5' RT							
	1133+15	6' LT							
	STAGE 2B SUBTOTALS								5
	PROJECT 1228-16-71 TOTALS								28
	PROJECT 1228-16-71 TOTALS								44

TEMPORARY SETTLING BASIN

ROADWAY	EROSION BALES EACH	GEOTEXTILE TYPE/HR	SY
PROJECT 1228-16-71	30		67
SETTLING BASIN	30		67
PROJECT 1228-16-71 TOTALS	30		67

Addendum No. 01
ID 1228-16-71
Revised Sheet 175
March 6, 2018

MAINTENANCE AND REPAIR OF HAUL ROADS (1228-16-71)

ROADWAY	MAINTENANCE AND REPAIR OF HAUL ROADS	1228-16-71
PROJECT 1228-16-71	EACH	1
PROJECT 1228-16-71 TOTAL:		1

ALL ITEMS CATEGORY 0010

MISCELLANEOUS QUANTITIES

HWY: IH-43

PROJECT NO: 1228-16-71

SHEET: 175

E

INLET PROTECTION

ROADWAY	STATION	OFFSET	INLET PROTECTION TYPEA	EACH	628.7005	INLET PROTECTION TYPEB	EACH	628.7020
GREEN TREE ROAD	33GT+58	35' RT	1					
	34GT+00	13' RT						
	34GT+06	13' LT						
	10JUN+78	15' RT						
	12JUN+54	29' RT						
	12JUN+78	5' RT						
	1130+49	5' RT						
	1130+49	47' RT						
	1132+63	3' RT						
	STAGE 1A SUBTOTALS							
GOOD HOPE SB ON RAMP	115GHC+96	5' RT	1					
	115GHC+88	20' LT	1					
STAGE 1B SUBTOTALS								2
GREEN TREE ROAD	34GT+00	13' RT	1					
	34GT+05	18' T						
	34GT+17	17' LT						
	34GT+14	18' RT						
	37GT+37	26' RT						
	37GT+37	20' LT						
	40GT+04	20' LT						
	40GT+10	21' RT						
	42GT+11	21' LT						
	42GT+11	21' RT						
GOOD HOPE SB ON RAMP	98GHC+42	2' LT	1					
	104GHC+41	7' LT	1					
	104GHC+42	3' LT	1					
	106GHC+55	13' LT	1					
	106GHC+56	4' LT	1					
	106GHC+57	6' LT	1					
	107GHC+06	7' LT	1					
	107GHC+07	3' LT	1					
	108GHC+82	2' LT	1					
	108GHC+82	7' LT	1					
GOOD HOPE SB ON RAMP CONT.	111GHC+83	5' LT	1					
	113GHC+17	5' LT	1					
	113GHC+50	12' LT	1					
	113GHC+70	7' LT	1					
	116GHC+45	27' RT	1					
	1124+50	13' LT	1					
	1132+63	46' RT	1					
	1139+10	47' LT	1					
	1139+26	46' LT	1					
	1139+75	47' LT	1					
JEAN NICOLET ROAD	1139+79	55' LT	1					
	10JUN+89	15' RT	1					
	12JUN+54	29' RT	1					
	12JUN+78	5' RT	1					
STAGE 2A SUBTOTALS								24
PROJECT 1228-16-71 TOTALS								29

COUNTY: MILWAUKEE

HWY: IH-43

PROJECT NO: 1228-16-71

SHEET: 175

E

TRAFFIC CONTROL FIXED MESSAGE SIGNS

LOCATION	FMS NO.	WOOD POSTS 4X6-INCH X 12-FT	TRAFFIC CONTROL SIGNS FIXED MESSAGE	SF
PROJECT 1228-16-71				
EB GREEN TREE ROAD	101	2	19.5	19.5
NB MILWAUKEE RIVER PKWY	101	2	19.5	19.5
SB MILWAUKEE RIVER PKWY	101	2	19.5	19.5
WB BENDER ROAD	102	2	18.0	18.0
EB BENDER ROAD	102	2	18.0	18.0
NB JEAN NICOLET ROAD	102	2	18.0	18.0
NB PORT WASHINGTON ROAD	103	2	18.0	18.0
SB PORT WASHINGTON ROAD	103	2	18.0	18.0
WB GREEN TREE ROAD	103	2	18.0	18.0
NB PORT WASHINGTON ROAD	104	--	6.3	6.3
NB PORT WASHINGTON ROAD	104	--	6.3	6.3
NB PORT WASHINGTON ROAD	104	--	6.3	6.3
SB PORT WASHINGTON ROAD	104	--	6.3	6.3
SB PORT WASHINGTON ROAD	104	--	6.3	6.3
EB GOOD HOPE ROAD	105	2	16.5	16.5
SB GREEN BAY ROAD	105	2	16.5	16.5
PROJECT 1228-16-71 TOTALS				237.3

INLET COVER REPAIR MAINTENANCE SPECIAL

ROADWAY	STATION	OFFSET	VANE	EACH	SPECIAL
PROJECT 1228-16-71					
143 SB	1122+10	13' L	1	1	1
	1124+50	13' L	1	1	1
PROJECT 1228-16-71 TOTALS				2	2

611.9900 S
DRAIN SLOTTED
VANE

611.9900 S
INLET COVER
REPAIR MAINTENANCE
SPECIAL

* EACH LOCATION WILL TOTAL 9 LINEAR FEET OF VANE DRAIN

PORTABLE SPEED TRAILER

ROADWAY	SPEED TRAILER	DAY S
PROJECT 1228-16-71		
JEAN NICOLET ROAD	245	245
PROJECT 1228-16-71 TOTAL		245

FIELD FACILITY OFFICE SPACE

ROADWAY	OFFICE SPACE
PROJECT 1228-16-71	
ROADWAY	EACH
PROJECT 1228-16-71 TOTAL	
1	

**PAVEMENT CLEANUP
(PROJECT 1228-16-71)**

ROADWAY	HOURS
PROJECT 1228-16-71	
PAVEMENT CLEANUP PROJECT 1228-16-71	250
PROJECT 1228-16-71 TOTAL	
250	

NOTE: QUANTITY ASSUMES 10 HOURS/WEEK

Addendum No. 01
ID 1228-16-71
Revised Sheet 178
March 6, 2018

SURVEY PROJECT

ROADWAY	LS
PROJECT 1228-16-71	
ROADWAY	1
PROJECT 1228-16-71 TOTAL	
1	

PROJECT NO: 1228-16-71

HWY: IH-43

COUNTY: MILWAUKEE

MISCELLANEOUS QUANTITIES

SHEET: 178

ALL ITEMS CATEGORY 0010

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 181
 March 6, 2018

SAWCUTS

690.0150 690.0250
 SAWING SAWING
 ASPHALT CONCRETE

LF LF

ROADWAY	STATION	OFFSET	NOTES
PROJECT 1228-16-71			
GOOD HOPE SB ON RAMP	104GHC+55 - 104GHC+55	RT	11
	118GHC+82 - 1118GHC+82	LT	22
	118GHC+82 - 119GHC+21	RT	60
GREEN TREE ROAD	31GT+00 - 31GT+00	LT	27
	32GT+50 - 32GT+63	LT	12
	32GT+85 - 32GT+96	LT	11
	33GT+15 - 33GT+47	RT	32
	33GT+44 - 33GT+54	LT	10
	36GT+44 - 36GT+59	RT	15
	36GT+79 - 16GT+88	LT	10
	41GT+46 - 41GT+73	RT	27
	42GT+34 - 42GT+58	LT	24
	42GT+85 - 42GT+85	LT	45
I-43	1122+48 - 1139+76	LT	1,728
	1130+10 - 1133+02	RT	356
	1130+94 - 1133+19	LT	222
JEAN NICOLET ROAD	1131+00 - 1133+00	RT	200
UNDISTRIBUTED	11JN+00 - 11JN+00	L/RT	--
			100
PROJECT 1228-16-71 TOTAL			2,855
			201

STAGE3, NB INSIDE SHOULDER

VIBRATION MONITORING

SPV 0135.01	MON
ROADWAY	7
GREEN TREE / I-43	7
PROJECT 1228-16-71 TOTAL	7

FLAGGING SPECIAL

ROADWAY	STAGE	ESTIMATED NO. OF FLAGGERS	SPV 0075.02 HOURS
JEAN NICOLET / GREEN TREE	1	2	100
JEAN NICOLET / GREEN TREE	3	2	164
PROJECT 1228-16-71 TOTAL			264

NOTE QUANTITY ASSUMES 2 HOURS/DAY

ALL ITEMS CATEGORY 0010

PROJECT NO: 1228-16-71

HWY: IH-43

COUNTY: MILWAUKEE

MISCELLANEOUS QUANTITIES

SHEET: 181

E

Addendum No. 01
ID 1228-16-71
Revised Sheet 183
March 6, 2018

STORM SEWER STRUCTURES

520.8000 611.0420 611.053 611.0535 611.0606 611.061 611.0624 611.0642 611.0651 611.0654 611.1005

STRUCTURE NUMBER	STATION	OFFSET	FLANGE OR RM ELEV	EXISTING RM ELEV	LOWEST INVERT	DEPTH	CONCRETE COLLARS		FOR PIPE		MANHOLE RECONSTRUCT		MANHOLE COVERS		MANHOLE COVERS		MANHOLE COVERS		MANHOLE COVERS		MANHOLE COVERS		CATCH BASIN 5-FT DIAMETER																					
							EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH		EACH	EACH	EACH	EACH																	
101	34GT+15	18.0' LT	682.35	--	675.50	5.60	--	--	--	--	1	--	--	1	--	--	--	--	--	--	--	1																						
EX MH01	34GT+00	9.9' LT	681.74	680.13	684.62	15.87	--	1	--	--	1	--	--	--	--	--	--	--	--	--	--	--																						
EX MH05	34GT+00	13.0' RT	681.69	680.14	671.30	9.14	--	1	--	--	--	--	--	--	--	--	--	--	--	--	--	--																						
EX MH08	32GT+30	20.8' RT	674.72	673.77	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--	--	--																						
102	34GT+16	18.0' RT	682.40	--	676.00	5.15	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	1																						
EX IN06	33GT+12	37.8' RT	677.05	676.25	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--	--	--																						
EX IN07	33GT+48	36.5' RT	678.02	676.91	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--	--	--																						
103	33GT+55	39.0' RT	675.80	--	671.58	2.97	--	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--																						
104	36GT+22	18.4' LT	694.35	--	690.00	3.10	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--																						
MH110	40GT+14	58.1' LT	700.50	--	693.17	6.08	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--																						
107	40GT+25	21.0' LT	701.65	--	692.45	7.55	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--																						
EX IN222	42GT+36	21.0' RT	701.50	--	690.00	10.25	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	1																						
EX IN223	42GT+11	21.0' LT	700.51	700.59	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--																						
105	41GT+60	21.0' RT	700.51	700.68	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--																						
106	41GT+60	21.0' LT	700.09	700.09	696.04	2.80	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--																						
106	41GT+60	21.0' RT	700.08	--	695.00	4.08	--	--	--	--	1	--	--	--	--	--	--	--	--	--	1	--																						
W. GREEN TREE ROAD SUBTOTALS																							4	4	3	6	1	1	3														3	
N. JEAN NICOLET ROAD SUBTOTALS																																												
114	12JN+60	16.0' LT	692.95	--	689.75	1.45	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--																					
115	12JN+60	16.0' RT	692.93	--	689.59	2.03	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--																					
EX IN116	102GHC+91	16.1' LT	692.93	--	689.20	2.38	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--																					
N. JEAN NICOLET ROAD SUBTOTALS																							1	1	3	1	1	1	1															

STORM SEWER STRUCTURES (CONT.)

STRUCTURE NUMBER	STATION	OFFSET	FLANGE OR RM ELEV	EXISTING RM ELEV	LOWEST INVERT	DEPTH	CONCRETE COLLARS		RECONSTRUCT		MANHOLE COVERS		MANHOLE COVERS		MANHOLE COVERS		INLET COVERS		INLET COVERS		INLET COVERS		CATCH BASIN 5-FT DIAMETER
							FOR PIPE EACH	MANHOLE EACH	TYPE J EACH	TYPE JS EACH	TYPE B EACH	TYPE H EACH	TYPE S EACH	TYPE V EACH	TYPE S EACH	TYPE V EACH	TYPE S EACH	TYPE V EACH	TYPE S EACH	TYPE V EACH	TYPE S EACH		
I43																							
MH200	40GT+43	141.3' RT	689.06		674.63	23.17	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--	
MH201	1130+15	11.0' RT	685.08		674.09	9.74	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--	
205	1130+49	4.0' RT	683.71		677.75	4.71	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
MH203	1130+49	11.0' RT	684.02		673.92	8.85	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--	
MH206	1132+32	11.0' RT	680.76		672.10	7.41	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
MH207	1132+33	11.2' RT	680.70		672.00	7.45	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--	
224	1132+63	45.9' RT	680.87		676.25	3.37	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
202	104GHC+42	7.0' LT	683.75		679.80	2.70	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
EX IN203	104GHC+42	3.4' RT	684.07		679.45	3.37	1	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
214	106GHC+56	12.3' LT	682.80		676.62	4.83	--	--	--	--	--	--	1	--	--	--	--	--	--	--	--	--	
212	106GHC+57	7.0' LT	680.45		676.59	2.61	--	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	
EX IN210	1132+65	46.5' LT	680.43		676.55	2.63	1	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
208	1132+65	7.4' LT	680.52		676.39	2.88	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
209	1132+64	2.6' RT	680.45		672.53	6.67	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
215	1133+14	47.0' LT	680.70		676.41	3.04	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
EX IN214	1133+14	57.8' LT	680.91		676.36	3.30	1	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
213	1133+15	5.6' LT	680.67		676.13	3.29	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
EX IN211	1124+50	13.0' LT	684.61		--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
EX IN219	1122+10	13.0' LT	680.02		--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
MH216	1133+16	0.2' LT	680.64		673.00	6.39	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	--	
230	108GHC+92	7.0' LT	684.12		681.10	1.77	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
EX IN231	1134+99	52.6' LT	684.23		681.00	1.98	1	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
236	111GHC+93	7.0' LT	689.20		685.00	2.95	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
237	113GHC+17	7.0' LT	689.70		686.00	2.45	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
226	113GHC+50	11.8' LT	691.00		686.26	3.49	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
238	113GHC+65	7.0' LT	690.25		686.42	2.58	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
239	113GHC+69	18.5' RT	691.13		686.65	3.23	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
240	1139+75	46.7' LT	690.69		686.97	2.47	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	1	
217	113GHC+16	17.5' RT	690.50		686.45	2.80	--	--	--	--	1	--	--	--	--	--	--	--	--	--	--	--	
242	116GHC+45	27.3' RT	700.56		696.12	3.19	--	--	--	1	5	1	12	2	2	--	--	--	--	--	--	1	
I43 SUBTOTALS							4			1	5	1	12	2	2							1	
PROJECT 1228-16-71 TOTALS							4			4	2	8	13	9	3	1	1	1	1	1	1	1	3

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 184
 March 6, 2018

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 185
 March 6, 2018

STORM SEWER STRUCTURES (CONT.)

STRUCTURE NUMBER	STATION	OFFSET	FLANGE OR RIM ELEV	EXISTING RIM ELEV	LOWEST INVERT	DEPTH	CATCH BASIN MANHOLES		MANHOLES		INLETS 2X2.5-FT	INLETS 2X3-FT	INLETS MEDIAN 1	ADJUSTING INLET COVERS	DRAIN SLOTTED VAN
							DIAMETER	DIAMETER	DIAMETER	DIAMETER					
W. GREEN TREE ROAD															
101	34GT+15	18.0' LT	682.35	--	675.50	5.60	--	--	--	--	--	--	--	--	--
EX MH-01	34GT+00	9.9' LT	681.74	680.13	664.62	15.87	--	--	--	--	--	--	--	--	--
EX MH-05	34GT+00	13.0' RT	681.69	680.14	671.30	9.14	--	--	--	--	--	--	--	--	--
EX MH-08	32GT+30	20.8' RT	674.72	673.77	--	--	--	--	--	--	--	--	--	--	--
102	34GT+16	18.0' RT	682.40	--	676.00	5.15	--	--	--	--	--	--	--	--	--
EX IN-06	33GT+12	37.8' RT	677.05	676.25	--	--	--	--	--	--	--	--	1	--	--
EX IN-07	33GT+48	36.5' RT	678.02	676.91	--	--	--	--	--	--	--	--	--	--	--
103	33GT+55	39.0' RT	675.80	--	671.58	2.97	--	--	--	--	--	1	--	--	--
104	36GT+22	18.4' LT	694.35	--	690.00	3.10	--	--	--	--	1	--	--	--	--
MH-10	40GT+14	58.1' LT	700.50	--	693.17	6.08	--	--	--	--	--	--	--	--	--
108	40GT+25	21.0' LT	701.65	--	692.85	7.55	--	--	--	--	1	--	--	--	--
107	40GT+36	21.0' RT	701.50	--	690.00	10.25	--	--	--	--	--	--	--	--	--
EX IN-22	42GT+11	21.0' LT	700.51	700.59	--	--	--	--	--	--	--	--	1	--	--
EX IN-23	42GT+11	21.0' RT	700.51	700.68	--	--	--	--	--	--	--	--	--	--	--
105	41GT+60	21.0' LT	700.09	--	696.04	2.80	--	--	--	--	1	--	--	--	--
106	41GT+60	21.0' RT	700.08	--	695.00	4.08	--	--	--	--	1	--	--	--	--
W. GREEN TREE ROAD SUBTOTALS															
N. JEAN NICOLET ROAD SUBTOTALS															
114	12JN+60	16.0' LT	692.95	--	689.75	1.95	--	--	--	--	1	--	--	--	--
115	12JN+60	16.0' RT	692.93	--	689.59	2.09	--	--	--	1	--	--	--	--	--
EX IN-116	102GHC+91	16.1' LT	692.93	--	689.20	2.40	--	--	--	--	--	--	--	--	--
N. JEAN NICOLET ROAD SUBTOTALS															

STORM SEWER STRUCTURES (CONT.)

STRUCTURE NUMBER	STATION	OFFSET	FLANGEOR RIM/ELEV	EXISTING RIM/ELEV	LOWEST INVERT	DEPTH	5-FT		4-FT		3-FT		2-FT		1-FT		ADJUSTING INLET COVERS	DRAIN SLOTTED VAIN	
							DIAMETER	DAMETER	DIAMETER	DAMETER	DIAMETER	DAMETER	DIAMETER	DIAMETER	DIAMETER	DIAMETER			DIAMETER
143																			
M#200	40GT+43	141.3 RT	699.05	--	674.63	23.17	--	--	--	--	--	--	--	--	--	--	--	--	611.9900
M#201	1130+15	11.0 RT	685.08	--	674.09	9.74	--	1	--	--	--	--	--	--	--	--	--	611.8115	
205	1130+49	4.0 RT	683.71	--	677.75	4.71	--	--	--	1	--	--	--	--	--	--	--	611.3901	
M#203	1130+49	11.0 RT	684.02	--	673.92	8.85	--	1	--	--	--	--	--	--	--	--	--	611.3225	
M#206	1132+32	11.0 RT	680.76	--	672.10	7.41	--	--	--	--	--	--	--	--	--	--	--	611.3220	
M#207	1132+33	11.2 RT	680.70	--	672.00	7.45	--	--	--	1	--	--	--	--	--	--	--	611.3220	
224	1132+63	45.9 RT	680.87	--	676.25	3.37	--	--	--	1	--	--	--	--	--	--	--	611.3901	
202	104GHC+42	7.0 LT	683.75	--	679.80	2.70	--	--	--	1	--	--	--	--	--	--	--	611.3225	
EX#203	104GHC+42	3.4 RT	684.07	--	679.45	3.37	--	--	--	1	--	--	--	--	--	--	--	611.3220	
214	106GHC+56	12.3 LT	682.80	--	676.62	4.93	--	--	--	--	--	--	--	--	1	--	--	611.3220	
212	106GHC+57	7.0 LT	680.45	--	676.59	2.61	--	--	--	1	--	--	--	--	--	--	--	611.3220	
EX#210	1132+65	46.5 LT	680.43	--	676.55	2.63	--	--	--	--	--	--	--	--	--	--	--	611.3220	
208	1132+65	7.4 LT	680.52	--	676.39	2.88	--	--	--	1	--	--	--	--	--	--	--	611.3220	
209	1132+64	2.6 RT	680.45	--	672.53	6.67	--	1	--	--	--	--	--	--	--	--	--	611.3220	
215	1133+14	57.0 LT	680.70	--	676.41	3.04	--	--	--	1	--	--	--	--	--	--	--	611.3220	
EX#214	1133+14	47.8 LT	680.91	--	676.36	3.30	--	--	--	--	--	--	--	--	--	--	--	611.3220	
213	1133+15	5.6 LT	680.67	--	676.13	3.29	--	--	--	1	--	--	--	--	--	--	--	611.3220	
EX#211	1124+50	13.0 LT	684.61	--	--	--	--	--	--	--	--	--	--	--	--	--	--	611.3220	
EX#219	1122+10	13.0 LT	680.02	--	--	--	--	--	--	--	--	--	--	--	--	--	--	611.3220	
M#216	1133+16	0.2 LT	680.64	--	673.00	6.39	--	--	--	1	--	--	--	--	--	--	--	611.3220	
230	108GHC+92	7.0 LT	684.12	--	681.10	1.77	--	--	--	1	--	--	--	--	--	--	--	611.3220	
EX#231	1134+99	52.6 LT	684.23	--	681.00	1.98	--	--	--	--	--	--	--	--	--	--	--	611.3220	
236	111GHC+83	7.0 LT	689.20	--	685.00	2.95	--	--	--	--	--	--	--	--	--	--	--	611.3220	
237	113GHC+17	7.0 LT	689.70	--	686.00	2.45	--	--	--	1	--	--	--	--	--	--	--	611.3220	
226	113GHC+50	11.8 LT	691.00	--	686.26	3.49	--	--	--	--	--	--	--	--	1	--	--	611.3220	
238	113GHC+65	7.0 LT	690.25	--	686.42	2.58	--	--	--	--	--	--	--	--	--	--	--	611.3220	
239	113GHC+89	18.5 RT	691.13	--	686.65	3.23	--	--	--	--	--	--	--	--	--	--	--	611.3220	
240	1139+75	46.7 LT	690.69	--	686.97	2.47	--	--	--	1	--	--	--	--	--	--	--	611.3220	
217	113GHC+16	17.5 RT	690.50	--	686.45	2.80	--	--	--	1	--	--	--	--	--	--	--	611.3220	
242	116GHC+45	27.3 RT	700.56	--	696.12	3.19	--	--	--	1	--	--	--	--	1	--	--	611.3220	
143 SUBTOTALS								1	4	2	3	1	1	1	9	1	2	6	
PROJECT 1228-16-71 TOTALS								3	1	2	3	1	1	1	10	5	3	6	

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 186
 March 6, 2018

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 187
 March 6, 2018

STORM SEWER PIPES															
		608.0312		608.0315		608.0318		608.0324		608.0330		608.0336		608.0430	
FROM STR	TO STR	INVERT ELEV	DISCH ELEV	SLOPE	LF	PIPE CLASS	REINFORCED CONCRETE	LF	PIPE CLASS	REINFORCED CONCRETE	LF	PIPE CLASS	REINFORCED CONCRETE	LF	PIPE CLASS
W. GREEN TREE ROAD															
101	EX MH-01	677.50	677.25	1.47%	--	17	--	--	--	--	--	--	--	--	--
102	EX MH-05	678.00	677.00	5.88%	--	17	--	--	--	--	--	--	--	--	--
103	EX MH-05	671.58	671.30	0.54%	--	52	--	--	--	--	--	--	--	--	--
104	101	690.00	677.50	0.04%	--	207	--	--	--	--	--	--	--	--	--
EX IN-17	103	671.70	671.58	1.33%	--	9	--	--	--	--	--	--	--	--	--
MH-110	108	693.17	692.85	0.62%	--	39	--	--	--	--	--	--	--	--	--
108	107	692.85	692.50	0.81%	--	43	--	--	--	--	--	--	--	--	--
106	107	695.00	694.43	0.46%	--	124	--	--	--	--	--	--	--	--	--
105	106	696.04	695.83	0.50%	--	42	--	--	--	--	--	--	--	--	--
W. GREEN TREE SUBTOTALS					--	302	248	--	--	--	--	--	--	--	--
N. JEAN NICOLET ROAD															
114	115	689.75	689.59	0.50%	32	--	--	--	--	--	--	--	--	--	--
115	EX IN-116	689.59	689.20	2.79%	14	--	--	--	--	--	--	--	--	--	--
N. JEAN NICOLET ROAD SUBTOTALS					46	--	--	--	--	--	--	--	--	--	--
I-43															
107	MH-200	692.00	691.30	0.58%	--	--	--	121	--	--	--	--	--	--	103
MH-201	MH-201	674.63	674.09	0.52%	--	--	--	--	--	34	--	--	--	--	--
MH-201	MH-203	674.09	673.92	0.50%	--	--	--	--	--	--	--	--	--	--	183
MH-203	MH-206	673.92	672.60	0.72%	--	--	--	--	--	--	--	--	--	--	--
MH-206	MH-207	672.10	672.00	0.45%	--	--	--	--	--	--	--	--	22	--	--
202	CC1	679.80	679.45	3.50%	10	--	--	--	--	--	--	--	--	--	--
205	MH-203	677.75	677.52	3.29%	7	--	--	--	--	--	--	--	--	--	--
214	212	676.62	676.59	0.60%	5	--	--	--	--	--	--	--	--	--	--
212	CC2	676.59	676.55	0.40%	10	--	--	--	--	--	--	--	--	--	--
208	209	676.39	675.53	8.60%	10	--	--	--	--	--	--	--	--	--	--
215	CC3	676.41	676.36	0.56%	9	--	--	--	--	--	--	--	--	--	--
213	MH-216	676.13	676.00	2.17%	6	--	--	--	--	--	--	--	52	--	--
216	209	673.00	672.53	0.90%	--	--	--	--	--	--	--	--	34	--	--
209	MH-207	672.53	672.00	4.56%	--	--	--	--	--	--	--	--	--	--	--
230	CC4	681.10	681.00	2.50%	4	--	--	--	--	--	--	--	--	--	--
237	236	686.00	685.00	0.81%	123	--	--	--	--	--	--	--	--	--	--
226	237	686.26	686.00	0.79%	33	--	--	--	--	--	--	--	--	--	--
238	226	686.42	686.26	1.00%	16	--	--	--	--	--	--	--	--	--	--
239	238	686.65	686.42	0.88%	26	--	--	--	--	--	--	--	--	--	--
240	239	686.97	686.89	0.89%	9	--	--	--	--	--	--	--	--	--	--
217	237	686.45	686.25	0.83%	25	--	--	--	--	--	--	--	--	--	--
242	239	696.12	687.14	3.21%	280	--	--	--	--	--	--	--	--	--	--
I-43 SUBTOTALS					324	249	248	121	34	108	286	--	--	--	--
PROJECT 1228-16-71 TOTAL															
					370	551	248	121	34	108	286	--	--	--	--

ALL ITEMS CATEGORY 0010

REMOVALS

LOCATION	I.D.	I.D.	SY	LF	EACH	EACH	EACH	LF	LF	LS
NICOLET PED TUNNEL - WEST ENTRANCE	--	--	12	107	--	--	1	--	--	--
NICOLET PED TUNNEL - EAST ENTRANCE	24	24	--	--	--	1	250	250	--	--
NICOLET PED TUNNEL	--	--	--	--	--	--	--	--	--	1
INLET 2001	--	--	--	--	--	1	--	--	--	--
MANHOLE 1001	--	--	--	--	1	--	--	--	--	--
PROJECT 1228-16-71 TOTALS	24	24	12	107	1	1	3	250	1	1

REMOVING SIDEWALK ITEM INCLUDES INTEGRAL PED CURB


NICOLET PED TUNNEL

LOCATION	CY	SF	SF	LF	LF	LF	LB	SY	LF	LF	CY
NICOLET PED TUNNEL - WEST ENTRANCE	65	210	210	210	45	100	2	60	77	77	--
NICOLET PED TUNNEL - EAST ENTRANCE	155	210	210	210	--	250	15	560	77	77	--
NICOLET PED TUNNEL	--	--	--	--	--	--	--	--	--	--	380
PROJECT 1228-16-71 TOTALS	220	420	420	420	45	350	17	620	154	154	380

* ADDITIONAL QUANTITIES SHOWN ELSEWHERE ON PLAN

Addendum No. 01
 ID 1228-16-71
 Added Sheet 188A
 March 6, 2018

STATE PROJECT NUMBER
1228-16-71



LIST OF DRAWINGS

- GENERAL PLAN & ELEVATION
- TYPICAL SECTION
- PH 43 SECTIONS
- PROFILE GRADE LINES & EXCAVATION LIMITS
- STRUCTURE BACKLASH LIMITS
- SUBSURFACE EXPLORATION
- WEST ABUTMENT DETAILS (1 OF 2)
- WEST ABUTMENT DETAILS (2 OF 2)
- EAST ABUTMENT DETAILS (1 OF 2)
- EAST ABUTMENT DETAILS (2 OF 2)
- MINOR WALLS
- PIER WALLS
- PIER WALL REINFORCEMENT
- PIER DETAILS & REINFORCEMENT
- 45W PRESTRESSED GIRDER
- 45W PRESTRESSED GIRDER DETAILS
- SUPERSUBSTRUCTURE FRAMING PLAN
- SUPERSUBSTRUCTURE REINFORCEMENT
- SUPERSUBSTRUCTURE DETAILS
- CURB RAMP DETAILS
- MODIFIED VERTICAL FACE PARAPET 'A'
- STEEL DIAPHRAGM
- MODIFIED VERTICAL FACE PARAPET 'A'
- SLOPE PAVING CRUSHED AGGREGATE SPECIAL

Addendum No. 1
ID 1228-16-71
Revised Sheet 355
March 6, 2018

William C. Decker
03/05/18

TOTAL ESTIMATED QUANTITIES

ITEM NO.	BID ITEM	UNIT	SUPER	WEST ABUT.	PIER	EAST ABUT.	TOTAL
203.0200.01	REMOVING OLD STRUCTURE STA. 40G+00	LS					1
206.0000.01	EXCAVATION FOR STRUCTURES BRIDGES B-40-917	TON		372	563	407	1,342
210.1500.00	BACKFILL STRUCTURE TYPE A	TON		56	175	68	949
502.0100	CONCRETE MASONRY BRIDGES	CY	650	56	175	68	1,578
502.3200	PROTECTIVE SURFACE TREATMENT	SY	1578				1,578
502.3220	PIGMENTED SURFACE SEALER	SY	180	7		13	200
503.0146	PRESTRESSED GIRDER TYPE I 48W-INCH	LB	1933	4,000	8,530	4,740	19,233
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	195,070	1,270	207,000	2,240	159,280
505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB					
506.2605	BEARING PADS ELASTOMERIC NON-LAMINATED	EACH	32	9	18	9	96
506.4000.01	STEEL DIAPHRAGMS B-40-917	EACH					
514.0000.01	STEEL DIAPHRAGMS B-40-917	EACH					
514.0901.01	RAILING TUBULAR SCREENING B-40-917	LF	431	15	2340	29	475
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY					
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY					
520.2168	PIPING CONCRETE 18" x 18" x 325-INCH	LF		805	1450	835	3,190
520.2206	PIPE UNDERDRAIN UNPERFORATED 6-INCH	LF		260	290	110	770
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF		110	150	260	260
645.0311	GEOTEXTILE TYPE DF SCHEDULE A	SY	70	4	85	155	155
SPV.0060.05	PILE DYNAMIC ANALYZER (PDIA) TESTING	EACH		2	4	2	8
SPV.0060.06	PILE DYNAMIC ANALYZER (PDIA) RESTRIKES	EACH		2	4	2	8
SPV.0060.07	CASE FILE WAVE ANALYSIS PROGRAM (CAPMAP) EVALUATION	EACH		2	4	2	8
SPV.0060.02	SLOPE PAVING CRUSHED AGGREGATE SPECIAL	SY	380	380	390	770	770
	NON-BID ITEMS						
	NAME PLATE	EACH					1
	ROCKWELL SHIELD	EACH					1
	PREFORMED JOINT FILLER	EACH					1/2" x 4"
	CORK FILLER	SIZE					
	SIZE						

ALL ITEMS ARE CATEGORY 0020

DESIGN DATA

LIVE LOAD:
 INVENTORY RATING: HS-20
 INVENTORY RATING FACTOR: RF = 1.07
 OPERATING RATING FACTOR: RF = 1.64
 WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV): 250 KIPS
 STRUCTURE IS DESIGNED FOR A FUTURE WEARING SURFACE OF 20 POUNDS PER SQUARE FOOT.

MATERIAL PROPERTIES:

CONCRETE MASONRY:
 SUPERSTRUCTURE $f_c = 4,000$ psi
 SUBSTRUCTURE $f_c = 4,000$ psi
 CIP CONCRETE PILING $f_c = 3,500$ psi
 45W-INCH PRESTRESSED GIRDERS $f_c = 8,500$ psi
 48W-INCH PRESTRESSED GIRDERS $f_c = 8,500$ psi
 BAR STEEL REINFORCEMENT $f_y = 60,000$ psi
 PRESTRESSING STRANDS ULTIMATE TENSILE STRENGTH = 270,000 psi

TRAFFIC DATA

GREEN TREE RD
 AADT = 4,800 (2046)
 AADT = 9,400 (2040)
 RDS = 30 MPH

IH-43 NB
 AADT = 39,900 (2001)
 AADT = 41,550 (2040)
 RDS = 70 MPH

IH-43 SB
 AADT = 41,550 (2001)
 AADT = 41,550 (2040)
 RDS = 70 MPH

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.
 ALL DIMENSIONS ARE IN FEET AND INCHES UNLESS OTHERWISE NOTED.
 COORDINATES ON THIS PLAN ARE REFERENCED TO THE WISCONSIN COUNTY COORDINATE SYSTEM (WCCS), MILWAUKEE COUNTY, NAD 83 (2007). ALL STATIONS AND ELEVATIONS ARE IN FEET.
 ELEVATIONS ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM NAVD 88 (2007).
 AT THE BACKFACE OF THE ABUTMENTS ALL VOLUME WHICH CANNOT BE PLACED BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH BACKFILL STRUCTURE.
 THE EXISTING GROUNDLINE SHALL BE THE UPPER LIMITS OF EXCAVATION FOR STRUCTURES BRIDGES B-40-917.
 BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.
 ALL REINFORCING BARS ARE ENGLISH. THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE. BAR DIMENSIONS ARE OUT TO OUT.
 BEVEL ALL EXPOSED EDGES OF CONCRETE 3/4" UNLESS OTHERWISE NOTED.
 THE HAUNCH CONCRETE QUANTITY IS BASED ON THE AVERAGE HAUNCH SHOWN ON THE PRESTRESSED ORDER DETAILS SHEET.
 EXISTING BRIDGE B-40-149 TO BE REMOVED IS A THREE SPAN CONCRETE VOTED SLAB SUPPORTED ON CONCRETE PIERS AND ABUTMENTS. LENGTH IS APPROXIMATELY 145' BACKFACE TO BACKFACE OF THE WEST ABUTMENT. APPROXIMATELY 350' LONG. A 360' LONG CAST-IN-PLACE CONCRETE WALL FOUNDED ON SPREAD FOOTINGS SOUTH OF THE WEST ABUTMENT WALL.
 COORDINATE THE REMOVAL OF B-40-149, REMOVAL OF R-40-30, AND CONSTRUCTION OF NEW BRIDGE B-40-917 WITH RETAINING WALLS R-40-641 AND R-40-642 AND WITH NEW STORM SEWERS. SEE R-40-641 AND R-40-642 PLANS FOR CONSTRUCTION SEQUENCE INFORMATION.
 PROTECTIVE SURFACE TREATMENT SHALL BE APPLIED TO THE FOLLOWING COMPLETED SURFACES:
 - TOP OF DECK SLAB SURFACES
 - PAVING NOTCH (PRIOR TO PLACING APPROACH PAVEMENT)
 PIGMENTED SURFACE SEALER SHALL BE APPLIED TO THE FOLLOWING COMPLETED SURFACES:
 - TOP AND INSIDE FACES OF PARAPETS
 ELASTOMERIC BEARING PADS NEED NOT BE INDIVIDUALLY MOLDED PROVIDED THE CUT EDGES ARE SOUTH AND TRUE.
 PILE SPLICES SHALL BE MADE BY A CERTIFIED WELDER, PER AWS D11.
 JOINT FILLER SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M153 TYPE 4.2, OR 3, OR AASHTO M213.
 SEAL ALL EXPOSED HORIZONTAL AND VERTICAL SURFACES OF 1/2" JOINT FILLER WITH NON-STAINING, NON-ASPHALTIC JOINT SEALER 1" DEEP & HOLD 1/8" BELOW SURFACE OF CONCRETE. COLOR TO MATCH ADJACENT SURFACES.
 THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH SLOPE PAVING MATERIAL TO THE EXTENT SHOWN ON THE GENERAL PLAN & ELEVATION SHEET AND ON THE SLOPE PAVING CRUSHED AGGREGATE ORDER DETAILS SHEET.
 THE UTILITY INFORMATION SHOWN ON THESE DRAWINGS CONCERNING TYPE AND LOCATION OF UTILITIES IS FOR INFORMATION ONLY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING HIS OWN DETERMINATION AS TO TYPE AND LOCATION OF UNDERGROUND UTILITIES AS MAY BE NECESSARY TO AVOID DAMAGE.
 NAME PLATE SHALL BE CONSIDERED INCIDENTAL TO ITEM 502.0100 "CONCRETE MASONRY BRIDGES". FABRICATE IN ACCORDANCE TO S.D.D. 12.A 3-10.

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 357
 March 6, 2018

William C. Decker
 03/05/18



1 31/18	ADDENDUM 1: SLOPE PAVING TYPE	HDA
NO.	DATE	REVISION
STATE OF WISCONSIN		
DEPARTMENT OF TRANSPORTATION		
STRUCTURE B-40-917		
BY	DATE	REVISION
HDA		
EJH		
QUANTITIES, NOTES & DESIGN DATA		
SHEET 3 OF 30		357






PLOT NAME : sfiles

PLOT BY : hndcrs

FILE NAME : \\N:\MHW00\443\Design\Plans\12290401\DesIgn\Plans\12290401.M11\wccs\Structures\1228-16-01 Green Tree\B-40-917\cadd\Bridges\2-26-2018 11:06:17 AM

Addendum No. 01
ID 1228-16-71
Revised Sheet 384
March 6, 2018

STATE PROJECT NUMBER 1228-16-71	
NO.	DATE
1	3/1/18
ADDENDUM 1	SLOPE PAVING TYPE
HDA	HDA
REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
STRUCTURE B-40-917	
PLAN	MSS
DATE	PKGS.
3-1-2018	30
SLOPE PAVING CRUSHED AGGREGATE SPECIAL	
SHEET 30 OF 30 384	



William C. Decker, SR.
303/0518
HEATHER D. ANDERS, PE
303/41-008
CEDARBURG, WI
3-1-2018
PROFESSIONAL ENGINEER
WISCONSIN

FILE NAME : \\\M:\M100\143\Des\gn\Plans\12290401\Des\gn\12290401.M1\w.c.decker\Structures\1228-16-01 Green Tree\B-40-917\cds\B917_080602.B\lps\pwr\eg\cds\egp18 11:06:19 AM PLOT BY : HAnders


PLOT NAME : #FILE8

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 408
 March 6, 2018

Project ID: 1228-16-71
 Division 3: IH-43 Median and NB Outside Shoulder

STATION	Distance	Area (SF)		Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)		Mass Ordinate
		Cut	Fill	Cut	EBS	Fill	Cut	Fill	
1130+32	77	22.20	0.00	0.0	0.0	0.0	0.0	0.0	0.0
1130+50	18	185.35	0.00	68.8	6.9	0.0	68.8	0.0	69
1130+75	25	274.99	0.00	213.1	21.3	0.0	281.9	0.0	282
1131+00	25	291.39	0.00	262.2	26.2	0.0	544.1	0.0	544
1131+25	25	310.26	0.00	278.5	27.9	0.0	822.7	0.0	823
1131+50	25	297.42	0.00	281.3	28.1	0.0	1,104.0	0.0	1,104
1132+00	50	223.38	0.00	482.2	48.2	0.0	1,586.2	0.0	1,586
1132+25	25	56.12	1.54	129.4	12.9	0.7	1,715.6	0.7	1,715
1132+50	25	42.34	9.07	45.6	4.6	4.9	1,761.2	5.6	1,756
1132+76	26	48.70	0.00	43.8	4.4	4.4	1,805.0	10.0	1,795
1133+00	24	32.34	0.00	36.0	3.6	0.0	1,841.1	10.0	1,831
1133+19	19	13.99	0.00	16.6	1.7	0.0	1,857.7	10.0	1,848
				2,340.6	234.1	10.0			

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 440
 March 6, 2018




PROJECT NO: 1228-16-71
 COUNTY: MILWAUKEE
 HWY: IH-43
 CROSS SECTIONS: I-43
 SHEET 440
 E

FILE NAME: F:\DESIGN\PLANS\122801\SHRETS\PLAN\122801\MILWAUKEE\GREEN\TREE\000003_XS_143.DWG
 LAYOUT NAME: 000145_XS

PLOT DATE: 2/26/2018 12:16 PM
 PLOT BY: ANDREW ROSEMBER
 PLOT NAME: I-43

PLOT SCALE: 1"=20' HORIZ. / 1"=20' VERT.
 WINDOUCADISSHEET 69


Addendum No. 01
 ID 1228-16-71
 Revised Sheet 441
 March 6, 2018



PROJECT NO: 1228-16-71
 COUNTY: MILWAUKEE
 HWY: IH-43
 CROSS SECTIONS: I-43
 SHEET 441
 E

FILENAME: F:\DESIGN\PLANS\122801\SHRETS\PLAN\122801L_MILWAUKEE_GREEN_TREE\060603_XS_143.DWG
 LAYOUT NAME: 060106_XS
 PLOT DATE: 2/26/2018 12:12 PM
 PLOT BY: ANDREW ROSEMEYER
 PLOT NAME:
 PLOT SCALE: 1 IN=20 FT HORIZ. / 1 IN=20 FT VERT.
 WINDOUCADISSHEET 69


Addendum No. 01
 ID 1228-16-71
 Revised Sheet 442
 March 6, 2018



PROJECT NO: 1228-16-71
 COUNTY: MILWAUKEE
 HWY: IH-43
 CROSS SECTIONS: I-43
 SHEET 442
 E

FILENAME: F:\DESIGN\PLANS\122801\SHRETS\PLAN\122801L_MILWAUKEE_GREEN_TREE\060603_XS_143.DWG
 LAYOUT NAME: 06017_XS
 PLOT DATE: 2/26/2018 12:11 PM
 PLOT BY: ANDREW ROSEMBER
 PLOT NAME: ANDREW ROSEMBER
 PLOT SCALE: 1 IN=20 FT HORIZ. / 1 IN=20 FT VERT.
 WISDOT/CADDIS SHEET 69

Addendum No. 01
 ID 1228-16-71
 Revised Sheet 443
 March 6, 2018



PROJECT NO: 1228-16-71
 COUNTY: MILWAUKEE
 HWY: IH-43
 CROSS SECTIONS: I-43
 SHEET 443
 E

FILENAME: F:\DISIGN\PLANS\122801\SHRETS\PLAN\12280401_MILWAUKEE_GREEN_TREX\060603_XS_143.DWG
 LAYOUT NAME: 060108_XS

PLOT DATE: 2/26/2018 12:09 PM
 PLOT BY: ANDREW ROSEMBER
 PLOT NAME:

PLOT SCALE: 1"=20' HORIZ. / 1"=20' VERT.
 WSDOT/CADDIS SHEET 69



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	108.4400 CPM Progress Schedule	1.000 EACH	_____.	_____.
0004	201.0105 Clearing	18.000 STA	_____.	_____.
0006	201.0205 Grubbing	18.000 STA	_____.	_____.
0008	203.0200 Removing Old Structure (station) 01. 40GT+00	LS	LUMP SUM	_____.
0010	203.0200 Removing Old Structure (station) 02. 14RWW+00	LS	LUMP SUM	_____.
0012	203.0210.S Abatement of Asbestos Containing Material (structure) 01. R-40-30	LS	LUMP SUM	_____.
0014	204.0100 Removing Pavement	4,366.000 SY	_____.	_____.
0016	204.0150 Removing Curb & Gutter **P**	4,471.000 LF	_____.	_____.
0018	204.0157 Removing Concrete Barrier	637.000 LF	_____.	_____.
0020	204.0165 Removing Guardrail **P**	680.000 LF	_____.	_____.
0022	204.0170 Removing Fence	597.000 LF	_____.	_____.
0024	204.0195 Removing Concrete Bases	5.000 EACH	_____.	_____.
0026	204.0210 Removing Manholes	5.000 EACH	_____.	_____.
0028	204.0220 Removing Inlets	17.000 EACH	_____.	_____.
0030	204.0245 Removing Storm Sewer (size) 01. 12- Inch	189.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	204.0245 Removing Storm Sewer (size) 02. 15-Inch	359.000 LF	_____.	_____.
0034	204.0245 Removing Storm Sewer (size) 03. 36-Inch	90.000 LF	_____.	_____.
0036	204.9060.S Removing (item description) 20. Ramp Control Signal Assembly Sidemount	2.000 EACH	_____.	_____.
0038	205.0100 Excavation Common	16,132.000 CY	_____.	_____.
0040	206.1000 Excavation for Structures Bridges (structure) 01. B-40-917	LS	LUMP SUM	_____.
0042	206.3000 Excavation for Structures Retaining Walls (structure) 01. R-40-641	LS	LUMP SUM	_____.
0044	206.3000 Excavation for Structures Retaining Walls (structure) 02. R-40-642	LS	LUMP SUM	_____.
0046	208.0100 Borrow	3,307.000 CY	_____.	_____.
0048	209.0300.S Backfill Coarse Aggregate (size) 04. No. 1	74.000 CY	_____.	_____.
0050	210.1500 Backfill Structure Type A	2,083.000 TON	_____.	_____.
0052	213.0100 Finishing Roadway (project) 05. 1228-16-71	1.000 EACH	_____.	_____.
0054	305.0110 Base Aggregate Dense 3/4-Inch	37.000 TON	_____.	_____.
0056	305.0120 Base Aggregate Dense 1 1/4-Inch	9,449.000 TON	_____.	_____.
0058	311.0110 Breaker Run	5,704.000 TON	_____.	_____.
0060	312.0110 Select Crushed Material	173.000 TON	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	415.0100 Concrete Pavement 10-Inch	86.000 SY	_____	_____
0066	416.0170 Concrete Driveway 7-Inch	53.000 SY	_____	_____
0068	416.0610 Drilled Tie Bars	65.000 EACH	_____	_____
0070	416.1110 Concrete Shoulder Rumble Strips	1,400.000 LF	_____	_____
0072	440.4410 Incentive IRI Ride	2,503.000 DOL	1.00000	2,503.00
0074	450.4000 HMA Cold Weather Paving	300.000 TON	_____	_____
0076	455.0605 Tack Coat	927.000 GAL	_____	_____
0078	460.2000 Incentive Density HMA Pavement	2,978.000 DOL	1.00000	2,978.00
0080	460.6223 HMA Pavement 3 MT 58-28 S	2,307.000 TON	_____	_____
0082	460.6224 HMA Pavement 4 MT 58-28 S	1,558.000 TON	_____	_____
0084	465.0120 Asphaltic Surface Driveways and Field Entrances	47.000 TON	_____	_____
0086	495.1000.S Cold patch	20.000 TON	_____	_____
0088	502.0100 Concrete Masonry Bridges **P**	949.000 CY	_____	_____
0090	502.3200 Protective Surface Treatment **P**	1,578.000 SY	_____	_____
0092	502.3210 Pigmented Surface Sealer	200.000 SY	_____	_____
0094	503.0146 Prestressed Girder Type I 45W-Inch **P**	1,933.000 LF	_____	_____



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	505.0400 Bar Steel Reinforcement HS Structures **P**	17,270.000 LB	_____.	_____.
0098	505.0600 Bar Steel Reinforcement HS Coated Structures **P**	159,280.000 LB	_____.	_____.
0100	506.0605 Structural Steel HS	38,110.000 LB	_____.	_____.
0102	506.2605 Bearing Pads Elastomeric Non- Laminated **P**	36.000 EACH	_____.	_____.
0104	506.4000 Steel Diaphragms (structure) 01. B-40- 917 **P**	32.000 EACH	_____.	_____.
0106	511.1200 Temporary Shoring (structure) 01. B-40- 917	2,340.000 SF	_____.	_____.
0108	511.1200 Temporary Shoring (structure) 02. R-40- 642	920.000 SF	_____.	_____.
0110	511.1200 Temporary Shoring (structure) 03. R-40- 641	1,520.000 SF	_____.	_____.
0112	512.0500 Piling Steel Sheet Permanent Delivered	17,040.000 SF	_____.	_____.
0114	512.0600 Piling Steel Sheet Permanent Driven	17,040.000 SF	_____.	_____.
0116	513.4091 Railing Tubular Screening (structure) 01. B-40-917	475.000 LF	_____.	_____.
0118	516.0500 Rubberized Membrane Waterproofing **P**	30.000 SY	_____.	_____.
0120	517.0600 Painting Epoxy System (structure) 01. R- 40-641	LS	LUMP SUM	_____.
0122	517.0600 Painting Epoxy System (structure) 02. R- 40-642	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0124	520.8000 Concrete Collars for Pipe	4.000 EACH	_____.	_____.
0126	550.2166 Piling CIP Concrete 16 X 0.375-Inch	3,390.000 LF	_____.	_____.
0128	601.0105 Concrete Curb Type A	67.000 LF	_____.	_____.
0130	601.0411 Concrete Curb & Gutter 30-Inch Type D	2,808.000 LF	_____.	_____.
0132	602.0410 Concrete Sidewalk 5-Inch	6,788.000 SF	_____.	_____.
0134	602.0515 Curb Ramp Detectable Warning Field Natural Patina	52.000 SF	_____.	_____.
0136	602.0615 Curb Ramp Detectable Warning Field Radial Natural Patina	108.000 SF	_____.	_____.
0138	603.1142 Concrete Barrier Type S42 **P**	2,034.000 LF	_____.	_____.
0140	603.1442 Concrete Barrier Type S42C **P**	1,727.000 LF	_____.	_____.
0142	603.8000 Concrete Barrier Temporary Precast Delivered	3,986.000 LF	_____.	_____.
0144	603.8125 Concrete Barrier Temporary Precast Installed	4,361.000 LF	_____.	_____.
0148	608.0312 Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	369.000 LF	_____.	_____.
0150	608.0315 Storm Sewer Pipe Reinforced Concrete Class III 15-Inch	552.000 LF	_____.	_____.
0152	608.0318 Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	248.000 LF	_____.	_____.
0154	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	121.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0156	608.0330 Storm Sewer Pipe Reinforced Concrete Class III 30-Inch	34.000 LF	_____.	_____.
0158	608.0336 Storm Sewer Pipe Reinforced Concrete Class III 36-Inch	108.000 LF	_____.	_____.
0160	608.0430 Storm Sewer Pipe Reinforced Concrete Class IV 30-Inch	286.000 LF	_____.	_____.
0162	611.0420 Reconstructing Manholes	4.000 EACH	_____.	_____.
0164	611.0530 Manhole Covers Type J	2.000 EACH	_____.	_____.
0166	611.0535 Manhole Covers Type J-Special	8.000 EACH	_____.	_____.
0168	611.0606 Inlet Covers Type B	1.000 EACH	_____.	_____.
0170	611.0610 Inlet Covers Type BW	13.000 EACH	_____.	_____.
0172	611.0624 Inlet Covers Type H	9.000 EACH	_____.	_____.
0174	611.0642 Inlet Covers Type MS	3.000 EACH	_____.	_____.
0176	611.0651 Inlet Covers Type S	1.000 EACH	_____.	_____.
0178	611.0654 Inlet Covers Type V	1.000 EACH	_____.	_____.
0180	611.1005 Catch Basins 5-FT Diameter	3.000 EACH	_____.	_____.
0182	611.1006 Catch Basins 6-FT Diameter	1.000 EACH	_____.	_____.
0184	611.2004 Manholes 4-FT Diameter	6.000 EACH	_____.	_____.
0186	611.2005 Manholes 5-FT Diameter	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0188	611.2006 Manholes 6-FT Diameter	3.000 EACH	_____.	_____.
0190	611.2007 Manholes 7-FT Diameter	1.000 EACH	_____.	_____.
0192	611.3220 Inlets 2x2-FT	1.000 EACH	_____.	_____.
0194	611.3225 Inlets 2x2.5-FT	10.000 EACH	_____.	_____.
0196	611.3230 Inlets 2x3-FT	5.000 EACH	_____.	_____.
0198	611.3901 Inlets Median 1 Grate	3.000 EACH	_____.	_____.
0200	611.8115 Adjusting Inlet Covers	3.000 EACH	_____.	_____.
0202	611.9900.S Drain Slotted Vane	2.000 EACH	_____.	_____.
0204	612.0206 Pipe Underdrain Unperforated 6-Inch	370.000 LF	_____.	_____.
0206	612.0406 Pipe Underdrain Wrapped 6-Inch	2,685.000 LF	_____.	_____.
0208	614.0905 Crash Cushions Temporary	5.000 EACH	_____.	_____.
0210	614.0920 Salvaged Rail	89.000 LF	_____.	_____.
0212	614.0950 Replacing Guardrail Posts and Blocks	25.000 EACH	_____.	_____.
0214	614.0951 Replacing Guardrail Rail and Hardware	89.000 LF	_____.	_____.
0216	614.1100 MGS Guardrail Temporary Thrie Beam Transition **P**	99.000 LF	_____.	_____.
0218	614.2300 MGS Guardrail 3	25.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0220	614.2620 MGS Guardrail Terminal Type 2	2.000 EACH	_____.	_____.
0222	616.0206 Fence Chain Link 6-FT	985.000 LF	_____.	_____.
0224	616.0600.S Fence Temporary	183.000 LF	_____.	_____.
0226	616.0700.S Fence Safety	365.000 LF	_____.	_____.
0228	618.0100 Maintenance And Repair of Haul Roads (project) 06. 1228-16-71	1.000 EACH	_____.	_____.
0230	619.1000 Mobilization	1.000 EACH	_____.	_____.
0232	623.0200 Dust Control Surface Treatment	13,800.000 SY	_____.	_____.
0234	624.0100 Water	140.000 MGAL	_____.	_____.
0236	625.0500 Salvaged Topsoil	8,898.000 SY	_____.	_____.
0238	627.0200 Mulching	451.000 SY	_____.	_____.
0240	628.1104 Erosion Bales	30.000 EACH	_____.	_____.
0242	628.1504 Silt Fence	1,405.000 LF	_____.	_____.
0244	628.1520 Silt Fence Maintenance	1,405.000 LF	_____.	_____.
0246	628.1905 Mobilizations Erosion Control	7.000 EACH	_____.	_____.
0248	628.1910 Mobilizations Emergency Erosion Control	8.000 EACH	_____.	_____.
0250	628.2002 Erosion Mat Class I Type A	4,016.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0252	628.2006 Erosion Mat Urban Class I Type A	2,778.000 SY	_____.	_____.
0254	628.2023 Erosion Mat Class II Type B	3,073.000 SY	_____.	_____.
0256	628.6510 Soil Stabilizer Type B	0.250 ACRE	_____.	_____.
0258	628.7005 Inlet Protection Type A	28.000 EACH	_____.	_____.
0260	628.7020 Inlet Protection Type D	44.000 EACH	_____.	_____.
0262	628.7504 Temporary Ditch Checks	35.000 LF	_____.	_____.
0264	628.7560 Tracking Pads	3.000 EACH	_____.	_____.
0266	628.7570 Rock Bags	30.000 EACH	_____.	_____.
0268	629.0210 Fertilizer Type B	11.000 CWT	_____.	_____.
0270	630.0120 Seeding Mixture No. 20	285.000 LB	_____.	_____.
0272	630.0200 Seeding Temporary	109.000 LB	_____.	_____.
0274	633.0200 Delineators Flexible **P**	59.000 EACH	_____.	_____.
0276	634.0612 Posts Wood 4x6-Inch X 12-FT	22.000 EACH	_____.	_____.
0278	634.0618 Posts Wood 4x6-Inch X 18-FT	17.000 EACH	_____.	_____.
0280	634.0816 Posts Tubular Steel 2x2-Inch X 16-FT	28.000 EACH	_____.	_____.
0282	635.0200 Sign Supports Structural Steel HS	1,000.000 LB	_____.	_____.
0284	636.0100 Sign Supports Concrete Masonry	1.600 CY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0286	636.0500 Sign Supports Steel Reinforcement	98.000 LB	_____.	_____.
0288	637.2210 Signs Type II Reflective H	256.400 SF	_____.	_____.
0290	637.2230 Signs Type II Reflective F	91.500 SF	_____.	_____.
0292	638.2101 Moving Signs Type I	1.000 EACH	_____.	_____.
0294	638.2102 Moving Signs Type II	3.000 EACH	_____.	_____.
0296	638.2601 Removing Signs Type I	1.000 EACH	_____.	_____.
0298	638.2602 Removing Signs Type II	49.000 EACH	_____.	_____.
0300	638.3000 Removing Small Sign Supports	45.000 EACH	_____.	_____.
0302	638.3100 Removing Structural Steel Sign Supports	2.000 EACH	_____.	_____.
0304	643.0300 Traffic Control Drums	23,065.000 DAY	_____.	_____.
0306	643.0410 Traffic Control Barricades Type II	2,460.000 DAY	_____.	_____.
0308	643.0420 Traffic Control Barricades Type III	6,350.000 DAY	_____.	_____.
0310	643.0705 Traffic Control Warning Lights Type A	12,330.000 DAY	_____.	_____.
0312	643.0715 Traffic Control Warning Lights Type C	1,980.000 DAY	_____.	_____.
0314	643.0800 Traffic Control Arrow Boards	260.000 DAY	_____.	_____.
0316	643.0900 Traffic Control Signs	27,260.000 DAY	_____.	_____.
0318	643.0920 Traffic Control Covering Signs Type II	36.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0320	643.1000 Traffic Control Signs Fixed Message	237.300 SF	_____.	_____.
0322	643.1050 Traffic Control Signs PCMS	375.000 DAY	_____.	_____.
0324	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0326	645.0111 Geotextile Type DF Schedule A	155.000 SY	_____.	_____.
0328	645.0120 Geotextile Type HR	67.000 SY	_____.	_____.
0330	646.1020 Marking Line Epoxy 4-Inch **P**	4,019.000 LF	_____.	_____.
0332	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch **P**	7,522.000 LF	_____.	_____.
0334	646.1555 Marking Line Grooved Contrast Permanent Tape 4-Inch	897.000 LF	_____.	_____.
0336	646.3555 Marking Line Grooved Contrast Permanent Tape 8-Inch	1,729.000 LF	_____.	_____.
0338	646.5020 Marking Arrow Epoxy	2.000 EACH	_____.	_____.
0340	646.5220 Marking Symbol Epoxy	4.000 EACH	_____.	_____.
0342	646.6120 Marking Stop Line Epoxy 18-Inch **P**	95.000 LF	_____.	_____.
0344	646.7120 Marking Diagonal Epoxy 12-Inch **P**	265.000 LF	_____.	_____.
0346	646.7220 Marking Chevron Epoxy 24-Inch **P**	186.000 LF	_____.	_____.
0348	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch **P**	172.000 LF	_____.	_____.
0350	646.9000 Marking Removal Line 4-Inch	4,307.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0352	646.9100 Marking Removal Line 8-Inch	166.000 LF	_____.	_____.
0354	646.9300 Marking Removal Special Marking	4.000 EACH	_____.	_____.
0356	649.0150 Temporary Marking Line Removable Tape 4-Inch	18,613.000 LF	_____.	_____.
0358	649.0760 Temporary Marking Raised Pavement Marker Type I	169.000 EACH	_____.	_____.
0360	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch **P**	1,495.000 LF	_____.	_____.
0362	652.0615 Conduit Special 3-Inch **P**	190.000 LF	_____.	_____.
0364	652.0700.S Install Conduit into Existing Item	6.000 EACH	_____.	_____.
0366	653.0140 Pull Boxes Steel 24x42-Inch	6.000 EACH	_____.	_____.
0368	653.0905 Removing Pull Boxes	4.000 EACH	_____.	_____.
0370	654.0101 Concrete Bases Type 1	2.000 EACH	_____.	_____.
0372	654.0108 Concrete Bases Type 8	3.000 EACH	_____.	_____.
0374	655.0210 Cable Traffic Signal 3-14 AWG **P**	670.000 LF	_____.	_____.
0376	655.0240 Cable Traffic Signal 7-14 AWG **P**	100.000 LF	_____.	_____.
0378	655.0510 Electrical Wire Traffic Signals 12 AWG **P**	4,005.000 LF	_____.	_____.
0380	655.0610 Electrical Wire Lighting 12 AWG **P**	522.000 LF	_____.	_____.
0382	655.0615 Electrical Wire Lighting 10 AWG **P**	210.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0384	655.0620 Electrical Wire Lighting 8 AWG **P**	5,180.000 LF	_____.	_____.
0386	655.0700 Loop Detector Lead In Cable **P**	450.000 LF	_____.	_____.
0388	657.0100 Pedestal Bases	2.000 EACH	_____.	_____.
0390	657.0420 Traffic Signal Standards Aluminum 13-FT	2.000 EACH	_____.	_____.
0392	658.0172 Traffic Signal Face 2S 12-Inch	2.000 EACH	_____.	_____.
0394	658.0173 Traffic Signal Face 3S 12-Inch	2.000 EACH	_____.	_____.
0396	670.0100 Field System Integrator	LS	LUMP SUM	_____.
0398	670.0200 ITS Documentation	LS	LUMP SUM	_____.
0400	671.0132 Conduit HDPE 3-Duct 2-Inch **P**	2,670.000 LF	_____.	_____.
0402	671.0232 Conduit HDPE Directional Bore 3-Duct 2-Inch **P**	535.000 LF	_____.	_____.
0404	671.0300 Fiber Optic Cable Marker	9.000 EACH	_____.	_____.
0406	673.0105 Communication Vault Type 1	3.000 EACH	_____.	_____.
0408	674.0200 Cable Microwave Detector **P**	155.000 LF	_____.	_____.
0410	674.0300 Remove Cable **P**	4,015.000 LF	_____.	_____.
0412	678.0072 Install Fiber Optic Cable Outdoor Plant 72-CT **P**	4,255.000 LF	_____.	_____.
0414	678.0300 Fiber Optic Splice	72.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0416	678.0400 Fiber Optic Termination	72.000 EACH	_____.	_____.
0418	678.0500 Communication System Testing	LS	LUMP SUM	_____.
0420	690.0150 Sawing Asphalt	2,855.000 LF	_____.	_____.
0422	690.0250 Sawing Concrete	355.000 LF	_____.	_____.
0424	715.0502 Incentive Strength Concrete Structures	5,694.000 DOL	1.00000	5,694.00
0426	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,400.000 HRS	5.00000	12,000.00
0428	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	3,600.000 HRS	5.00000	18,000.00
0430	SPV.0045 Special 01. Portable Speed Trailer	245.000 DAY	_____.	_____.
0432	SPV.0060 Special 02. Tieback Anchors	112.000 EACH	_____.	_____.
0434	SPV.0060 Special 03. Tieback Anchors Performance Tests	7.000 EACH	_____.	_____.
0436	SPV.0060 Special 04. Tieback Anchors Extended Creep Tests	4.000 EACH	_____.	_____.
0438	SPV.0060 Special 05. Pile Dynamic Analyzer (PDA) Testing	8.000 EACH	_____.	_____.
0440	SPV.0060 Special 06. Pile Dynamic Analyzer (PDA) Restrikes	8.000 EACH	_____.	_____.
0442	SPV.0060 Special 07. Case Pile Wave Analysis Program (CAPWAP) Evaluation	3.000 EACH	_____.	_____.
0444	SPV.0060 Special 08. Adjusting Sanitary Manhole	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0446	SPV.0060 Special 09. Reconstruct Sanitary Manhole	3.000 EACH	_____.	_____.
0448	SPV.0060 Special 10. Field Facility Office Space	1.000 EACH	_____.	_____.
0450	SPV.0060 Special 11. Inlet Cover Repair Maintenance Special	2.000 EACH	_____.	_____.
0452	SPV.0060 Special 21. Lamp Disposal High Intensity Discharge	3.000 EACH	_____.	_____.
0454	SPV.0060 Special 22. Lighting Units Salvaged	3.000 EACH	_____.	_____.
0456	SPV.0075 Special 01. Pavement Cleanup Project (1228-16-71)	250.000 HRS	_____.	_____.
0458	SPV.0075 Special 02. Flagging Special	264.000 HRS	_____.	_____.
0460	SPV.0090 Special 01. Concrete Barrier Temporary Precast Left In Place	862.000 LF	_____.	_____.
0462	SPV.0090 Special 04. Concrete Curb & Gutter SHES 30-Inch Type D	153.000 LF	_____.	_____.
0464	SPV.0105 Special 01. Survey Project 1228-16-71	LS	LUMP SUM	_____.
0466	SPV.0105 Special 02. Structure Modification MMSD DC0406	LS	LUMP SUM	_____.
0468	SPV.0105 Special 03. Maintenance of Lighting System	LS	LUMP SUM	_____.
0470	SPV.0165 Special 01. Salvage and Replace Brick Pavers	43.000 SF	_____.	_____.
0472	SPV.0180 Special 01. Geogrid Reinforcement	260.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180313012 Project(s): 1228-16-71

Federal ID(s): WISC 2018142

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0474	SPV.0195 Special 01. Excavation, Hauling, and Disposal of Creosote Contaminated Soil	2,110.000 TON	_____.	_____.
0476	201.0120 Clearing	24.000 ID	_____.	_____.
0478	201.0220 Grubbing	24.000 ID	_____.	_____.
0480	204.0155 Removing Concrete Sidewalk	700.000 SY	_____.	_____.
0482	204.0280 Sealing Pipes	3.000 EACH	_____.	_____.
0484	204.9090.S Removing (item description) 01. Electrical Wires from Conduit	250.000 LF	_____.	_____.
0486	204.9105.S Removing (item description) 01. Nicolet Ped Tunnel Entrances	LS	LUMP SUM	_____.
0488	209.0200.S Backfill Controlled Low Strength	22.000 CY	_____.	_____.
0490	416.1715 Concrete Pavement Repair SHES	33.000 SY	_____.	_____.
0492	SPV.0035 Special 01. Flowable Fill	380.000 CY	_____.	_____.
0494	SPV.0135 Special 01. Vibration Monitoring	7.000 MON	_____.	_____.
0496	SPV.0180 Special 02. Slope Paving Crushed Aggregate Special	770.000 SY	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.