



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

March 12, 2018

### NOTICE TO ALL CONTRACTORS:

**Proposal #31: 4321-03-71**  
**V Reedsville, 4<sup>th</sup> St**  
**Mud Creek Bridge**  
**Loc Str**  
**Manitowoc County**

### Letting of March 13, 2018

This is Addendum No. 01

### Special Provisions:

Revised Special Provisions	
Article No.	Description
27	Streambed Material, Item SPV.0035.01.

### Special Provisions

#### 27. Streambed Material, Item SPV.0035.01.

Replace entire section titled **B Materials** with the following:

#### **B Materials**

Streambed Material shall be naturally occurring pit run material conforming to the material specified in Section 313 of the Standard Specification, with at least 50 percent by weight retained on the 1" sieve, with the remaining material composed of pebble and sand. The maximum size of an individual piece cannot be larger than 2 ½ inches. Material shall be washed to remove silt/clay either prior to placement or after placement as described in section C (Construction) of this specification.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

