



Wisconsin Department of Transportation

April 5, 2018

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #18: 8120-04-73, WISC 2018 199
C Rice Lake, Knapp Street
Bear Paw Avenue to Hammond Avenue
STH 48
Barron County

8120-04-74, WISC 2018 200
C Rice Lake, Knapp Street
CTH SS East Junction Intersection
STH 48
Barron County

8120-04-75, WISC 2018 201
C Rice Lake, Knapp Street
Wisconsin Avenue Intersection
STH 48
Barron County

Letting of April 10, 2018

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
455.0605	Tack Coat	GAL	3404	107	3511
460.6445	HMA Pavement 5 MT 58-34 H	TON	4,082	130	4,212

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0120	Removing Asphaltic Surface Milling	SY	0	780	780
440.4410	Incentive IRI Ride	DOL	0	6000	6000

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
79	Miscellaneous Quantities (Removing Asphaltic Surface Table Added)
81	Miscellaneous Quantities (HMA & Tack Coat updated)

Schedule of Items

Attached, dated April 5, 2018, are the revised Schedule of Items Pages 2 and 12.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 79 and 81.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 02
ID 8120-04-73
Revised Sheet 79
April 5, 2018

REMOVING ASPHALTIC SURFACE MILLING

204.0120		REMOVING ASPHALTIC SURFACE MILLING		
CATEGORY	STAGE	STA	LT/RT	SY
0010	2	41+35	46+46	420
SUBTOTAL		0010		420
0010	3	41+35	46+46	360
SUBTOTAL		0010		360
TOTAL				780

REMOVING CONCRETE

204.0100		REMOVING CONCRETE	
CATEGORY	STAGE	LOCATION	SY
0010	1B	0+30NS - 0+60NS	15
SUBTOTAL			15
0040		WATERMAIN	450
SUBTOTAL			450
TOTAL			465

BASE AGGREGATE

208.1100		305.0120		305.0110	
CATEGORY	STAGE	STATION	LT/RT	TON	TON
0010	2	41+35	47+50	-	9
		47+50	55+00	2	1
		55+00	62+50	6	-
		62+50	70+00	62	-
		70+00	77+50	27	-
		77+50	END	2	-
TURN LANE					
		63+60	67+15	57	-
SUBTOTAL				93	10
0010	3	41+35	47+50	-	9
		47+50	55+00	757	1
		55+00	62+50	782	-
		62+50	70+00	215	-
		70+00	77+50	356	-
		77+50	END	321	-
SUBTOTAL				0	2,431
0040	2/3	WATERMAIN		156	-
SUBTOTAL				0	156
TOTAL				93	2,743

REMOVING CONCRETE SURFACE PARTIAL DEPTH

204.0109.S		REMOVING CONCRETE SURFACE PARTIAL DEPTH		
CATEGORY	STAGE	STA	SF	
0010	2	41+35	47+50	14,542
		47+50	55+00	21,544
		55+00	62+50	17,765
		62+50	70+00	20,689
		70+00	77+50	19,795
		77+50	END	12,793
SUBTOTAL				107,128
0010	3	41+35	47+50	14,542
		47+50	55+00	18,416
		55+00	62+50	18,723
		62+50	70+00	19,710
		70+00	77+50	19,391
		77+50	END	17,817
SUBTOTAL				108,599
TOTAL				215,727

HMA PAVEMENT

CATEGORY	STAGE	STA	STA	LT/RT	SY	TON	HMA PAVEMENT	TACK COAT	CONCRETE BASE	REHEATING
		41+35	47+50	RT		187	5 MT 58-34 H	GAL	0	460.4110.S
0030	2	41+35	47+50	RT		187			0	
		SUBTOTAL		0030		187			0	
0010	2	41+35	47+50	RT		156		285		
		47+50	55+00	RT		403		336		
		55+00	62+50	RT		332		277		
		62+50	70+00	RT		408		340		
		70+00	77+50	RT		370		308		
		77+50	END	RT		239		200		
		SUBTOTAL		0010		1,908		1,746	0	
		SUBTOTAL		0010		1,908		1,746	0	
0010	3	41+35	47+50	LT		332		276		1,230
		47+50	55+00	LT		372		310		1,500
		55+00	62+50	LT		350		292		1,500
		62+50	70+00	LT		368		307		1,500
		70+00	77+50	LT		362		302		1,500
		77+50	END	LT		333		278		1,064
		SUBTOTAL		0010		2,117		1,765	8,294	
0040	2/3	WATERMAIN								
		SUBTOTAL		0010		0		0	0	
		SUBTOTAL		0010		4,212		3,511	8,294	
		SUBTOTAL		0010		4,212		3,511	8,294	

SURFACE PREPARATION

CATEGORY	STAGE	STA	STA	LT/RT	EACH	CONCRETE PAVEMENT REPAIR	CONCRETE PAVEMENT REPLACEMENT	ASPHALTIC SURFACE PATCHING	JOINT REPAIR	SPV. 0105.01 PREPARATION OF FOUNDATION FOR ASPHALTIC PAVING SPECIAL
		416.0610*	416.1710		416.1720	465.0110	509.1000			
0010	2	41+35	47+50	RT						
		47+50	55+00	RT				46		
		55+00	62+50	RT				68		
		62+50	70+00	RT				56		
		70+00	77+50	RT				65		
		77+50	END	RT				62		
		SUBTOTAL		0010		0	0	337	0	1
0010	3	41+35	47+50	RT				46		
		47+50	55+00	RT				59		
		55+00	62+50	RT				59		
		62+50	70+00	RT				62		
		70+00	77+50	RT				61		
		77+50	END	RT				56		
		SUBTOTAL		0010		0	0	343	0	0
		SUBTOTAL		0010		0	0	300	100	1
		SUBTOTAL		0010		50	600	300	680	100
		SUBTOTAL		0010		50	600	300	680	100
		SUBTOTAL		0010		50	600	300	680	100

Addendum No. 02
 ID 8120-04-73
 Revised Sheet 81
 April 5, 2018



Proposal Schedule of Items

Proposal ID: 20180410018 Project(s): 8120-04-73, 8120-04-74, 8120-04-75

Federal ID(s): WISC 2018199, WISC 2018200, WISC 2018201

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	416.0620 Drilled Dowel Bars	132.000 EACH	_____.	_____.
0036	416.1710 Concrete Pavement Repair	600.000 SY	_____.	_____.
0038	416.1720 Concrete Pavement Replacement	300.000 SY	_____.	_____.
0040	455.0605 Tack Coat	3,511.000 GAL	_____.	_____.
0042	460.2000 Incentive Density HMA Pavement	2,620.000 DOL	1.00000	2,620.00
0044	460.4110.S Reheating HMA Pavement Longitudinal Joints	8,294.000 LF	_____.	_____.
0046	460.6445 HMA Pavement 5 MT 58-34 H	4,212.000 TON	_____.	_____.
0048	465.0110 Asphaltic Surface Patching	680.000 TON	_____.	_____.
0050	465.0120 Asphaltic Surface Driveways and Field Entrances	88.000 TON	_____.	_____.
0052	465.0125 Asphaltic Surface Temporary	63.000 TON	_____.	_____.
0054	509.1000 Joint Repair	100.000 SY	_____.	_____.
0056	601.0409 Concrete Curb & Gutter 30-Inch Type A	1,919.000 LF	_____.	_____.
0058	601.0580 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type R	116.000 LF	_____.	_____.
0060	601.0600 Concrete Curb Pedestrian	134.000 LF	_____.	_____.
0062	602.0405 Concrete Sidewalk 4-Inch	520.000 SF	_____.	_____.
0064	602.0415 Concrete Sidewalk 6-Inch	16,910.000 SF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180410018 Project(s): 8120-04-73, 8120-04-74, 8120-04-75

Federal ID(s): WISC 2018199, WISC 2018200, WISC 2018201

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0344	SPV.0105 Special 06. Traffic Signal Controller and Cabinet Knapp St & Wisconsin Ave	LS	LUMP SUM	_____.
0346	204.0120 Removing Asphaltic Surface Milling	780.000 SY	_____.	_____.
0348	440.4410 Incentive IRI Ride	6,000.000 DOL	1.00000	6,000.00
Section: 0001			Total:	_____.
			Total Bid:	_____.