



# Wisconsin Department of Transportation

April 26, 2018

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #11: 1229-05-70, WISC 2018 237**  
**North South Freeway**  
**Sth 32 to North Ozaukee County Line**  
**IH 043**  
**Ozaukee County**

### Letting of May 8, 2018

This is Addendum No. 01, which provides for the following:

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
646.1555	Marking Line Grooved Contrast Permanent Tape 4-inch	LF	195,194	-146,561	48,633
646.3555	Marking Line Grooved Contrast Permanent Tape 8-inch	LF	24,985	-3,414	21,571

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
185	Misc. Quan. Sht. – Added location clarification for Item SPV.0085.01
193	Misc. Quan. Sht. – Revised quantity chart for Pavt. Marking Items 646.1555 & 646.3555

**Schedule of Items**

Attached, dated April 26, 2018, are the revised Schedule of Items Page 6.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 185, 193

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

Addendum No. 01  
ID 1229-05-70  
Revised Sheet 185  
April 26, 2018

SPECIAL (SEALING CRACKS AND JOINTS WITH HOT-APPLIED SEALANT)

SPV.0085.01  
SPECIAL (SEALING CRACKS  
AND JOINTS WITH HOT-  
APPLIED SEALANT)

CATEGORY	LOCATION	LB	REMARKS
0010	IH 43 NB & SB	228682	MAINLINE TRANSVERSE JOINTS IN THE EXISTING CONCRETE PAVEMENT AND THE LONGITUDINAL JOINT AT THE CENTERLINE
0010	UNDISTRIBUTED	228668	CRACKS IN THE CONCRETE PAVEMENT NOT LOCATED AT A CONCRETE JOINT
TOTAL 0010		251550	

NOTE: NO SEALANT SHOULD BE APPLIED AT THE LONGITUDINAL JOINT BETWEEN THE EDGE OF CONCRETE AND ASPHALT SHOULDER

CONCRETE ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	CONCRETE PAVEMENT REPAIR SHES	CONCRETE PAVEMENT REPLACEMENT SHES	CONTINUOUS DIAMOND GRINDING CONCRETE PAVEMENT	INCENTIVE IRI RIDE	DOL	EACH	MARKING REMOVAL	RAISED PAVEMENT MARKERS	SAWING CONCRETE	REMARKS
					SY	SY	SY						LF	
416.1715			416.1725		438	4327	57383				202	202	432	
	200+00	-	435+00	SB BEGIN PROJECT TO S OF STH 33	0	400	62162				264	264	780	
	435+00	-	620+00	SB S OF STH 33 TO W OF STH 32	48	549	35514				134	134	309	
	620+00	-	825+00	SB W OF STH 32 TO N OF LAKE DR	0	561	56674				235	235	155	
	825+00	-	977+29.01	SB N OF LAKE DR TO N OF CTH D	36	135	44667				186	186	217	
	977+29.01	-		SB N OF CTH D TO END PROJECT	16	261								
	200+00	-	435+00	NB BEGIN PROJECT TO S OF STH 33	0	329	51624				222	222	24	
	435+00	-	620+00	NB S OF STH 33 TO W OF STH 32	0	452	62649				300	300	614	
	620+00	-	825+00	NB W OF STH 32 TO N OF LAKE DR	0	225	37858				134	134	182	
	825+00	-	977+29.01	NB N OF LAKE DR TO N OF CTH D	0	631	56870				230	230	608	
	977+29.01	-		NB N OF CTH D TO END PROJECT	20	346	45485				161	161	278	
0010	PROJECT Undistributed				--	400	--		150000	--	--	--	--	
0010	TOTAL 0010				135	4327	510886		150000		2068		3599	

PAVEMENT MARKING

646.1040 646.1555 646.3555

CATEGORY	STATION	TO	STATION	LOCATION	MARKING LINE GROOVED WET REF EPOXY 4-INCH		MARKING LINE GROOVED CONTRAST PERMANENT TAPE 4-INCH		MARKING LINE GROOVED CONTRAST PERMANENT TAPE 8-INCH	
					WHITE LF	YELLOW LF	WHITE LF	WHITE LF	WHITE LF	WHITE LF
0010	829+70	-	854+50	SB-BEGIN PROJECT-CTHV/STH 32	1904	2377	620	-	-	-
0010	299+80	-	50+00	SB-ON RAMP FROM CTHV/STH 32	1828	1436	-	-	1314	-
0010	0+00	-	19+96.50	SB-OFF RAMP TO CTHV/STH 32	2548	1640	150	-	645	-
0010	854+50	-	220+00	SB-CTHV/STH 32-STH 33	14091	16228	-	-	-	-
0010	210+00	-	218+00	SB-ON RAMP FROM STH 33	2006	832	-	-	1273	-
0010	225+45.34	-	235+40	SB-OFF RAMP TO E STH 33	1504	763	-	-	1591	460
0010	237+97.04	-	288+20	SB-ON RAMP FROM 57 TO 43	897	-	-	-	1456	-
0010	220+00	-	451+80	STH 33-STH 32/CTH H	19168	22043	5694	-	-	-
0010	429+11.69	-	451+80	SB-ON RAMP FROM STH 32/CTH H	2193	923	-	-	1484	-
0010	453+14.57	-	474+40.00	SB-OFF RAMP TO STH 32/CTH H	2057	1058	166	-	726	-
0010	453+14.57	-	809+45.81	STH 32/CTH H-CTH D	33071	35404	-	-	-	-
0010	793+47.12	-	809+45.81	SB-ON RAMP FROM CTH D	2285	965	-	-	1097	-
0010	807+32.69	-	825+00.00	SB OFF RAMP TO CTH D	2325	1344	177	-	713	-
0010	809+45.81	-	977+00	CTH D-END PROJECT	15791	16763	-	-	-	-
				Sub-Tota1	101668	101776	493	23757	10299	460
0010	30+00	-	37+50.00	NB-OFF RAMP TO STH 32	2785	2189	114	-	644	-
0010	829+70	-	854+50	NB-BEGIN PROJECT-CTHV/STH 32	1710	2467	-	620	-	-
0010	60+14.70	-	72+59.39	NB-ON RAMP FROM STH 32	2223	979	-	-	1863	-
0010	854+50	-	220+00	NB-CTHV/STH 32-STH 33	13853	16123	-	-	-	-
0010	202+11.89	-	212+00	NB-OFF RAMP TO STH 33	1702	777	179	-	1412	66
0010	224+00	-	234+50	NB-ON RAMP FROM STH 33	1145	453	-	-	1166	-
0010	220+00	-	451+80	STH 33-STH 32/CTH H	19436	20967	-	5925	-	606
0010	263+80.55	-	267+00	NB-OFF RAMP FROM 43 TO 57	-	308	-	-	725	-
0010	431+18.67	-	450+10.99	NB-OFF RAMP TO STH 32/CTH H	1958	888	168	-	954	-
0010	450+86.77	-	471+00.00	NB-ON RAMP FROM STH 32/CTH H	2428	1307	-	-	1519	-
0010	453+14.57	-	809+45.81	STH 32/CTH H-CTH D	33525	35579	-	8942	-	-
0010	788+00.00	-	809+45.81	NB-OFF RAMP TO CTH D	2168	1194	156	-	704	-
0010	809+45.81	-	825+00.00	NB-ON RAMP FROM CTH D	2388	1089	-	-	1152	-
0010	809+45.81	-	977+29	CTH D-END PROJECT	15463	16778	-	-	-	-
				Sub-Tota1	100785	101098	617	23766	10140	672
				TOTAL 0010	405328	48633	48633	21571	21571	672

Addendum No. 01  
ID 1229-05-70  
Revised Sheet 193  
April 26, 2018

CONTINUED ON NEXT PAGE



Proposal Schedule of Items

Proposal ID: 20180508011 Project(s): 1229-05-70

Federal ID(s): WISC 2018237

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0164	645.0111 Geotextile Type DF Schedule A	370.000 SY	_____.	_____.
0166	645.0120 Geotextile Type HR	28.000 SY	_____.	_____.
0168	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	405,328.000 LF	_____.	_____.
0170	646.1555 Marking Line Grooved Contrast Permanent Tape 4-Inch	48,633.000 LF	_____.	_____.
0172	646.3555 Marking Line Grooved Contrast Permanent Tape 8-Inch	21,571.000 LF	_____.	_____.
0174	646.4505 Marking Line Same Day Paint 4-Inch	191,348.000 LF	_____.	_____.
0176	646.5020 Marking Arrow Epoxy	33.000 EACH	_____.	_____.
0178	646.5120 Marking Word Epoxy	12.000 EACH	_____.	_____.
0180	646.5420 Marking Aerial Enforcement Bar Epoxy	10.000 EACH	_____.	_____.
0182	646.5520 Marking Outfall Epoxy	729.000 EACH	_____.	_____.
0184	646.6120 Marking Stop Line Epoxy 18-Inch	325.000 LF	_____.	_____.
0186	646.7220 Marking Chevron Epoxy 24-Inch	1,768.000 LF	_____.	_____.
0188	646.9400 Marking Removal Plowable Raised Pavement Markers	2,068.000 EACH	_____.	_____.
0190	650.4500 Construction Staking Subgrade	2,425.000 LF	_____.	_____.
0192	650.5000 Construction Staking Base	2,425.000 LF	_____.	_____.
0194	650.6000 Construction Staking Pipe Culverts	1.000 EACH	_____.	_____.

