



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

May 2, 2018

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #41: 7919-01-70, WISC 2018 261
CTH F – River Falls
CTH F – Dry Run Road
CTH M
Pierce County

Letting of May 8, 2018

This is Addendum No. 03, which provides for the following:

Schedule of Items:

| Revised Bid Item Quantities | | | | | |
|-----------------------------|---------------------------|------|--------------|------------------|----------------|
| Bid Item | Item Description | Unit | Old Quantity | Revised Quantity | Proposal Total |
| 646.1020 | Marking Line Epoxy 4-Inch | LF | 100,250 | -36,600 | 63,650 |

Plan Sheets:

| Revised Plan Sheets | |
|---------------------|--|
| Plan Sheet | Plan Sheet Title (brief description of changes to sheet) |
| 41 | Miscellaneous Quantity Sheet – Pavement Marking |

Schedule of Items

Attached, dated May 2, 2018, are the revised Schedule of Items Page 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 41

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

SIGNING ITEMS - CONT'D

| SIGN NO. | SIGN CODE | STATION | LOCATION | SIZE | 637.2210 | | 634.0612 | | 634.0614 | | 638.2102 | | 638.3000 | | REMARKS |
|-----------------|-----------|---------|----------|-----------|------------|---------|------------|---------|------------|---------|------------|---------|------------|---------------------|--------------------------------|
| | | | | | REFLECTIVE | TYPE II | REFLECTIVE | TYPE II | REFLECTIVE | TYPE II | REFLECTIVE | TYPE II | REFLECTIVE | TYPE II | |
| 611 | W1-8R | 255+41 | LT | 18" X 24" | -- | 3.00 | -- | -- | -- | -- | -- | -- | -- | RIGHT ARROW | MOUNT ON SAME POST AS SIGN 605 |
| 612 | W3-5 | 268+27 | RT | 36" X 36" | -- | 9.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | REDUCED SPEED AHEAD | |
| 614 | W1-5L | 268+81 | LT | 30" X 30" | -- | 6.25 | -- | 1 | 1 | 1 | 1 | 1 | 1 | CURVE AHEAD | |
| 615 | W13-1P | 268+81 | LT | 18" X 18" | -- | 2.25 | -- | -- | -- | -- | -- | -- | -- | ADVISORY 45 MPH | MOUNT ON SAME POST AS SIGN 614 |
| 616 | D11-1 | 272+35 | LT | 24" X 18" | -- | 3.00 | 1 | -- | -- | -- | -- | -- | -- | BIKE ROUTE | |
| 617 | R1-1 | 273+15 | LT | 30" X 30" | -- | 5.18 | -- | 1 | 1 | 1 | 1 | 1 | 1 | STOP SIGN | |
| 618 | R1-1 | 273+57 | RT | 30" X 30" | -- | 5.18 | -- | 1 | 1 | 1 | 1 | 1 | 1 | STOP SIGN | |
| 619 | R2-1 | 274+64 | RT | 24" X 30" | -- | 5.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | SPEED LIMIT 45 | |
| 620 | R2-1 | 274+64 | RT | 24" X 30" | -- | 5.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | SPEED LIMIT 55 | |
| 621 | W14-3 | 272+25 | RT | 48" X 36" | -- | 5.56 | -- | 1 | 1 | 1 | 1 | 1 | 1 | NO PASSING ZONE | |
| 700 | R2-1 | 290+39 | LT | 24" X 30" | -- | 5.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | SPEED LIMIT 45 | |
| 701 | R2-1 | 291+24 | RT | 24" X 30" | -- | 5.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | SPEED LIMIT 45 | |
| 702 | R1-1 | 290+95 | RT | 30" X 30" | -- | 5.18 | -- | 1 | 1 | 1 | 1 | 1 | 1 | STOP SIGN | |
| 703 | R1-1 | 297+21 | RT | 30" X 30" | -- | 5.18 | -- | 1 | 1 | 1 | 1 | 1 | 1 | STOP SIGN | |
| 704 | R2-1 | 301+50 | RT | 24" X 30" | -- | 5.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | SPEED LIMIT 45 | |
| 705 | W5-52L | 301+97 | LT | 12" X 36" | -- | 3.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | BRIDGE SIGN | |
| 706 | W5-52R | 302+07 | RT | 12" X 36" | -- | 3.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | BRIDGE SIGN | |
| 707 | W5-52R | 302+36 | LT | 12" X 36" | -- | 3.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | BRIDGE SIGN | |
| 708 | W5-52L | 302+49 | RT | 12" X 36" | -- | 3.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | BRIDGE SIGN | |
| 709 | S3-1 | 307+55 | LT | 36" X 36" | 9.00 | -- | -- | 1 | 1 | 1 | 1 | 1 | 1 | BUS STOP AHEAD | |
| 800 | R2-1 | 310+07 | LT | 24" X 30" | -- | 5.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | SPEED LIMIT 45 | |
| 801 | R2-1 | 310+04 | RT | 24" X 30" | -- | 5.00 | -- | 1 | 1 | 1 | 1 | 1 | 1 | SPEED LIMIT 35 | |
| 802 | R1-1 | 311+01 | RT | 30" X 30" | -- | 5.18 | -- | 1 | 1 | 1 | 1 | 1 | 1 | STOP SIGN | |
| 803 | W14-3 | 312+71 | LT | 48" X 36" | -- | 5.56 | -- | 1 | 1 | 1 | 1 | 1 | 1 | NO PASSING ZONE | |
| 804 | R2-1 | 312+81 | LT | 30" X 30" | -- | 5.18 | -- | 1 | 1 | 1 | 1 | 1 | 1 | STOP SIGN | MOUNT ON SAME POST AS SIGN 803 |
| 805 | I2-2 | 312+71 | LT | 60" X 15" | -- | 6.25 | -- | 1 | 1 | 1 | 1 | 1 | 1 | PERCEC | MOUNT ON SAME POST AS SIGN 803 |
| 806 | M1-5A | 312+71 | LT | 24" X 24" | 4.00 | -- | -- | 1 | 1 | 1 | 1 | 1 | 1 | CTH M | |
| SHEET SUBTOTALS | | | | | 88 | 44 | 1 | 22 | 48 | 2 | 4 | 53 | 96 | 22 | |
| TOTALS | | | | | 170 | 243 | 17 | 48 | 2 | 4 | 53 | 96 | 22 | | |

PAVEMENT MARKING ITEMS

| STATION - STATION | LOCATION | 648.0100 | | COMMENTS |
|-------------------|----------|----------|--------|---------------------|
| | | WHITE | YELLOW | |
| 99+40 - 313+54 | LT | 21,425 | -- | CTH M LANE LINE |
| 99+40 - 313+54 | RT | 21,425 | -- | CTH M LANE LINE |
| 99+40 - 105+00 | CL | 1,120 | 0.11 | CTH M DOUBLE SOLID |
| 105+00 - 142+00 | CL | 925 | 0.70 | CTH M SKIPS |
| 142+00 - 151+25 | CL | 1,156 | 0.18 | CTH M SKIPS & SOLID |
| 151+25 - 153+40 | CL | 54 | 0.04 | CTH M SKIPS |
| 153+40 - 171+25 | CL | 2,231 | 0.34 | CTH M SKIPS & SOLID |
| 171+25 - 175+00 | CL | 94 | 0.07 | CTH M SKIPS |
| 175+00 - 184+40 | CL | 1,175 | 0.18 | CTH M SKIPS & SOLID |
| 184+40 - 199+25 | CL | 1,688 | 0.26 | CTH M SKIPS & SOLID |
| 199+25 - 216+55 | CL | 3,460 | 0.33 | CTH M DOUBLE SOLID |
| 216+55 - 227+95 | CL | 1,425 | 0.22 | CTH M SKIPS & SOLID |
| 227+95 - 235+95 | CL | 200 | 0.15 | CTH M SKIPS |
| 235+95 - 245+75 | CL | 1,225 | 0.19 | CTH M SKIPS & SOLID |
| 245+75 - 264+95 | CL | 3,840 | 0.36 | CTH M DOUBLE SOLID |
| 264+95 - 273+35 | CL | 988 | 0.16 | CTH M SKIPS & SOLID |
| 273+35 - 312+85 | CL | 9,988 | 0.75 | CTH M SKIPS |
| 312+85 - 313+54 | CL | 137 | 0.01 | CTH M DOUBLE SOLID |
| TOTALS | | 42,350 | 20,800 | |
| | | 63,650 | 4.05 | |

PAVEMENT MARKING EPOXY 8-INCH

| STATION - STATION | LOCATION | 646.3020 | REMARKS |
|-------------------|----------|----------|-------------|
| 99+40 - 313+53 | CL | 90 | ISLAND GORE |
| TOTALS | | 90 | |

PAVEMENT MARKING STOP LINE EPOXY 18-INCH

| STATION - STATION | LOCATION | 646.6120 | REMARKS |
|-------------------|----------|----------|-----------------|
| 99+50 | CTHF | 23 | RIGHT TURN LANE |
| 99+44 | CTHF | 15 | LANE |
| TOTALS | | 38 | |

CONSTRUCTION STAKING ITEMS

| STATION - STATION | LOCATION | 650.5500 | 650.6000 | 650.8000 | 650.9910 |
|-------------------|----------|----------|----------|----------|----------|
| 99+40 - 313+53 | CTHM | -- | -- | 21,413 | -- |
| PROJECT | | 2,150 | -- | -- | 1 |
| GOLDEN ACRES RD | | -- | 1 | -- | -- |
| 1047TH ST | | -- | 1 | -- | -- |
| 880TH ST | | -- | 1 | -- | -- |
| KNNIC VIEW DR | | -- | 1 | -- | -- |
| TOTALS | | 2,150 | 4 | 21,410 | 1 |



Proposal Schedule of Items

Proposal ID: 20180508041 Project(s): 7919-01-70

Federal ID(s): WISC 2018261

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

| Proposal Line Number | Item ID Description | Approximate Quantity and Units | Unit Price | Bid Amount |
|----------------------|--|--------------------------------|------------|------------|
| 0130 | 643.0300 Traffic Control Drums | 1,500.000 DAY | _____. | _____. |
| 0132 | 643.0420 Traffic Control Barricades Type III | 120.000 DAY | _____. | _____. |
| 0134 | 643.0705 Traffic Control Warning Lights Type A | 240.000 DAY | _____. | _____. |
| 0136 | 643.0900 Traffic Control Signs | 3,825.000 DAY | _____. | _____. |
| 0138 | 643.5000 Traffic Control | 1.000 EACH | _____. | _____. |
| 0140 | 646.1020 Marking Line Epoxy 4-Inch | 63,650.000 LF | _____. | _____. |
| 0142 | 646.3020 Marking Line Epoxy 8-Inch | 90.000 LF | _____. | _____. |
| 0144 | 646.6120 Marking Stop Line Epoxy 18-Inch | 38.000 LF | _____. | _____. |
| 0146 | 648.0100 Locating No-Passing Zones | 4.050 MI | _____. | _____. |
| 0148 | 650.5500 Construction Staking Curb Gutter and Curb & Gutter | 2,150.000 LF | _____. | _____. |
| 0150 | 650.6000 Construction Staking Pipe Culverts | 4.000 EACH | _____. | _____. |
| 0152 | 650.8000 Construction Staking Resurfacing Reference | 21,410.000 LF | _____. | _____. |
| 0154 | 650.9910 Construction Staking Supplemental Control (project) 01. 7919-01-70 | LS | LUMP SUM | _____. |
| 0156 | 690.0150 Sawing Asphalt | 862.000 LF | _____. | _____. |
| 0158 | 690.0250 Sawing Concrete | 18.000 LF | _____. | _____. |
| 0160 | ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR | 1,200.000 HRS | 5.00000 | 6,000.00 |

