



# Wisconsin Department of Transportation

August 30, 2018

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #05: 2250-12-70, WISC 2018 375  
Main St/1<sup>st</sup> St Vil Waterford  
Buena Park Rd to Milw Ave (STH 36)  
STH 20  
Racine County**

### Letting of September 11, 2018

This is Addendum No. 03, which provides for the following:

#### Special Provisions:

Added Special Provisions	
Article No.	Description
85	Railing Pipe, Item 513.2050.S; Railing Steel Type C4 (Structure), Item 513.7021.01; Railing Steel Pedestrian Type C4, Item 513.8021.01 - 513.8021.05 (Structure).
86	Material and Equipment Staging

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
690.0200	Sawing Concrete	LF	6,636	625	7,261

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
372	Miscellaneous Quantities (revised Sawing Concrete quantity)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 03**

**2250-12-70**

**August 30, 2017**

**Special Provisions**

- 85. Railing Pipe, Item 513.2050.S; Railing Steel Type C4 (Structure), Item 513.7021.01; Railing Steel Pedestrian Type C4, Item 513.0821.01 – 513.8021.05 (Structure).**

*Supplement section 513 of the standard specifications with the following:*

Paint all Railing Pipe, Railing Steel Type C4, and Railing Steel Pedestrian Type C4 with black paint, federal color number 17038.

- 86. Material and Equipment Staging.**

Submit a map showing all proposed material stockpile or equipment storage locations to the Engineer 14 days prior to either preconstruction or proposed use, whichever comes first. Identify the specific purposes for the location. Do not stockpile material or equipment until locations are approved by the engineer. Stockpiles and other material storage on W. Main Street from Jefferson Street to S. First Street and on E. Main Street from First Street to Milwaukee Street will be limited to a height of five feet and timeframe of two weeks unless the engineer approves otherwise in writing.

**Schedule of Items**

Attached, dated August 30, 2018, are the revised Schedule of Items Page 23.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 372

END OF ADDENDUM

Addendum No. 03  
ID 2250-12-70  
Revised Sheet 372  
August 30, 2018

**SAWING**

690.0150 690.0200  
SAWING

CATEGORY ROADWAY	STATION TO	STATION	SIDE	ASPHALT		CONCRETE		COMMENTS
				LF	LF	LF	LF	
0010 STH 20	306+25	- 310+00	RT	144	22			
	310+00	- 316+00	RT	12				
	316+00	- 322+00	RT	7				
	322+00	- 328+00	RT	10				
	328+00	- 334+00	RT	53				
	334+00	- 340+00	LT/RT	398				
	340+00	- 346+00	LT/RT	90	8			
	346+00	- 352+00	LT/RT	113	33			
	352+00	- 358+00	LT/RT	337	64			
	358+00	- 364+27	LT/RT	336	181			
	366+78	- 370+50	LT/RT	35				
	370+50	- 376+50	LT/RT	74	42			
	376+50	- 382+50	LT/RT	169				
	382+50	- 388+50	LT/RT	--				
	388+50	- 394+50	LT/RT	160				
	394+50	- 400+50	LT/RT	96				
	400+50	- 406+00	LT/RT	397				
	5+62	- 9+50	LT/RT	50				
	10+75	- 15+49	LT/RT	61				
	20+25	- 21+50	LT/RT	31	10			
	30+30	- 31+25	LT/RT	22				
	40+30	- 41+75	LT/RT	107				
	50+00	- 51+51	LT/RT	30	11			
	60+30	- 61+00	LT/RT	21	11			
	68+75	- 69+70	LT/RT	35	14			
	77+20	- 79+60	LT/RT	82	19			
	80+40	- 83+00	LT/RT	101	84			
	88+80	- 89+75	LT/RT	46	20			
	90+25	- 81+25	LT/RT	40	27			
	100+60	- 103+50						
	120+25	- 120+65	LT/RT	36	19			
	160+38	- 161+28	LT/RT	45				
	170+38	- 170+67	LT/RT	36				
	179+32	- 179+62	LT/RT	36				
	188+50	- 189+54	LT/RT	24				
	190+44	- 190+57	LT/RT	24				
	129+00	- 129+75	LT/RT	45	21			
	130+25	- 131+00	LT/RT	34	17			
	UNDISTRIBUTED			1,732	5,886	SAWING FOR STAGING		
	CATEGORY 0010 SUBTOTAL			5,069	6,489			
0150	103+50	- 105+50	LT/RT	53				
	105+50	- 109+75	LT/RT	127	103			
	138+70	- 139+75	LT/RT	37	15			
	140+25	- 141+25	LT/RT	128	14			
	149+22	- 149+75	LT/RT	18				
	150+30	- 151+50	LT/RT	176	15			
	UNDISTRIBUTED							
	CATEGORY 0150 SUBTOTAL			539	772			
	PROJECT TOTAL			5,608	7,261			

ALL ITEMS CATEGORY 0010 UNLESS NOTED

MISCELLANEOUS QUANTITIES

SHEET NO: 372

PROJECT NO: 2250-12-70

HWY: STH 20

COUNTY: RACINE

DATE : 8/28/2018 4:13PM

PLOT NAME : 03201.mq

PLOT SCALE : 1.000000:1.000000

WISDOT / CADDS SHEET 42



## Proposal Schedule of Items

Proposal ID: 20180911005 Project(s): 2250-12-70

Federal ID(s): WISC 2018375

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0660	659.1125 Luminaires Utility LED C	49.000 EACH	_____.	_____.
0662	659.2230 Lighting Control Cabinets 240/480 30-Inch	2.000 EACH	_____.	_____.
0664	661.0200 Temporary Traffic Signals for Intersections (location) 01. STH 20 & CTH W/Buena Park Rd	LS	LUMP SUM	_____.
0666	661.0200 Temporary Traffic Signals for Intersections (location) 02. STH 20 & Jefferson St	LS	LUMP SUM	_____.
0668	661.0200 Temporary Traffic Signals for Intersections (location) 03. STH 20 & E. Main St	LS	LUMP SUM	_____.
0670	678.0700 Install Wireless Antennas	2.000 EACH	_____.	_____.
0672	690.0150 Sawing Asphalt	5,608.000 LF	_____.	_____.
0674	690.0250 Sawing Concrete	7,261.000 LF	_____.	_____.
0676	715.0415 Incentive Strength Concrete Pavement	17,430.000 DOL	1.00000	17,430.00
0678	715.0502 Incentive Strength Concrete Structures	5,300.000 DOL	1.00000	5,300.00
0680	715.0710 Optimized Aggregate Gradation Incentive	43,730.000 DOL	1.00000	43,730.00
0682	999.1500.S Crack and Damage Survey	LS	LUMP SUM	_____.
0684	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	3,000.000 HRS	5.00000	15,000.00
0686	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	6,500.000 HRS	5.00000	32,500.00