



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

October 15, 2018

### NOTICE TO ALL CONTRACTORS:

**Proposal #09: 5087-00-70**  
**CTH Y – CTH B**  
**Fish Creek Bridge B-32-0235**  
**CTH J**  
**La Crosse County**

### Letting of November 13, 2018

This is Addendum No. 01, which provides for the following:

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
9	Miscellaneous Quantities; Removed "Undistributed" line from Pay Plan Quantity items and distributed those quantities amongst the STA-STA lines. All total quantities remained the same.

#### **Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 9

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

204.0165 REMOVING GUARDRAIL

STATION	-	STATION	LOCATION	RAIL	LF
47+62	-	48+00	LT	38	
47+64	-	48+00	RT	36	
48+63	-	48+97	LT	34	
48+63	-	49+00	RT	37	
TOTAL					145

205.0100 EXCAVATION COMMON \*\*p\*\*

LOCATION	EXC. COMMON	FILL	EXPANDED FILL	WASTE	
CY (3)	CY (1)	CY (2)	CY	CY	
SOUTH APPROACH	190	102	133	57	
NORTH APPROACH	293	162	211	82	
TOTAL					483
TOTAL					264
TOTAL					343
TOTAL					140

- (1) - NOT A BID ITEM - FOR INFORMATIONAL PURPOSES ONLY.
- (2) - FILL EXPANSION 30%
- (3) - EXISTING ASPHALTIC PAVEMENT IS INCLUDED IN COMMON EXCAVATION TOTALS.

305.0110 BASE AGGREGATE DENSE 3/4-INCH  
305.0120 BASE AGGREGATE DENSE 1 1/4-INCH  
624.0100 WATER

STATION	-	STATION	TON	3/4-INCH	1 1/4-INCH	WATER	MGAL	
46+25	-	47+85.40	33	327	10.8			
48+59.90	-	50+00	30	292	9.7			
TOTAL								63
TOTAL								619
TOTAL								20.5

455.0605 TACK COAT  
465.0105 ASPHALTIC SURFACE

STATION	-	STATION	TACK	ASPHALTIC	
GALE	TON	TON	COAT	SURFACE	
46+25	-	47+85.40	26	113	
48+59.90	-	50+00	23	101	
TOTAL					49
TOTAL					214

\*\*p\*\* - PAY PLAN QUANTITY

NOTE:  
ALL ITEMS AND QUANTITIES ON THIS SHEET ARE FOR  
ENGINEERS ESTIMATE CATEGORY 0010 UNLESS OTHERWISE NOTED.

628.1504 SILT FENCE  
628.1520 SILT FENCE MAINTENANCE

STATION	-	STATION	LOCATION	FENCE	MAINT.
LF	LF	LF	LF	LF	LF
46+15	-	48+25	LT	235	235
46+15	-	48+25	RT	235	235
48+35	-	50+10	LT	190	190
48+35	-	50+10	RT	190	190
UNDISTRIBUTED					213
TOTAL					1063
TOTAL					1063

628.2008 EROSION MAT URBAN CLASS I TYPE B

STATION	-	STATION	LOCATION	SY	
47+10	-	47+75	LT	57	
47+10	-	48+20	RT	183	
48+40	-	49+35	LT	76	
48+40	-	49+35	RT	62	
UNDISTRIBUTED					95
TOTAL					473

628.1905 MOBILIZATIONS EROSION CONTROL  
628.1910 MOBILIZATIONS EMERGENCY CONTROL

DESCRIPTION	MOBILIZATION	EMERGENCY MOB.	
EACH	EACH	EACH	
PROJECT 5087-00-70	2	2	
TOTAL			2
TOTAL			2

Addendum No. 01  
ID 5087-00-70  
Revised Sheet 9  
October 15, 2018

614.2300 MGS GUARDRAIL 3  
614.2500 MGS THRIE BEAM TRANSITION  
614.2610 MGS GUARDRAIL TERMINAL EAT

STATION	-	STATION	LOCATION	GUARDRAIL	THRIE BEAM	TRANSITION	TERMINAL EAT
LF	LF	LF	LF	EACH	EACH	EACH	EACH
46+72.27	-	47+25.40	LT	-	-	1	1
46+72.27	-	47+25.40	RT	-	-	1	1
47+25.40	-	47+37.90	LT	12.5	-	-	-
47+25.40	-	47+37.90	RT	12.5	-	-	-
47+37.90	-	47+77.30	LT	-	39.4	-	-
47+37.90	-	47+77.30	RT	-	39.4	-	-
48+68.00	-	49+07.40	LT	-	39.4	-	-
48+68.00	-	49+07.40	RT	-	39.4	-	-
49+07.40	-	49+19.90	LT	12.5	-	-	-
49+07.40	-	49+19.90	RT	12.5	-	-	-
49+19.90	-	49+73.03	LT	-	-	1	1
49+19.90	-	49+73.03	RT	-	-	1	1
TOTAL					50	157.6	4

618.00 MAINTENANCE AND REPAIR OF HAUL ROADS 5087-00-70  
(CAT 0040)

LOCATION	EACH
PROJECT 5087-00-70	1
TOTAL	1

625.0500 SALVAGED TOPSOIL \*\*p\*\*  
627.0200 MULCHING \*\*p\*\*  
629.0210 FERTILIZER TYPE B \*\*p\*\*  
630.0120 SEEDING MIXTURE NO. 20 \*\*p\*\*  
630.0200 SEEDING TEMPORARY \*\*p\*\*

STATION	-	STATION	LOCATION	SALVAGED TOPSOIL	MULCHING	FERTILIZER	SEEDING #20	SEEDING TEMPORARY	
SY	SY	CWT	LB	LB	LB	LB	LB	LB	
46+25	-	48+20	LT	169	141	0.14	6	6	
46+25	-	48+20	RT	389	222	0.27	12	12	
48+40	-	50+00	LT	184	118	0.14	6	6	
48+40	-	50+00	RT	165	113	0.12	5	5	
TOTAL									907
TOTAL									594
TOTAL									0.67
TOTAL									29
TOTAL									29

PROJECT NO: 5087-00-70

HWY: CTH J

COUNTY: LA CROSSE

MISCELLANEOUS QUANTITIES

SHEET

9

E

FILE NAME: \\SRD01\PROJECTS\W01\CTH\CH01\5087\3-H\MAIL\DSGN\5-DRAWINGS\LD-CIVIL\CAD\CIVIL-3DSHEET\PLAN\601-MCLDING LAYOUT\TABLE-00AS01.dwg

PLOT BY: TOREY R. LEONARD

PLOT NAME:

301/12/2018 8:24 AM

WSDOT/CADD/SHEET 42