



Wisconsin Department of Transportation

December 4, 2018

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #13: 7102-00-70
T La Grange, Dolphin Road
Mill Creek Bridge B-41-0312
Loc Str
La Crosse County

Letting of December 11, 2018

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
205.0100	Excavation Common	CY	569	0	569

Note: The bid item listed above was pay plan quantity. This addendum removes the pay plan quantity designation on all bid items. There were no quantity changes.

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
5	EOQ (Removed Pay Plan Quantity)
7	Miscellaneous Quantities (Removed Pay Plan Quantity)

Schedule of Items

Attached, dated December 4, 2018, are the revised Schedule of Items Page 1.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 5 and 7.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Estimate Of Quantities

7102-00-70

Line	Item	Item Description	Unit	Total	Qty
0002	203.0600.S	Removing Old Structure Over Waterway With Minimal Debris (station) 01. 10+00	LS	1,000	1,000
0004	204.0165	Removing Guardrail	LF	112,000	112,000
0006	205.0100	Excavation Common	CY	569,000	569,000
0008	206.1000	Excavation for Structures Bridges (structure) 01. B-41-312	LS	1,000	1,000
0010	210.1500	Backfill Structure Type A	TON	270,000	270,000
0012	213.0100	Finishing Roadway (project) 01. 7102-00-70	EACH	1,000	1,000
0014	305.0110	Base Aggregate Dense 3/4-Inch	TON	24,000	24,000
0016	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	440,000	440,000
0018	311.0110	Breaker Run	TON	585,000	585,000
0020	455.0605	Tack Coat	GAL	27,000	27,000
0022	465.0105	Asphaltic Surface	TON	104,000	104,000
0024	502.0100	Concrete Masonry Bridges	CY	130,000	130,000
0026	502.3200	Protective Surface Treatment	SY	171,000	171,000
0028	505.0400	Bar Steel Reinforcement HS Structures	LB	5,770,000	5,770,000
0030	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	14,750,000	14,750,000
0032	513.4061	Railing Tubular Type M 01. B-41-312	LF	81,000	81,000
0034	516.0500	Rubberized Membrane Waterproofing	SY	12,000	12,000
0036	550.2106	Piling CIP Concrete 10 3/4 X 0.365-Inch	LF	245,000	245,000
0038	606.0300	Riprap Heavy	CY	80,000	80,000
0040	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	160,000	160,000
0042	618.0100	Maintenance And Repair of Haul Roads (project) 01. 7102-00-70	EACH	1,000	1,000
0044	619.1000	Mobilization	EACH	1,000	1,000
0046	624.0100	Water	MGAL	46,000	46,000
0048	625.0500	Salvaged Topsoil	SY	480,000	480,000
0050	627.0200	Mulching	SY	790,000	790,000
0052	628.1504	Silt Fence	LF	615,000	615,000
0054	628.1520	Silt Fence Maintenance	LF	615,000	615,000
0056	628.1905	Mobilizations Erosion Control	EACH	2,000	2,000
0058	628.1910	Mobilizations Emergency Erosion Control	EACH	2,000	2,000
0060	628.6005	Turbidity Barriers	SY	190,000	190,000
0062	629.0210	Fertilizer Type B	CWT	0.700	0.700
0064	630.0120	Seeding Mixture No. 20	LB	30,000	30,000
0066	630.0200	Seeding Temporary	LB	30,000	30,000
0068	634.0612	Posts Wood 4x6-Inch X 12-FT	EACH	4,000	4,000
0070	637.2230	Signs Type II Reflective F	SF	12,000	12,000
0072	638.2602	Removing Signs Type II	EACH	4,000	4,000
0074	638.3000	Removing Small Sign Supports	EACH	4,000	4,000

Addendum No. 01
 ID 7102-00-70
 Revised Sheet 5
 December 4, 2018

Addendum No. 01
ID 7102-00-70
Revised Sheet 7
December 4, 2018

205.0100 EXCAVATION COMMON

LOCATION	EXC. COMMON CY (9)	FILL CY (1)	EXPANDED FILL CY (2)	WASTE CY
STA 8+75 - STA. 9+78.71	67	87	87	153
STA 10+17.29 - STA 11+50	329	39	50	279
TOTALS:	569	106	137	432

(1) - NOT A BID ITEM - FOR INFORMATIONAL PURPOSES ONLY.
 (2) - FILL EXPANSION 30%
 (3) - EXISTING ASPHALTIC PAVEMENT IS INCLUDED IN COMMON EXCAVATION TOTALS. SEE EARTHWORK TABLE.

455.0605 TACK COAT
485.0105 ASPHALTIC SURFACE

STATION	STATION	TACK COAT GAL	ASPHALTIC SURFACE TON
8+75	9+78.71	12	46
10+17.29	11+50.00	15	58
TOTALS:		27	104

204.0165 REMOVING GUARDRAIL

STATION	STATION	LOCATION	LF
9+54 - 9+82	RT		28
9+54 - 9+82	LT		28
10+18 - 10+46	LT		28
10+18 - 10+46	RT		28
TOTALS:			112

204.0165 TACK COAT
485.0105 ASPHALTIC SURFACE

STATION	STATION	TACK COAT GAL	ASPHALTIC SURFACE TON
8+75	9+78.71	12	46
10+17.29	11+50.00	15	58
TOTALS:		27	104

625.0500 SALVAGED TOPSOIL

STATION	STATION	LOCATION	SY	MULCHING SY	FERTILIZER CWT	SEEDING LB	SEEDING #20 LB	TEMPORARY WATER* MGAL
8+75	9+80	RT	75	130	0.10	5	5	4
8+75	9+80	LT	105	155	0.15	6	6	5
10+16	11+50	RT	90	165	0.15	6	6	5
10+16	11+50	LT	115	180	0.15	7	7	6
UNDISTRIBUTED			95	160	0.15	6	6	5
TOTALS:			480	790	0.70	30	30	25

*ADDITIONAL QUANTITY INCLUDED WITH BASE AGGREGATE ITEMS.

618.0100 MAINTENANCE AND REPAIR OF HAUL ROADS

DESCRIPTION	PROJECT 7102-00-70
HAUL ROADS	1
REPAIR OF	1
TOTAL:	2

*CATEGORY 0030 ITEM

305.0110 BASE AGGREGATE DENSE 3/4-INCH
305.0120 BASE AGGREGATE DENSE 1 1/4-INCH
311.0110 BREAKER RUN
624.0100 WATER

STATION	STATION	LOCATION	TON	BREAKER RUN TON	WATER* MGAL
8+75.00	9+78.71	LT	10	280	9
10+17.29	11+50.00	LT	14	325	12
TOTALS:			24	585	21

*ADDITIONAL QUANTITY INCLUDED WITH EROSION CONTROL ITEMS

628.6005 TURBIDITY BARRIERS

LOCATION	SY
SOUTH ABUT	83
NORTH ABUT	72
UNDISTRIBUTED	35
TOTAL:	190

634.0612 POSTS WOOD 4x6-INCH x 12-FT
637.2230 SIGNS TYPE II REFLECTIVE F
638.2602 REMOVING SIGNS TYPE II
638.3000 REMOVING SMALL SIGN SUPPORTS

STATION	LOCATION	SIZE	SIGN CODE	WOOD POSTS EACH	REMOVING SIGNS TYPE II EACH	REMOVING SMALL SIGN SUPPORTS EACH	COMMENTS
9+75	RT	12"x96"	W5-52R	1	-	-	OBJECT MARKER
9+81	RT	-	-	1	1	-	EXISTING OBJECT MARKER
9+82	LT	12"x96"	W5-52L	1	-	-	OBJECT MARKER
9+81	LT	-	-	1	1	-	EXISTING OBJECT MARKER
10+45	RT	12"x96"	W5-52L	1	-	-	OBJECT MARKER
10+19	RT	-	-	1	1	-	EXISTING OBJECT MARKER
10+21	LT	12"x96"	W5-52R	1	-	-	OBJECT MARKER
10+19	LT	-	-	1	1	-	EXISTING OBJECT MARKER
TOTALS:				12	4	4	

628.1504 SILT FENCE
628.1520 SILT FENCE MAINTENANCE

STATION	STATION	LOCATION	LF	MAINT.
8+75	9+93	LT	120	120
8+75	9+82	RT	105	105
10+27	11+50	LT	125	125
10+04	11+50	RT	140	140
UNDISTRIBUTED			125	125
TOTALS:			615	615

643.0420 TRAFFIC CONTROL BARRICADES TYPE III
643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A
643.0900 TRAFFIC CONTROL SIGNS

LOCATION	DAYS	EACH	TRAFFIC CONTROL BARRICADES TYPE III	TRAFFIC CONTROL WARNING LIGHTS TYPE A	TRAFFIC CONTROL SIGNS
OTH G INTERSECTION	71	142	142	4	284
BEGINNING OF PROJECT	71	7	497	10	213
END OF PROJECT	71	7	497	10	284
DOGWOOD AVE INTERSECTION	71	2	142	4	213
UNDISTRIBUTED	71	2	142	2	142
TOTALS:			1,420	2,130	1,136

650.4500 CONSTRUCTION STAKING SUBGRADE
650.9000 CONSTRUCTION STAKING BASE
650.9920 CONSTRUCTION STAKING SLOPE STAKES
650.9910 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL 7102-00-70

STATION	STATION	BASE LF	SLOPE STAKES LF	SUPPLEMENTAL CONTROL LS
8+75	9+78.71	104	104	104
10+17.29	11+50	133	133	133
TOTALS:		237	237	237

660.0150 SAWING ASPHALT

STATION	LF
8+75	18
11+50	18
TOTAL:	36

*** - PAY PLAN QUANTITY
NOTE: ALL ITEMS ARE CATEGORY 000 UNLESS NOTED OTHERWISE.



Proposal Schedule of Items

Proposal ID: 20181211013 Project(s): 7102-00-70

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0600.S Removing Old Structure Over Waterway With Minimal Debris (station) 01. 10+00	LS	LUMP SUM	_____.
0004	204.0165 Removing Guardrail	112.000 LF	_____.	_____.
0006	205.0100 Excavation Common	569.000 CY	_____.	_____.
0008	206.1000 Excavation for Structures Bridges (structure) 01. B-41-312	LS	LUMP SUM	_____.
0010	210.1500 Backfill Structure Type A	270.000 TON	_____.	_____.
0012	213.0100 Finishing Roadway (project) 01. 7102-00-70	1.000 EACH	_____.	_____.
0014	305.0110 Base Aggregate Dense 3/4-Inch	24.000 TON	_____.	_____.
0016	305.0120 Base Aggregate Dense 1 1/4-Inch	440.000 TON	_____.	_____.
0018	311.0110 Breaker Run	585.000 TON	_____.	_____.
0020	455.0605 Tack Coat	27.000 GAL	_____.	_____.
0022	465.0105 Asphaltic Surface	104.000 TON	_____.	_____.
0024	502.0100 Concrete Masonry Bridges	130.000 CY	_____.	_____.
0026	502.3200 Protective Surface Treatment	171.000 SY	_____.	_____.
0028	505.0400 Bar Steel Reinforcement HS Structures	5,770.000 LB	_____.	_____.
0030	505.0600 Bar Steel Reinforcement HS Coated Structures	14,750.000 LB	_____.	_____.
0032	513.4061 Railing Tubular Type M 01. B-41-312	81.000 LF	_____.	_____.