



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

April 18, 2019

NOTICE TO ALL CONTRACTORS:

Proposal #23: 4090-07-71, WISC 2019 294
WCL – Campbellsport
Golden Corners Road – Baumann Street
STH 67
Fond du Lac County

Letting of May 14, 2019

This is Addendum No. 01, which provides for the following:

Schedule of Items:

| Added Bid Item Quantities | | | | | |
|---------------------------|-----------------------|------|--------------|------------------|----------------|
| Bid Item | Item Description | Unit | Old Quantity | Revised Quantity | Proposal Total |
| 611.0530 | Manhole Covers Type J | EA | 0 | 1 | 1 |

Plan Sheets:

| Revised Plan Sheets | |
|---------------------|---|
| Plan Sheet | Plan Sheet Title (brief description of changes to sheet) |
| 59 | Miscellaneous quantity table revised to include bid item 611.0530 and additional information for the depth of the manhole structure has been added. |

Schedule of Items

Attached, dated April 18, 2019, are the revised Schedule of Items Page 9.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 59.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

STORM SEWER SUMMARY

| CATEGORY | STATION | LOCATION | LOGATION | 520. 8000* CONCRETE COLLARS FOR PIPE EA | 522. 1036* APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 36-INCH EA | 608. 0336 STORM SEWER PIPE REINFORCED CONCRETE CLASS III 36-INCH LF | 611. 0530 MANHOLE COVERS TYPE J EA | 611. 2005 MANHOLES 5-FT DIAMETER EA | 650. 4000 CONSTRUCTION STAKING STORM SEWER EA | REMARKS |
|----------|---------|------------------|----------|--|--|--|---------------------------------------|--|--|---|
| 0010 | 1071+77 | STH 67, 26.0' LT | --- | 1 | 1 | 53 | --- | --- | 1 | I INVERT ELEVATION=1041.40, PIPE SLOPE=1.24% |
| 0010 | 1072+31 | STH 67, 22.0' LT | --- | --- | --- | 479 | 1 | 1 | 1 | I INVERT ELEVATION=1040.74, PIPE-SLOPE 0.69%, RIM ELEVATION=1048.48, STRUCTURE HEIGHT=(RIM ELEV-INVERT ELEV-CASTING HEIGHT-6" ADJUSTMENT)=6.50 FT |
| 0010 | 1077+10 | STH 67, 22.0' LT | 1 | --- | --- | --- | --- | --- | --- | I INVERT ELEVATION 1037.44 - FIELD VERIFY PRIOR TO INSTALLATION |
| | | | | 1 | 1 | 532 | 1 | 1 | 2 | |

*-ADDITIONAL QUANTITIES SHOWN ELSEWHERE

Addendum No. 01
ID 4090-07-71
Revised Sheet 59
April 18, 2019



Proposal Schedule of Items

Proposal ID: 20190514023 Project(s): 4090-07-71
 Federal ID(s): WISC 2019294

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

| Proposal Line Number | Item ID Description | Approximate Quantity and Units | Unit Price | Bid Amount |
|----------------------|--|--------------------------------|------------|------------|
| 0250 | 649.0120 Temporary Marking Line Epoxy 4-Inch | 51,095.000 LF | _____ | _____ |
| 0252 | 650.4000 Construction Staking Storm Sewer | 2.000 EACH | _____ | _____ |
| 0254 | 650.6000 Construction Staking Pipe Culverts | 1.000 EACH | _____ | _____ |
| 0256 | 650.8000 Construction Staking Resurfacing Reference | 29,807.000 LF | _____ | _____ |
| 0258 | 650.9910 Construction Staking Supplemental Control (project) 01. Project 4090-07-71 | LS | LUMP SUM | _____ |
| 0260 | 650.9920 Construction Staking Slope Stakes | 9,687.000 LF | _____ | _____ |
| 0262 | 690.0150 Sawing Asphalt | 2,230.000 LF | _____ | _____ |
| 0264 | 690.0250 Sawing Concrete | 150.000 LF | _____ | _____ |
| 0266 | 715.0502 Incentive Strength Concrete Structures | 500.000 DOL | 1.00000 | 500.00 |
| 0268 | 740.0440 Incentive IRI Ride | 45,160.000 DOL | 1.00000 | 45,160.00 |
| 0270 | ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR | 2,000.000 HRS | 5.00000 | 10,000.00 |
| 0272 | ASP.1T0G On-the-Job Training Graduate at \$5.00/HR | 1,320.000 HRS | 5.00000 | 6,600.00 |
| 0274 | SPV.0090 Special 01. Salvage and Reset Fence | 475.000 LF | _____ | _____ |
| 0276 | 611.0530 Manhole Covers Type J | 1.000 EACH | _____ | _____ |

Section: 0001 Total: _____

Total Bid: _____

