



Wisconsin Department of Transportation

May 6, 2019

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #41: 9030-11-60, WISC 2019 312
Merrill - Rhinelander
Big Hay Meadow Creek
Bridge B-35-20
STH 17
Lincoln County

9215-01-64, WISC 2019316
Ogema - Tomahawk
Wisconsin River Bridge B-35-0052
STH 86
Lincoln County

Letting of May14, 2019

This is Addendum No. 01, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
18	Temporary Portable Rumble Strips, Item 643.0310.S

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0310.S.01	Temporary Portable Rumble Strips 9030-11-60	LS	0	1	1
643.0310.S.02	Temporary Portable Rumble Strips 9215-01-64	LS	0	1	1

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01
9030-11-60, 9215-01-64
May 6, 2019

Special Provisions

18. Temporary Portable Rumble Strips, Item 643.0310.S.

A Description

This special provision describes providing, relocating, maintaining, and removing temporary portable rumble strips.

B Materials

Furnish RoadQuake2 or Roadquake2F temporary portable rumble strips, by Plastic Safety Systems. Do not use alternate products or methods without preapproval by the Bureau of Traffic Operations.

C Construction

C.1 Placement

Provide rumble strips where the plans show or the engineer directs as follows:

1. Before placing rumble strips, clean the roadway of sand and other materials that may cause slippage.
2. Place one end of the rumble strips 6 inches from the roadway centerline. Extend the strips perpendicular to the direction of travel. Ensure strips lay flat on the roadway surface.
3. Only one series of rumble strips, placed before the first work zone, is required per direction of travel for multiple work zones spaced 1 mile or less apart. Work zones spaced greater than 1 mile apart require a separate series of rumble strips.

C.2 Maintenance

Maintain rumble strips as follows:

1. If rumble strips slide, become out of alignment, or are no longer in the wheel path of approaching vehicles during the work period, thoroughly clean both sides of the rumble strips and reset on a clean roadway.
2. Repair or replace damaged rumble strips immediately.

D Measurement

The department will measure temporary portable rumble strips as a single lump sum unit of work acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
643.0310.S.01	Temporary Portable Rumble Strips 9030-11-60	LS
643.0310.S.02	Temporary Portable Rumble Strips 9215-01-64	LS

Payment is full compensation for providing, relocating, maintaining or replacing, and removing temporary portable rumble strips.

stp-643-020 (20161130)

Schedule of Items

Attached, dated May 6, 2019, are the revised Schedule of Items Page 7.

END OF ADDENDUM



Proposal Schedule of Items

Proposal ID: 20190514041 Project(s): 9030-11-60, 9215-01-64

Federal ID(s): WISC 2019312, WISC 2019316

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0192	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,200.000 HRS	5.00000	6,000.00
0194	SPV.0090 Special 01. Cleaning Parapets Special	613.000 LF	_____.	_____.
0196	SPV.0165 Special 01. Prestressed Concrete Girder Repair	30.000 SF	_____.	_____.
0198	643.0310.S Temporary Portable Rumble Strips 01. 9030-11-30	LS	LUMP SUM	_____.
0200	643.0310.S Temporary Portable Rumble Strips 02. 9215-01-64	LS	LUMP SUM	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.