



# Wisconsin Department of Transportation

October 30, 2019

**Division of Transportation Systems Development**  
Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

## NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

**Proposal #06: 5155-02-63, WISC 2019675**  
**Madison - Evansville**  
**Byrne Road to Netherwood Road**  
**USH 14**  
**Dane County**

**5155-02-83, WISC 2019676**  
**Madison - Evansville**  
**Mccoys Rd/Byrne Rd/STH 138 Bridges**  
**USH 14**  
**Dane County**

## Letting of November 12, 2019

This is Addendum No. 01, which provides for the following:

### Special Provisions:

Deleted Special Provisions	
Article No.	Description
16	Reheating HMA Pavement Longitudinal Joints, Item 460.4110.S
27	Removing HMA Pavement Notched Wedge Longitudinal Joint Milling, Item SPV.0090.01

### Schedule of Items:

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
460.4110.S	Reheating HMA Pavement Longitudinal Joints	LF	5250	0	0
SPV.0090.01	Removing HMA Pavement Notched Wedge Longitudinal Joint Milling	LF	5250	0	0

### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
143	Miscellaneous Quantities (Removed items from Asphalt Items)
144	Miscellaneous Quantities (Removed items from Asphalt Items)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**  
**5155-02-63 & 5155-02-83**  
**October 30, 2019**

**Special Provisions**

**16. DELETED**

**27. DELETED**

**Schedule of Items**

Attached, dated October 30, 2019, are the revised Schedule of Items Pages 1 – 12.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 143 and 144.

END OF ADDENDUM

ASPHALT ITEMS

455.0605 460.6224 465.0125

CATEGORY	STATION	TO	STATION	LOCATION	TACK COAT	HMA PAVEMENT		REMARKS
						4 MT 58-28 S	TEMPORARY	
					GAL	TON	TON	
0010	209+35' EB'	-	222+80' EB'	USH 14 EB	700	1120	-	MILL & OVERLAY
	224+88' EB'	-	233+30' EB'	USH 14 EB	650	1030	-	MILL & OVERLAY
	700+00' WB'	-	704+35' WB'	USH 14 EB	350	540	-	MILL & OVERLAY
	823+30' WB'	-	825+05' WB'	USH 14 WB	60	94	-	BUTT JOINT B-13-244
	827+22' WB'	-	829+10' WB'	USH 14 WB	60	94	-	BUTT JOINT B-13-244
	355+50' EB'	-	357+17' EB'	USH 14 EB	60	94	-	BUTT JOINT B-13-245
	359+45' EB'	-	361+30' EB'	USH 14 EB	60	94	-	BUTT JOINT B-13-245
	816+00' WB'	-	825+09' WB'	USH 14 WB 0.5' LT	15	23	-	FILL RUMBLE STRIP
	818+20' WB'	-	825+09' WB'	USH 14 WB 25' RT	10	17	-	FILL RUMBLE STRIP
	827+09' WB'	-	831+00' WB'	USH 14 WB 0.5' LT	6	10	-	FILL RUMBLE STRIP
	827+09' WB'	-	831+00' WB'	USH 14 WB 25' RT	6	10	-	FILL RUMBLE STRIP
	353+00' EB'	-	357+51' EB'	USH 14 EB 0.5' RT	7	11	-	FILL RUMBLE STRIP
	353+00' EB'	-	357+51' EB'	USH 14 EB 25' LT	7	11	-	FILL RUMBLE STRIP
	359+32' EB'	-	365+00' EB'	USH 14 EB 25' LT	9	14	-	FILL RUMBLE STRIP
	359+32' EB'	-	409+00' EB'	USH 14 EB 0.5' RT	80	125	-	FILL RUMBLE STRIP
	373+00' EB'	-	392+00' EB'	USH 14 EB 25' LT	30	47	-	FILL RUMBLE STRIP
	878+00' WB'	-	881+00' WB'	USH 14 WB 0.5' LT	10	15	-	FILL RUMBLE STRIP
	878+62' WB'	-	888+85' WB'	CROSSOVER X1	160	-	276	
	417+00' EB'	-	439+35' EB'	USH 14 EB 0.5' RT	70	110	-	FILL RUMBLE STRIP
	417+00' EB'	-	513+35' EB'	USH 14 EB	250	-	455	EB SHOULDERS
	441+10' EB'	-	495+00' EB'	USH 14 EB 0.5' RT	170	270	-	FILL RUMBLE STRIP
	496+75' EB'	-	518+50' EB'	USH 14 EB 0.5' RT	70	110	-	FILL RUMBLE STRIP
	417+00' EB'	-	439+35' EB'	USH 14 EB 25' LT	40	56	-	FILL RUMBLE STRIP
	441+10' EB'	-	495+00' EB'	USH 14 EB 25' LT	90	135	-	FILL RUMBLE STRIP
	496+75' EB'	-	518+50' EB'	USH 14 EB 25' LT	40	54	-	FILL RUMBLE STRIP

Removed Items 460.4110.S Reheating  
HMA Pavement Longitudinal Joints and  
SPV.0090.01 Removing HMA Pavement  
Notched Wedge Longitudinal Joint Milling

CONTINUED ON NEXT PAGE

Addendum No. 01  
ID 5155-02-83  
Revised Sheet 143  
October 30, 2019

Addendum No. 01  
ID 5155-02-83  
Revised Sheet 144  
October 30, 2019

ASPHALT ITEMS

455.0605 460.6224 465.0125

CATEGORY	STATION	TO	STATION	LOCATION	TACK COAT	HMA PAVEMENT 4 MT 58-28 S	ASPHALTIC SURFACE TEMPORARY	REMARKS		
								GAL	TON	
	979+80' WB'	-	1001+18' WB'	CROSSOVER X2	300	-	480			
	991+00' WB'	-	1002+00' WB'	USH 14 WB 0.5' LT	40	55	-		FILL RUMBLE STRIP	
	598+75' EB'	-	629+50' EB'	USH 14 EB 0.5' RT	100	155	-		FILL RUMBLE STRIP	
	598+75' EB'	-	629+50' EB'	USH 14 EB 25' LT	50	77	-		FILL RUMBLE STRIP	
	631+60' EB'	-	639+25' EB'	USH 14 EB 25' LT	15	19	-		FILL RUMBLE STRIP	
	631+60' EB'	-	657+00' EB'	USH 14 EB 0.5' RT	80	125	-		FILL RUMBLE STRIP	
	645+10' EB'	-	657+00' EB'	USH 14 EB 25' LT	20	30	-		FILL RUMBLE STRIP	
	1065+60' WB'	-	1081+32' WB'	CROSSOVER X3, X4	550	-	950			
	1068+00' WB'	-	1096+25' WB'	USH 14 WB 0.5' LT	90	140	-		FILL RUMBLE STRIP	
	1068+00' WB'	-	1096+25' WB'	USH 14 WB 25' RT	50	70	-		FILL RUMBLE STRIP	
	613+45' EB'	-	644+15' EB'	USH 14 EB	90	-	155		EB SHOULDERS	
	1081+32' WB'	-	1108+06' WB'	USH 14 WB	70	-	135		WB SHOULDERS	
	1098+40' WB'	-	1121+00' WB'	USH 14 WB 0.5' LT	70	115	-		FILL RUMBLE STRIP	
	1098+40' WB'	-	1104+40' WB'	USH 14 WB 25' RT	10	15	-		FILL RUMBLE STRIP	
	1108+06' WB'	-	1113+69' WB'	USH 14 WB 60' LT	30	-	40		WB SHOULDERS	
	1108+75' WB'	-	1121+00' WB'	USH 14 WB 25' RT	20	30	-		FILL RUMBLE STRIP	
	1110+73' WB'	-	1121+74' WB'	CROSSOVER X5, X6	300	-	500			
TOTAL					4895	4915		2991		

Removed Items 460.4110.S Reheating  
HMA Pavement Longitudinal Joints and  
SPV.0090.01 Removing HMA Pavement  
Notched Wedge Longitudinal Joint Milling



Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0200 Removing Old Structure (station) 01. 906+00	LS	LUMP SUM	_____.
0004	203.0200 Removing Old Structure (station) 02. 1097+00	LS	LUMP SUM	_____.
0006	203.0200 Removing Old Structure (station) 03. 630+61.34	LS	LUMP SUM	_____.
0008	203.0200 Removing Old Structure (station) 04. 224+00	LS	LUMP SUM	_____.
0010	203.0210.S Abatement of Asbestos Containing Material (structure) 01. B-13-793	LS	LUMP SUM	_____.
0012	203.0210.S Abatement of Asbestos Containing Material (structure) 02. B-13-251	LS	LUMP SUM	_____.
0014	203.0210.S Abatement of Asbestos Containing Material (structure) 03. B-13-252	LS	LUMP SUM	_____.
0016	204.0100 Removing Pavement	1,095.000 SY	_____.	_____.
0018	204.0115 Removing Asphaltic Surface Butt Joints	3,400.000 SY	_____.	_____.
0020	204.0120 Removing Asphaltic Surface Milling	30,259.000 SY	_____.	_____.
0022	204.0165 Removing Guardrail	5,199.000 LF	_____.	_____.
0024	204.0170 Removing Fence	210.000 LF	_____.	_____.
0026	204.0180 Removing Delineators and Markers	2.000 EACH	_____.	_____.
0028	204.0210 Removing Manholes	2.000 EACH	_____.	_____.
0030	204.0220 Removing Inlets	11.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	204.0245 Removing Storm Sewer (size) 01. 12-Inch	452.000 LF	_____.	_____.
0034	204.0245 Removing Storm Sewer (size) 02. 18-Inch	766.000 LF	_____.	_____.
0036	204.0245 Removing Storm Sewer (size) 03. 24-Inch	180.000 LF	_____.	_____.
0038	205.0100 Excavation Common	4,032.000 CY	_____.	_____.
0040	205.3000.S Temporary Emergency Pullouts	2.000 EACH	_____.	_____.
0042	206.1000 Excavation for Structures Bridges (structure) 01. B-13-793	LS	LUMP SUM	_____.
0044	206.1000 Excavation for Structures Bridges (structure) 02. B-13-251	LS	LUMP SUM	_____.
0046	206.1000 Excavation for Structures Bridges (structure) 03. B-13-252	LS	LUMP SUM	_____.
0048	206.1000 Excavation for Structures Bridges (structure) 04. B-13-241	LS	LUMP SUM	_____.
0050	208.0100 Borrow	1,422.000 CY	_____.	_____.
0052	208.1100 Select Borrow	480.000 CY	_____.	_____.
0054	210.1500 Backfill Structure Type A	1,034.000 TON	_____.	_____.
0056	213.0100 Finishing Roadway (project) 01. 5155-02-63	1.000 EACH	_____.	_____.
0058	213.0100 Finishing Roadway (project) 01. 5155-02-83	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0060	305.0110 Base Aggregate Dense 3/4-Inch	3,590.000 TON	_____	_____
0062	305.0120 Base Aggregate Dense 1 1/4-Inch	6,149.000 TON	_____	_____
0064	305.0500 Shaping Shoulders	278.000 STA	_____	_____
0066	312.0110 Select Crushed Material	8,680.000 TON	_____	_____
0068	415.0120 Concrete Pavement 12-Inch	774.000 SY	_____	_____
0070	415.0410 Concrete Pavement Approach Slab	706.000 SY	_____	_____
0072	416.0610 Drilled Tie Bars	92.000 EACH	_____	_____
0074	416.1010 Concrete Surface Drains	45.600 CY	_____	_____
0076	455.0605 Tack Coat	4,895.000 GAL	_____	_____
0078	460.2000 Incentive Density HMA Pavement	2,800.000 DOL	1.00000	2,800.00
0082	460.6224 HMA Pavement 4 MT 58-28 S	4,915.000 TON	_____	_____
0084	465.0125 Asphaltic Surface Temporary	2,991.000 TON	_____	_____
0086	465.0400 Asphaltic Shoulder Rumble Strips	52,820.000 LF	_____	_____
0088	502.0100 Concrete Masonry Bridges	1,617.000 CY	_____	_____
0090	502.3200 Protective Surface Treatment	4,690.000 SY	_____	_____
0092	502.3210 Pigmented Surface Sealer	1,072.000 SY	_____	_____
0094	502.4204 Adhesive Anchors No. 4 Bar	32.000 EACH	_____	_____



## Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	502.4205 Adhesive Anchors No. 5 Bar	504.000 EACH	_____.	_____.
0098	505.0400 Bar Steel Reinforcement HS Structures	12,420.000 LB	_____.	_____.
0100	505.0600 Bar Steel Reinforcement HS Coated Structures	340,200.000 LB	_____.	_____.
0102	505.0800.S Bar Steel Reinforcement HS Stainless Structures 01. B-13-793	390.000 LB	_____.	_____.
0104	506.2605 Bearing Pads Elastomeric Non-Laminated	24.000 EACH	_____.	_____.
0106	506.4000 Steel Diaphragms (structure) 01. B-13-241	24.000 EACH	_____.	_____.
0108	506.4000 Steel Diaphragms (structure) 02. B-13-251	20.000 EACH	_____.	_____.
0110	506.4000 Steel Diaphragms (structure) 03. B-13-252	20.000 EACH	_____.	_____.
0112	506.7050.S Removing Bearings (structure) 01. B-13-251	12.000 EACH	_____.	_____.
0114	506.7050.S Removing Bearings (structure) 02. B-13-252	12.000 EACH	_____.	_____.
0116	509.0301 Preparation Decks Type 1	225.000 SY	_____.	_____.
0118	509.0302 Preparation Decks Type 2	169.000 SY	_____.	_____.
0120	509.0500 Cleaning Decks	1,522.000 SY	_____.	_____.
0122	509.1500 Concrete Surface Repair	245.000 SF	_____.	_____.
0124	509.2000 Full-Depth Deck Repair	2.000 SY	_____.	_____.





## Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0126	509.2500 Concrete Masonry Overlay Decks	138.000 CY	_____.	_____.
0128	511.1200 Temporary Shoring (structure) 01. B-13-793	2,800.000 SF	_____.	_____.
0130	516.0500 Rubberized Membrane Waterproofing	67.000 SY	_____.	_____.
0132	521.1012 Apron Endwalls for Culvert Pipe Steel 12-Inch	3.000 EACH	_____.	_____.
0134	521.1018 Apron Endwalls for Culvert Pipe Steel 18-Inch	1.000 EACH	_____.	_____.
0136	521.1618 Apron Endwalls for Culvert Pipe Sloped Side Drains Steel 18-Inch 10 to 1	2.000 EACH	_____.	_____.
0138	521.3112 Culvert Pipe Corrugated Steel 12-Inch	200.000 LF	_____.	_____.
0140	521.3118 Culvert Pipe Corrugated Steel 18-Inch	766.000 LF	_____.	_____.
0142	521.3124 Culvert Pipe Corrugated Steel 24-Inch	180.000 LF	_____.	_____.
0144	550.0500 Pile Points	58.000 EACH	_____.	_____.
0146	550.2106 Piling CIP Concrete 10 3/4 X 0.365-Inch	2,830.000 LF	_____.	_____.
0148	603.8000 Concrete Barrier Temporary Precast Delivered	10,450.000 LF	_____.	_____.
0150	603.8125 Concrete Barrier Temporary Precast Installed	21,770.000 LF	_____.	_____.
0152	604.0600 Slope Paving Select Crushed Material	362.000 SY	_____.	_____.
0154	604.9010.S Slope Paving Repair Crushed Aggregate	216.000 CY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0156	604.9015.S Reseal Crushed Aggregate Slope Paving	310.000 SY	_____.	_____.
0158	606.0200 Riprap Medium	234.000 CY	_____.	_____.
0160	608.0212 Storm Sewer Pipe Reinforced Concrete Class II 12-Inch	46.000 LF	_____.	_____.
0162	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	32.000 LF	_____.	_____.
0164	611.0530 Manhole Covers Type J	2.000 EACH	_____.	_____.
0166	611.0606 Inlet Covers Type B	3.000 EACH	_____.	_____.
0168	611.0642 Inlet Covers Type MS	12.000 EACH	_____.	_____.
0170	611.0654 Inlet Covers Type V	4.000 EACH	_____.	_____.
0172	611.2005 Manholes 5-FT Diameter	2.000 EACH	_____.	_____.
0174	611.3220 Inlets 2x2-FT	7.000 EACH	_____.	_____.
0176	611.3902 Inlets Median 2 Grate	6.000 EACH	_____.	_____.
0178	612.0212 Pipe Underdrain Unperforated 12-Inch	208.000 LF	_____.	_____.
0180	612.0406 Pipe Underdrain Wrapped 6-Inch	572.000 LF	_____.	_____.
0182	613.1100.S Cable Barrier Type 1	8,970.000 LF	_____.	_____.
0184	613.1200.S Cable Barrier End Terminal Type 1	8.000 EACH	_____.	_____.
0186	614.0150 Anchor Assemblies for Steel Plate Beam Guard	16.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0188	614.1000 MGS Guardrail Temporary	847.000 LF	_____.	_____.
0190	614.1100 MGS Guardrail Temporary Thrie Beam Transition	158.000 LF	_____.	_____.
0192	614.1200 MGS Guardrail Temporary Terminal EAT	4.000 EACH	_____.	_____.
0194	614.2300 MGS Guardrail 3	4,929.000 LF	_____.	_____.
0196	614.2500 MGS Thrie Beam Transition	631.000 LF	_____.	_____.
0198	614.2610 MGS Guardrail Terminal EAT	14.000 EACH	_____.	_____.
0200	614.2620 MGS Guardrail Terminal Type 2	4.000 EACH	_____.	_____.
0202	616.0100 Fence Woven Wire (height) 01. 4 FT	210.000 LF	_____.	_____.
0204	618.0100 Maintenance And Repair of Haul Roads (project) 01. 5155-02-83	1.000 EACH	_____.	_____.
0206	619.1000 Mobilization	1.000 EACH	_____.	_____.
0208	624.0100 Water	93.000 MGAL	_____.	_____.
0210	625.0500 Salvaged Topsoil	20,470.000 SY	_____.	_____.
0212	628.1504 Silt Fence	825.000 LF	_____.	_____.
0214	628.1520 Silt Fence Maintenance	825.000 LF	_____.	_____.
0216	628.1905 Mobilizations Erosion Control	14.000 EACH	_____.	_____.
0218	628.1910 Mobilizations Emergency Erosion Control	11.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0220	628.2004 Erosion Mat Class I Type B	20,470.000 SY	_____.	_____.
0222	628.7005 Inlet Protection Type A	6.000 EACH	_____.	_____.
0224	628.7504 Temporary Ditch Checks	100.000 LF	_____.	_____.
0226	628.7555 Culvert Pipe Checks	4.000 EACH	_____.	_____.
0228	629.0210 Fertilizer Type B	14.000 CWT	_____.	_____.
0230	630.0130 Seeding Mixture No. 30	381.000 LB	_____.	_____.
0232	633.0100 Delineator Posts Steel	2.000 EACH	_____.	_____.
0234	633.0500 Delineator Reflectors	2.000 EACH	_____.	_____.
0236	633.1100 Delineators Temporary	117.000 EACH	_____.	_____.
0238	633.5200 Markers Culvert End	11.000 EACH	_____.	_____.
0240	634.0618 Posts Wood 4x6-Inch X 18-FT	2.000 EACH	_____.	_____.
0242	637.2210 Signs Type II Reflective H	40.000 SF	_____.	_____.
0244	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0246	643.0300 Traffic Control Drums	108,278.000 DAY	_____.	_____.
0248	643.0420 Traffic Control Barricades Type III	12,786.000 DAY	_____.	_____.
0250	643.0705 Traffic Control Warning Lights Type A	12,046.000 DAY	_____.	_____.
0252	643.0715 Traffic Control Warning Lights Type C	18,494.000 DAY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0254	643.0800 Traffic Control Arrow Boards	849.000 DAY	_____.	_____.
0256	643.0900 Traffic Control Signs	41,607.000 DAY	_____.	_____.
0258	643.0910 Traffic Control Covering Signs Type I	15.000 EACH	_____.	_____.
0260	643.0920 Traffic Control Covering Signs Type II	161.000 EACH	_____.	_____.
0262	643.1000 Traffic Control Signs Fixed Message	66.750 SF	_____.	_____.
0264	643.1050 Traffic Control Signs PCMS	380.000 DAY	_____.	_____.
0266	643.1100.S Dynamic Late Merge System	185.000 DAY	_____.	_____.
0268	643.1200.S Portable Automated Real-Time Traffic Queue Warning System	130.000 DAY	_____.	_____.
0270	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0272	645.0111 Geotextile Type DF Schedule A	92.000 SY	_____.	_____.
0274	645.0120 Geotextile Type HR	135.000 SY	_____.	_____.
0276	646.1020 Marking Line Epoxy 4-Inch	85,175.000 LF	_____.	_____.
0278	646.3020 Marking Line Epoxy 8-Inch	2,998.000 LF	_____.	_____.
0280	646.5020 Marking Arrow Epoxy	11.000 EACH	_____.	_____.
0282	646.5120 Marking Word Epoxy	3.000 EACH	_____.	_____.
0284	646.7220 Marking Chevron Epoxy 24-Inch	1,250.000 LF	_____.	_____.



## Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0286	646.9000 Marking Removal Line 4-Inch	61,315.000 LF	_____.	_____.
0288	646.9100 Marking Removal Line 8-Inch	950.000 LF	_____.	_____.
0290	646.9300 Marking Removal Special Marking	13.000 EACH	_____.	_____.
0292	649.0150 Temporary Marking Line Removable Tape 4-Inch	146,155.000 LF	_____.	_____.
0294	649.0250 Temporary Marking Line Removable Tape 8-Inch	850.000 LF	_____.	_____.
0296	649.0550 Temporary Marking Arrow Removable Tape	4.000 EACH	_____.	_____.
0298	649.0960 Temporary Marking Removable Mask Out Tape 6-Inch	420.000 LF	_____.	_____.
0300	650.4000 Construction Staking Storm Sewer	21.000 EACH	_____.	_____.
0302	650.4500 Construction Staking Subgrade	6,415.000 LF	_____.	_____.
0304	650.5000 Construction Staking Base	6,415.000 LF	_____.	_____.
0306	650.7000 Construction Staking Concrete Pavement	407.000 LF	_____.	_____.
0308	650.8000 Construction Staking Resurfacing Reference	3,430.000 LF	_____.	_____.
0310	650.9910 Construction Staking Supplemental Control (project) 01. 5155-02-83	LS	LUMP SUM	_____.
0312	650.9920 Construction Staking Slope Stakes	15,190.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0314	661.0200 Temporary Traffic Signals for Intersections (location) 01. CTH MM & McCoy Road	LS	LUMP SUM	_____.
0316	690.0150 Sawing Asphalt	800.000 LF	_____.	_____.
0318	690.0250 Sawing Concrete	74.000 LF	_____.	_____.
0320	715.0415 Incentive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0322	715.0502 Incentive Strength Concrete Structures	10,702.000 DOL	1.00000	10,702.00
0324	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,000.000 HRS	5.00000	5,000.00
0326	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	800.000 HRS	5.00000	4,000.00
0328	SPV.0060 Special 01. Verify Landmark Reference Monuments	1.000 EACH	_____.	_____.
0330	SPV.0060 Special 02. Landmark Reference Monuments Special	1.000 EACH	_____.	_____.
0332	SPV.0060 Special 03. Test Pits	48.000 EACH	_____.	_____.
0336	SPV.0090 Special 02. Rout and Seal Special	1,080.000 LF	_____.	_____.
0338	SPV.0105 Special 01. Remove Temporary Crossover X1	LS	LUMP SUM	_____.
0340	SPV.0105 Special 02. Remove Temporary Crossover X2	LS	LUMP SUM	_____.
0342	SPV.0105 Special 03. Remove Temporary Crossover X3, X4	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20191112006 Project(s): 5155-02-63, 5155-02-83

Federal ID(s): WISC 2019675, WISC 2019676

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0344	SPV.0105 Special 04. Remove Temporary Crossover X5, X6	LS	LUMP SUM	_____.
0346	SPV.0180 Special 01. Joint Repair Milling	360.000 SY	_____.	_____.
	Section: 0001		Total:	_____.
			Total Bid:	_____.