



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

November 5, 2019

NOTICE TO ALL CONTRACTORS:

Proposal #17: 1320-17-70, WISC 2019 686
Janesville - Delavan
USH 14 / STH 89 to Turtle Creek Drive
STH 11
Walworth County

Letting of November 12, 2019

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
4	Traffic

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
465.0125	Asphaltic Surface Temporary	Ton	0	3,875	3,875

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
196	Miscellaneous Quantities – Added Asphaltic Surface Temporary to table

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

1320-17-70

November 5, 2019

Special Provisions

4. Traffic.

Replace paragraph one with the following:

Access will be maintained for residents and businesses during the project. A hard closure of STH 11 is needed to remove the box culvert and place the three 72-inch culvert pipe and mortar endwalls. The closure will be allowed beginning on June 15, 2020 and must end by 12:01 AM, August 29, 2020. Notice of the future detour must be posted by two weeks prior to beginning the closure.

Schedule of Items

Attached, dated November 5, 2019, are the revised Schedule of Items Page 12.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 196.

END OF ADDENDUM

Addendum No. 02
ID 1320-17-70
Revised Sheet 196
November 5, 2019

3

STATION LIMITS	LOCATION	SAFETY EDGE		3MT 58-28 S		HMA PAVEMENT		TACK COAT	
		TONS	TONS	TONS	TONS	TONS	TONS	TONS	GAL
20+75-21+00	STH 11	--	--	--	13	--	--	--	8
21+00-31+81	STH 11	170	1168	1337	502	--	--	--	378
31+81-87+68	STH 11	494	3907	4401	2241	--	--	--	1638
87+68-104+14	STH 11	194	1669	1885	957	--	--	--	655
104+14-106+75	STH 11	31	187	218	107	--	--	--	78
106+75-109+53	STH 11	33	219	252	126	--	--	--	90
109+53-109+78	STH 11	--	--	--	12	--	--	--	7
110+49-110+74	STH 11	--	--	--	12	--	--	--	7
110+74-112+49	STH 11	21	139	160	80	--	--	--	57
112+49-116+75	STH 11	50	306	356	175	--	--	--	127
116+75-125+00	STH 11	97	751	849	431	--	--	--	300
125+00-172+66	STH 11	562	3242	3804	1860	--	--	--	1367
172+66-180+58	STH 11	93	758	851	435	--	--	--	300
180+58-197+27	STH 11	197	1159	1356	665	--	--	--	487
197+27-207+26	STH 11	118	991	1109	568	--	--	--	390
207+26-217+92	STH 11	126	768	893	440	--	--	--	320
217+92-225+68	STH 11	92	747	839	429	--	--	--	296
225+68-242+00	STH 11	193	1196	1389	686	--	--	--	497
242+00-242+25	STH 11	--	--	9	--	--	--	--	5
5+31-8+77	PINKS LN	--	382	382	167	--	--	--	96
8+77-13+97	PINKS LN	--	--	--	123	--	--	--	55
91+98 RT	KENNY LN	--	91	91	61	--	--	--	35
121+45 RT	OLD 89 RD	--	118	118	76	--	--	--	43
176+33 LT	KIUG RD	--	147	147	92	--	--	--	53
200+93 LT	WESTWOOD DR	--	91	91	60	--	--	--	34
203+77 RT	LAWSON SCHOOL RD	--	105	105	68	--	--	--	39
223+07 RT	AUTUMN DR	--	103	103	71	--	--	--	40
223+07 LT	PLEASANT ST (W)	--	66	66	45	--	--	--	26
230+73 LT	PLEASANT ST (MIDDLE)	--	61	61	43	--	--	--	25
237+27 LT	PLEASANT ST (E)	--	72	72	49	--	--	--	28
TOTAL			20937	10312	290				7477

STATION	ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES		BACKFILL SLURRY SPV.0035.01 CY
	TON	TON	
20+00-71+00	44	119	757
71+00-125+00	19	1215	106
125+00-188+00	40	370	130
188+00-242+00	50	2171	117
TOTAL	153	3875	1110

STATION LIMITS	LOCATION	BASE AGG.	
		DENSE 3/4 INCH 305.0110	TON
20+75-21+00	STH 11	--	--
21+00-31+81	STH 11	275	3843
31+81-87+68	STH 11	867	4913
87+68-104+14	STH 11	180	2145
104+14-106+75	STH 11	44	237
106+75-109+53	STH 11	47	235
109+53-109+78	STH 11	--	--
110+49-110+74	STH 11	--	--
110+74-112+49	STH 11	30	178
112+49-116+75	STH 11	62	364
116+75-125+00	STH 11	127	1216
125+00-172+66	STH 11	734	3539
172+66-180+58	STH 11	120	1304
180+58-197+27	STH 11	270	1376
197+27-207+26	STH 11	141	1588
207+26-217+92	STH 11	168	948
217+92-225+68	STH 11	99	645
225+68-242+00	STH 11	252	1081
242+00-242+25	STH 11	--	--
5+31-8+77	PINKS LN	104	1276
8+77-13+97	PINKS LN	--	--
91+98 RT	KENNY LN	9	178
121+45 RT	OLD 89 RD	16	222
176+33 LT	KIUG RD	28	287
200+93 LT	WESTWOOD DR	6	205
203+77 RT	LAWSON SCHOOL RD	11	245
223+07 RT	AUTUMN DR	0	78
223+07 LT	PLEASANT ST (W)	3	175
230+73 LT	PLEASANT ST	1	190
237+27 LT	PLEASANT ST (E)	4	188
TOTAL		3599	26656

LOCATION	UNDISTRIBUTED	
	TON	TON
BREAKER RUN 311.0110	5250	
TOTAL	5250	

PROJECT NO. 1320-17-70	Hwy: STH 11	COUNTY: WALLWORTH	MISCELLANEOUS QUANTITIES	SHEET: 196
FILENAME:		PLOT DATE:	PLOT NAME:	PLOT SCALE: 1:1

3



Proposal Schedule of Items

Proposal ID: 20191112017 Project(s): 1320-17-70

Federal ID(s): WISC 2019686

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0334	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	3,600.000 HRS	5.00000	18,000.00
0336	SPV.0035 Special 02. Backfill Slurry	1,110.000 CY	_____.	_____.
0338	SPV.0060 Special 01. Temporary Steel Cover Plates	8.000 EACH	_____.	_____.
0340	SPV.0060 Special 02. Field Facilities Office Space	1.000 EACH	_____.	_____.
0342	SPV.0090 Special 01. Heavy Duty Silt Fence	1,468.000 LF	_____.	_____.
0344	646.4520 Marking Line Same Day Epoxy 4-Inch	25,093.000 LF	_____.	_____.
0346	465.0125 Asphaltic Surface Temporary	3,875.000 TON	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.