



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

February 6, 2020

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #23: 4210-07-71
T Greenbush,
Mullet River Bridge
CTH A
Sheboygan County

Letting of February 11, 2020

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
201.0120	Clearing	ID	30	-30	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
15	Revised Clearing 201.0120

Schedule of Items

Attached, dated February 6, 2020, are the revised Schedule of Items Pages 1 – 6.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 15.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

CLEARING AND GRUBBING

CATEGORY	STA	TO STA	GRUBBING	STA	ID
0010	78+59.53	TO 90+22.69	3	3	30
TOTALS			3	3	30

FINISHING ROADWAY 4210-07-71

CATEGORY	PROJECT ID	EACH
0010	4197-04-71	1
TOTALS		1

OBLITERATING OLD ROAD

CATEGORY	STA	TO STA	ROAD	STA	6
0010	81+00	87+00	TOTAL	6	6

CONCRETE PAVEMENT APPROACH SLAB

CATEGORY	STA	TO STA	APPROACH SLAB	SY
0010	78+59.53	TO 85+24.40	80	
0010	85+89.63	TO 90+22.69	79	
TOTALS			159	

MOBILIZATION

CATEGORY	PROJECT ID	EACH
0010	4210-07-71	1
TOTALS		1

EARTHWORK SUMMARY

CATEGORY	DIVISION	FROM/TO STATION	LOCATION	EXCAVATION (1) COMMON	EXCAVATION (2) CUT	EMB (3) CY	UNAVAILABLE PAVEMENT (4) CY	AVAILABLE MATERIAL (5) CY	UNEXPANDED FILL CY	EXPANDED FILL (1.20) CY	MASS ORDNATE 4/14 WASTE CY	BORROW CY
0010	1	78+59.53 - 85+24.40	SOUTH APPROACH	1273	0	1273	124	1149	1711	2053	-904	0
0010	2	85+89.63 - 90+22.69	NORTH APPROACH	1558	0	1558	81	1477	36	43	1434	0
UNDISTRIBUTED				0	1257	0	0	0	0	0	0	0
GRAND TOTAL				2831	1257	4088	205	2626	1747	2096	-530	0
TOTAL COMMON EXCAVATION				4088								2338

Addendum No. 02
ID 4210-07-71
Revised Sheet 15
February 6, 2020

PAVING ITEMS

CATEGORY	LOCATION	STA	TO STA	BASE AGGREGATE 1/2-INCH DENSE	BREAKER RUN	TACK COAT	HMA PAVEMENT 3 LT 58-28 S	HMA PAVEMENT 4 LT 58-28 S	ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES	WATER
0010	78+59.53 TO 85+24.40	229	2,485	1732	119	343	240	5	34.3	
0010	85+89.63 TO 90+22.69	151	815	568	39	112	79	5	22.5	
TOTALS		380	3,300	2,300	158	455	319	10	56.8	

LANDSCAPING ITEMS

CATEGORY	LOCATION	STA	TO STA	TOPSOIL	MULCHING	FERTILIZER TYPE B	SEEDING MIXTURE NO. 80	BORROW PIT	SEED
0010	78+59.53 TO 90+22.69	1678	1678	1.50	1.50	9	9	27	25
0010	78+59.53 TO 90+22.69	1818	1818	1.50	1.50	18	18	27	25
SUB-TOTAL		3496	3496	3.00	3.00	27	27	54	50
25% UNDISTRIBUTED QUANTITIES		874	874	1.00	1.00	7	7	21	12.5
TOTALS		4370	4370	4.00	4.00	34	34	75	62.5

CULVERT PIPE

CATEGORY	STA	TO STA	LOCATION	APRON ENDWALL FOR CULVERT PIPE	CULVERT PIPE	CORRUGATED PIPE STEEL	12-INCH THICKNESS	CHECK
0010	79+06	26' LT	2	25	1			
0010	80+30	26' LT	2	25	1			
0010	87+63	26' RT	2	25	1			
0010	88+13	25' RT	2	25	1			
TOTALS		8	100		4			

GUARDRAIL

CATEGORY	STA	TO STA	LOCATION	MGS THREE BEAM TRANSITION	MGS GUARDRAIL TERMINAL/EA
0010	84+14.71	85+08.23	LF	39	1
0010	84+29.37	85+22.89	RT	39	1
0010	85+91.13	86+84.65	LF	39	1
0010	86+05.80	86+99.32	RT	39	1
TOTALS		156	4		

MISCELLANEOUS QUANTITIES

CATEGORY	STA	TO STA	LOCATION	ASPHALTIC SURFACE DRIVEWAYS AND FIELD ENTRANCES	WATER	SEEDING MIXTURE NO. 80	BORROW PIT	SEED
0010	465.0120	624.0100	5	5	10	34.3	5	22.5
TOTALS			10	10	20	56.8	10	45.0

PROJECT NO: 4197-04-71 **HWY: LOCAL ROAD** **COUNTY: SHEBOYGAN** **SHEET 15**

FILE NAME: P:\LAYOUT NAME - 030201.rwg PLOT DATE: 2/6/2020 1:52 PM PLOT NAME: <USER> WISDOT/CADD SHEET 02



Proposal Schedule of Items

Proposal ID: 20200211023 Project(s): 4210-07-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	3.000 STA	_____.	_____.
0006	201.0205 Grubbing	3.000 STA	_____.	_____.
0008	201.0220 Grubbing	30.000 ID	_____.	_____.
0010	203.0100 Removing Small Pipe Culverts	2.000 EACH	_____.	_____.
0014	204.0250 Abandoning Manholes	1.000 EACH	_____.	_____.
0016	205.0100 Excavation Common	4,088.000 CY	_____.	_____.
0018	206.1000 Excavation for Structures Bridges (structure) 01. B-59-199	LS	LUMP SUM	_____.
0020	208.0100 Borrow	2,338.000 CY	_____.	_____.
0022	210.1500 Backfill Structure Type A	462.000 TON	_____.	_____.
0024	213.0100 Finishing Roadway (project) 01. 4210-07-71	1.000 EACH	_____.	_____.
0026	214.0100 Obliterating Old Road	6.000 STA	_____.	_____.
0028	305.0110 Base Aggregate Dense 3/4-Inch	380.000 TON	_____.	_____.
0030	305.0120 Base Aggregate Dense 1 1/4-Inch	3,300.000 TON	_____.	_____.
0032	311.0110 Breaker Run	2,300.000 TON	_____.	_____.
0034	415.0410 Concrete Pavement Approach Slab	159.000 SY	_____.	_____.
0036	455.0605 Tack Coat	158.000 GAL	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200211023 Project(s): 4210-07-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0038	460.2000 Incentive Density HMA Pavement	500.000 DOL	1.00000	500.00
0040	460.5223 HMA Pavement 3 LT 58-28 S	455.000 TON	_____	_____
0042	460.5224 HMA Pavement 4 LT 58-28 S	319.000 TON	_____	_____
0044	465.0120 Asphaltic Surface Driveways and Field Entrances	10.000 TON	_____	_____
0046	502.0100 Concrete Masonry Bridges	172.000 CY	_____	_____
0048	502.3200 Protective Surface Treatment	217.000 SY	_____	_____
0050	502.3210 Pigmented Surface Sealer	89.000 SY	_____	_____
0052	503.0136 Prestressed Girder Type I 36-Inch	310.000 LF	_____	_____
0054	505.0400 Bar Steel Reinforcement HS Structures	3,900.000 LB	_____	_____
0056	505.0600 Bar Steel Reinforcement HS Coated Structures	19,930.000 LB	_____	_____
0058	506.2605 Bearing Pads Elastomeric Non-Laminated	10.000 EACH	_____	_____
0060	506.4000 Steel Diaphragms (structure) 01. B-59-199	4.000 EACH	_____	_____
0062	516.0500 Rubberized Membrane Waterproofing	18.000 SY	_____	_____
0064	521.1012 Apron Endwalls for Culvert Pipe Steel 12-Inch	8.000 EACH	_____	_____
0066	521.3112 Culvert Pipe Corrugated Steel 12-Inch	100.000 LF	_____	_____



Proposal Schedule of Items

Proposal ID: 20200211023 Project(s): 4210-07-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0068	550.0500 Pile Points	14.000 EACH	_____.	_____.
0070	550.1120 Piling Steel HP 12-Inch X 53 Lb	1,050.000 LF	_____.	_____.
0072	606.0300 Riprap Heavy	200.000 CY	_____.	_____.
0074	612.0406 Pipe Underdrain Wrapped 6-Inch	172.000 LF	_____.	_____.
0076	614.0150 Anchor Assemblies for Steel Plate Beam Guard	4.000 EACH	_____.	_____.
0078	614.0200 Steel Thrie Beam Structure Approach	20.000 LF	_____.	_____.
0080	614.2500 MGS Thrie Beam Transition	156.000 LF	_____.	_____.
0082	614.2610 MGS Guardrail Terminal EAT	4.000 EACH	_____.	_____.
0084	619.1000 Mobilization	1.000 EACH	_____.	_____.
0086	624.0100 Water	56.800 MGAL	_____.	_____.
0088	625.0500 Salvaged Topsoil	4,370.000 SY	_____.	_____.
0090	627.0200 Mulching	4,370.000 SY	_____.	_____.
0092	628.1504 Silt Fence	855.000 LF	_____.	_____.
0094	628.1520 Silt Fence Maintenance	855.000 LF	_____.	_____.
0096	628.1905 Mobilizations Erosion Control	4.000 EACH	_____.	_____.
0098	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200211023 Project(s): 4210-07-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0100	628.2006 Erosion Mat Urban Class I Type A	3,737.000 SY	_____.	_____.
0102	628.6005 Turbidity Barriers	269.000 SY	_____.	_____.
0104	628.7504 Temporary Ditch Checks	210.000 LF	_____.	_____.
0106	628.7555 Culvert Pipe Checks	4.000 EACH	_____.	_____.
0108	629.0210 Fertilizer Type B	4.000 CWT	_____.	_____.
0110	630.0180 Seeding Mixture No. 80	34.000 LB	_____.	_____.
0112	630.0300 Seeding Borrow Pit	13.000 LB	_____.	_____.
0114	630.0500 Seed Water	85.000 MGAL	_____.	_____.
0116	634.0612 Posts Wood 4x6-Inch X 12-FT	6.000 EACH	_____.	_____.
0118	637.2230 Signs Type II Reflective F	22.000 SF	_____.	_____.
0120	638.2602 Removing Signs Type II	10.000 EACH	_____.	_____.
0122	638.3000 Removing Small Sign Supports	10.000 EACH	_____.	_____.
0124	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0126	643.0420 Traffic Control Barricades Type III	1,350.000 DAY	_____.	_____.
0128	643.0705 Traffic Control Warning Lights Type A	2,700.000 DAY	_____.	_____.
0130	643.0900 Traffic Control Signs	12,960.000 DAY	_____.	_____.
0132	643.0920 Traffic Control Covering Signs Type II	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200211023 Project(s): 4210-07-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0134	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0136	645.0111 Geotextile Type DF Schedule A	46.000 SY	_____.	_____.
0138	645.0120 Geotextile Type HR	322.000 SY	_____.	_____.
0140	646.1020 Marking Line Epoxy 4-Inch	4,656.000 LF	_____.	_____.
0142	650.4500 Construction Staking Subgrade	1,164.000 LF	_____.	_____.
0144	650.5000 Construction Staking Base	1,164.000 LF	_____.	_____.
0146	650.6500 Construction Staking Structure Layout (structure) 01. B-59-199	LS	LUMP SUM	_____.
0148	650.9910 Construction Staking Supplemental Control (project) 01. 4210-07-71	LS	LUMP SUM	_____.
0150	650.9920 Construction Staking Slope Stakes	2,328.000 LF	_____.	_____.
0152	690.0150 Sawing Asphalt	70.000 LF	_____.	_____.
0154	715.0415 Incentive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0156	715.0502 Incentive Strength Concrete Structures	1,080.000 DOL	1.00000	1,080.00
0158	999.1500.S Crack and Damage Survey	LS	LUMP SUM	_____.
0160	203.0600.S Removing Old Structure Over Waterway With Minimal Debris (station) 01. STA. 85+71.50	LS	LUMP SUM	_____.

Section: 0001

Total: _____.

Total Bid: _____.

