



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

February 3, 2020

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #25: 9266-11-03, WISC 2020 049**  
**V Ashwaubenon, Vanderperren Way**  
**Holmgren Way – Ashland Avenue**  
**CTH HH**  
**Brown County**

### Letting of February 11, 2020

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
8	Work By Others (Brown County)

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
205.0100	Common Excavation	CY	13,130	-1,264	11,866

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
650.4500	Construction Staking Subgrade	LF	0	3,625	3,625
650.5000	Construction Staking Base	LF	0	3,625	3,625

**Plan Sheets:**

<b>Revised Plan Sheets</b>	
<b>Plan Sheet</b>	<b>Plan Sheet Title (brief description of changes to sheet)</b>
58	Miscellaneous Quantities (Earthwork Summary – Revised subtotal for EBS Excavation under division for Stage 3A, which ultimately affects the project total for bid item Common Excavation. Removed zeros for each location under EBS Excavation, Reduced EBS in Fill, and Expanded EBS Backfill to clarify that EBS is only included as an undistributed quantity. Included quantities for Salvaged/Unusable Pavement Material. Revised subtotal and total quantities for Reduced EBS in Fill and Expanded EBS Backfill. Revised quantities for Mass Ordinate and Waste per these previous changes.)
69	Miscellaneous Quantities – (added two new bid items, Construction Staking Subgrade and Construction Staking Base, to the Construction Staking table)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**9266-11-03**

**February 3, 2020**

**Special Provisions**

**8. Work by Others (Brown County).**

*Insert the following paragraph after the bulleted list in section titled **Paving Operations**:*

Brown County will perform the final grading prior to paving operations. Provide additional base material, someone to haul away excess base material, and/or direction on where to stockpile excess base material, as needed, to Brown County.

Provide lighting for nighttime work performed by the County as described in the Special Provision "Nighttime Work Lighting-Stationary".

**Schedule of Items**

Attached, dated February 3, 2020, are the revised Schedule of Items Pages 1 and 9.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 58 and 69.

END OF ADDENDUM

EARTHWORK SUMMARY

Division	From/To Station	Location	205.0100 Common Excavation (1)		Salvaged/Unusable Pavement Material (4)	Available Material (5)	Reduced EBS Backfill (7)		Expanded Fill (8)		Mass Ordinate +/- (9)	Waste	Comment:
			Cut (2)	EBS Excavation (3)			Factor	Factor	Unexpanded Fill	Factor			
Stage 2	06+21'E/B/24+22EB' 11+85'W/B/16+27WB' 332+24'A/332+70'A' 00+06'ANE/700+22'ANE' 00+03'BNW/01+27'BNW' 00+00'D/00+24'D' 00+01'SW/01+98'SW' 00+00'S/02+85'S'	CTH HH Eastbound CTH HH Westbound STH 172 Off Ramp STH 172 On Ramp NE Curb Return STH 172 On Ramp NW Curb Return STH 172 On Ramp Middle Ashland Avenue SW Curb Return Holmgren Way Sidewalk	5,103 699 111 12 102 31 210 49	1,263 1,263	1,575 430 0 0 0 0 0 0	3,528 269 111 12 102 31 210 49	0.89 1.30	1.25 1.25	1,379 235 0 0 202 0 1 3	1,724 294 0 0 252 0 1 4	1,804 -26 111 12 -150 31 210 45	1,804 0 111 12 0 0 210 45	
Stage 2 Subtotal		Undistributed EBS Excavation	6,317	1,263	2,005	4,312	0	1,643	1,820	2,275	395	395	
Stage 3A	06+08'W/B/24+30'W/B' 00+31'ANW/01+76'ANW' 323+08'C/325+69'C' 00+24'D/02+10'D' 00+01'NW/00+76'NW'	CTH HH Westbound STH 172 Off Ramp NW Curb Return STH 172 On Ramp East STH 172 On Ramp Middle Ashland Avenue NW Curb Return Undistributed EBS Excavation	2,763 169 469 117 54	714 714	1,315 0 0 0 0	1,448 169 469 117 54			530 36 262 0 3	663 45 327 0 4	785 124 141 117 50	785 124 141 117 50	
Stage 3A Subtotal		Undistributed EBS Excavation	3,571	714	1,315	2,256	0	929	831	1,039	288	288	
Grand Total		Total Common Excavation	9,889	1,978	3,320	6,569	0	2,571	2,651	3,314	683	683	
			11,866										

Notes:

- (1) Common Excavation is the sum of the Cut and EBS Excavation columns. Item number 205.0100. No deductions are made from the volume measured under the Excavation Common bid item for pavement removed under the Removing Pavement bid item.
- (2) Salvaged/Unusable Pavement Material is included in Cut.
- (3) EBS Excavation to be backfilled with Cut.
- (4) Salvaged/Unusable Pavement Material
- (5) Available Material = Cut - Salvaged/Unusable Pavement Material
- (6) Reduced EBS in Fill - Excavated EBS material is usable in Fills outside the 1:1 slope. EBS in Fill Reduction factor = 0.8
- (7) Expanded EBS Backfill - This is to be filled with Cut material. EBS Backfill Factor = 1.3.
- (8) Expanded Fill Factor = 1.25  
Depending on selections:  
Or  
Or  
Or
- (9) The Mass Ordinate + or - Qty calculated for the Division. Plus quantity indicates an excess of material within the Division. Minus quantity indicates a shortage of material within the Division.

Addendum No. 01  
ID 9266-11-03  
Revised Sheet 58  
February 3, 2020

**Expanded Fill = (Unexpanded Fill - Rock \* Rock Factor - Reduced Marsh - Reduced EBS) \* Fill Factor**  
 Expanded Fill = (Unexpanded Fill - Rock \* Rock Factor - Reduced EBS) \* Fill Factor  
 Expanded Fill = (Unexpanded Fill - Rock \* Rock Factor - Reduced Marsh) \* Fill Factor  
 Expanded Fill = (Unexpanded Fill - Rock \* Rock Factor) \* Fill Factor

\*\*\*ALL ITEMS CATEGORY 0010 UNLESS OTHERWISE NOTED.





Proposal Schedule of Items

Proposal ID: 20200211025 Project(s): 9266-11-03

Federal ID(s): WISC 2020049

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0110 Clearing	80.000 SY	_____.	_____.
0004	201.0120 Clearing	141.000 ID	_____.	_____.
0006	201.0210 Grubbing	80.000 SY	_____.	_____.
0008	201.0220 Grubbing	141.000 ID	_____.	_____.
0010	203.0100 Removing Small Pipe Culverts	2.000 EACH	_____.	_____.
0012	204.0100 Removing Pavement	13,380.000 SY	_____.	_____.
0014	204.0150 Removing Curb & Gutter	28.000 LF	_____.	_____.
0016	204.0155 Removing Concrete Sidewalk	131.000 SY	_____.	_____.
0018	204.0165 Removing Guardrail	40.000 LF	_____.	_____.
0020	204.0170 Removing Fence	155.000 LF	_____.	_____.
0022	204.0195 Removing Concrete Bases	2.000 EACH	_____.	_____.
0024	204.0210 Removing Manholes	1.000 EACH	_____.	_____.
0026	204.0220 Removing Inlets	28.000 EACH	_____.	_____.
0028	204.0245 Removing Storm Sewer (size) 01. 12-Inch	735.000 LF	_____.	_____.
0030	204.0291.S Abandoning Sewer	11.000 CY	_____.	_____.
0032	205.0100 Excavation Common	11,866.000 CY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200211025 Project(s): 9266-11-03

Federal ID(s): WISC 2020049

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0256	SPV.0060 Special 02. Adjusting Sanitary Manhole Covers	7.000 EACH	_____.	_____.
0258	SPV.0060 Special 03. Adjusting Water Valve Boxes	3.000 EACH	_____.	_____.
0260	SPV.0060 Special 04. Covering Traffic Signal Head	7.000 EACH	_____.	_____.
0262	SPV.0090 Special 01. Turtle Fence Salvaged	250.000 LF	_____.	_____.
0264	SPV.0105 Special 01. Remove Signal	LS	LUMP SUM	_____.
0266	SPV.0170 Special 01. Proof Rolling	40.000 STA	_____.	_____.
0268	650.4500 Construction Staking Subgrade	3,625.000 LF	_____.	_____.
0270	650.5000 Construction Staking Base	3,625.000 LF	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.

