



Wisconsin Department of Transportation

February 26, 2020

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

Proposal #33: 7735-01-61, WISC 2020 090
Gilmanton - Independence
STH 88 to STH 93
STH 121
Buffalo & Trempealeau County

7735-01-62, WISC 2020 091
Gilmanton - Independence
CTH BB West Junction to STH 93
STH 121
Buffalo & Trempealeau County

Letting of March 10, 2020

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
646.1020	Marking Line Epoxy 4-Inch	LF	101,546	185,292	286,838
646.4520	Marking Line Same Day Epoxy 4-Inch	LF	99,318	35,015	134,333
649.0105	Temporary Marking Line Paint 4-Inch	LF	198,636	63,830	262,466

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
54	Pavement marking line quantities were updated on the plan sheet.

Schedule of Items

Attached, dated February 27, 2020, are the revised Schedule of Items Page 7.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 54.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

ALL 0010 CATEGORY ITEMS ARE PROJECT 7735-01-61 UNLESS OTHERWISE NOTED.

PAVEMENT MARKING SUMMARY

STATION TO	STATION	LOCATION	MARKING LINE		MARKING LINE		TEMPORARY MARKING LINE	
			EPOXY 4-INCH	PAINT 4-INCH	EPOXY 4-INCH	PAINT 4-INCH	EPOXY 4-INCH	PAINT 4-INCH
			LF	LF	LF	LF	LF	LF
156+39	171+07	EDGE LINE RT	1,468	-	-	-	649.0105	-
172+06	250+36	EDGE LINE RT	7,830	-	-	-	649.0105	1,576
251+61	277+47	EDGE LINE RT	2,586	-	-	-	649.0105	32
278+19	358+05	EDGE LINE RT	7,986	-	-	-	649.0105	2,424
358+99	401+41	EDGE LINE RT	4,242	-	-	-	649.0105	51,016
406+38	412+88	EDGE LINE RT	650	-	-	-	649.0105	2,110
413+50	458+69	EDGE LINE RT	4,519	-	-	-	649.0105	128
459+47	481+64	EDGE LINE RT	2,217	-	-	-	649.0105	646
482+57	877+54	EDGE LINE RT	39,497	-	-	-	649.0105	1,070
878+24	924+13	EDGE LINE RT	4,589	-	-	-	649.0105	1,020
925+00	932+30	EDGE LINE RT	730	-	-	-	649.0105	1,724
156+39	159+88	EDGE LINE LT	349	-	-	-	649.0105	61,746
160+72	162+71	EDGE LINE LT	199	-	-	-	649.0105	200,720
163+44	277+07	EDGE LINE LT	11,363	-	-	-	649.0105	262,466
277+79	330+63	EDGE LINE LT	5,284	-	-	-	649.0105	
331+59	401+41	EDGE LINE LT	6,982	-	-	-	649.0105	
406+38	412+46	EDGE LINE LT	608	-	-	-	649.0105	
413+50	517+91	EDGE LINE LT	10,441	-	-	-	649.0105	
518+83	853+38	EDGE LINE LT	33,655	-	-	-	649.0105	
856+32	877+54	EDGE LINE LT	2,122	-	-	-	649.0105	
878+24	908+71	EDGE LINE LT	3,047	-	-	-	649.0105	
910+02	924+13	EDGE LINE LT	1,411	-	-	-	649.0105	
925+00	932+30	EDGE LINE LT	730	-	-	-	649.0105	
156+39	161+55	CL	645	645	1,114	-	649.0105	
161+55	172+34	CL	1,349	1,349	2,330	-	649.0105	
172+34	284+14	CL	22,360	22,360	44,720	-	649.0105	
284+14	298+95	CL	1,851	1,851	3,198	-	649.0105	
298+95	306+80	CL	981	981	1,696	-	649.0105	
306+80	308+99	CL	55	55	36	-	649.0105	
308+99	318+31	CL	1,165	1,165	2,014	-	649.0105	
318+31	325+40	CL	177	177	114	-	649.0105	
325+40	336+41	CL	1,376	1,376	2,378	-	649.0105	
336+41	339+93	CL	704	704	1,408	-	649.0105	
339+93	351+90	CL	1,496	1,496	2,586	-	649.0105	
351+90	362+45	CL	264	264	168	-	649.0105	
362+45	373+11	CL	1,333	1,333	2,302	-	649.0105	
373+11	401+41	CL	5,660	5,660	11,320	-	649.0105	
406+38	719+72	CL	62,668	62,668	125,336	-	649.0105	
SUBTOTAL 1 =			254,589	102,084	200,720	-	649.0105	

PAVEMENT MARKING SUMMARY

STATION TO	STATION	LOCATION	MARKING LINE		MARKING LINE		TEMPORARY MARKING LINE	
			EPOXY 4-INCH	PAINT 4-INCH	EPOXY 4-INCH	PAINT 4-INCH	EPOXY 4-INCH	PAINT 4-INCH
			LF	LF	LF	LF	LF	LF
719+72	727+02	CL	913	913	1,576	-	649.0105	
727+02	729+01	CL	50	50	32	-	649.0105	
729+01	740+23	CL	1,403	1,403	2,424	-	649.0105	
740+23	867+77	CL	25,508	25,508	51,016	-	649.0105	
867+77	877+54	CL	1,221	1,221	2,110	-	649.0105	
878+24	878+83	CL	74	74	128	-	649.0105	
878+83	919+18	CL	1,009	1,009	646	-	649.0105	
919+18	924+13	CL	619	619	1,070	-	649.0105	
925+00	929+72	CL	590	590	1,020	-	649.0105	
929+72	934+03	CL	862	862	1,724	-	649.0105	
SUBTOTAL 2 =			32,249	32,249	61,746	-	649.0105	
SUBTOTAL 1 =			254,589	102,084	200,720	-	649.0105	
PROJECT TOTALS =			286,838	134,333	262,466	-	649.0105	

LOCATING NO-PASSING ZONES

STATION TO	STATION	LOCATION	MI	REMARKS
156+49	932+35	STH 121	14.69	
PROJECT TOTALS =			14.69	

CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) 01... 7735-01-61

LOCATION	LS	REMARKS
PROJECT 7735-01-61	1	
PROJECT TOTALS =		1

CONSTRUCTION STAKING RESURFACING REFERENCE

STATION TO	STATION	LOCATION	LF	REMARKS
156+49	932+35	LT/RT	77,586	MAINLINE
PROJECT TOTALS =			77,586	

Addendum No. 01
ID 7735-01-61
Revised Sheet 54
February 27, 2020

* TEMPORARY MARKING LINE PAINT ASSUMED TO BE PLACED TWICE ON BINDER LIFT TO ACCOMMODATE CONSTRUCTION STAGING.



Proposal Schedule of Items

Proposal ID: 20200310033 Project(s): 7735-01-61, 7735-01-62

Federal ID(s): WISC 2020091, WISC 2020090

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0192	645.0120 Geotextile Type HR	705.000 SY	_____.	_____.
0194	646.1020 Marking Line Epoxy 4-Inch	286,838.000 LF	_____.	_____.
0196	646.4520 Marking Line Same Day Epoxy 4-Inch	134,333.000 LF	_____.	_____.
0198	648.0100 Locating No-Passing Zones	14.690 MI	_____.	_____.
0200	649.0105 Temporary Marking Line Paint 4-Inch	262,466.000 LF	_____.	_____.
0202	650.6000 Construction Staking Pipe Culverts	47.000 EACH	_____.	_____.
0204	650.8000 Construction Staking Resurfacing Reference	77,586.000 LF	_____.	_____.
0206	650.9910 Construction Staking Supplemental Control (project) 01. 7735-01-61	LS	LUMP SUM	_____.
0208	690.0150 Sawing Asphalt	2,338.000 LF	_____.	_____.
0210	690.0250 Sawing Concrete	33.000 LF	_____.	_____.
0212	740.0440 Incentive IRI Ride	58,280.000 DOL	1.00000	58,280.00
0214	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	660.000 HRS	5.00000	3,300.00
0216	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	660.000 HRS	5.00000	3,300.00
0218	SPV.0060 Special 01. Cleaning Ditch	37.000 EACH	_____.	_____.
0220	SPV.0060 Special 02. Cleaning Box Culverts	1.000 EACH	_____.	_____.
0222	SPV.0105 Special 01. Material Transfer Vehicle	LS	LUMP SUM	_____.

