



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

April 1, 2020

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #05: 5630-06-61, WISC 2020 128
Sauk City – IH39
CTH DL to Acro Drive
STH 78
Columbia County

Letting of April 14, 2020

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

Added Special Provisions	
Article No.	Description
22	Asphaltic Surface Wedging, Item SPV.0195.01.

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
SPV.0195.01	Asphaltic Surface Wedging	Ton	0	498	498

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
28	Miscellaneous Quantities (added Asphaltic Surface Wedging)
29	Miscellaneous Quantities (added Asphaltic Surface Wedging)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

5630-06-61

April 1, 2020

Special Provisions

3. Prosecution and Progress

Replace entire article language with the following;

Begin work within ten calendar days after the engineer issues a written notice to do so. Notice to proceed will be provided no sooner than August 10, 2020.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

Northern Long-eared Bat (*Myotis septentrionalis*)

Northern Long-eared Bats (NLEB) have the potential to inhabit the project limits because they roost in trees. Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the Federal Endangered Species Act. If an individual bat or active roost is encountered during construction operations, stop work and notify the engineer and the WisDOT Regional Environmental Coordinator (REC).

If additional construction activities beyond what was originally specified are required to complete the work, approval from the engineer, following coordination with WisDOT REC, is required prior to initiating these activities.

Paving Operations

Mill and pave lower layer west of Station 123+50 within 48 hours of the milling operation. Pave the upper layer within 48 hours of paving the lower layer. Mill and pave east of Station 123+50 within 48 hours of the milling operation. No more than 3 miles of pavement are to be milled and left unpaved at any time. The Department will allow the super-elevation wedging and lower lift of widening to be an independent operation. Cold weather paving is not anticipated.

22. Asphaltic Surface Wedging, Item SPV.0195.01.

A Description

Follow Standard Specifications 460.1.

B Materials

Modify Standard Specifications 460.2 to waive density testing for Asphaltic Surface Wedging, Item SPV.195.01.

C Construction

Follow Standard Specifications 460.3.

D Measurement

Follow Standard Specifications 460.4.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0195.01	Asphaltic Surface Wedging	Ton

Schedule of Items

Attached, dated April 1, 2020, are the revised Schedule of Items Page 4.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 28, 29

END OF ADDENDUM

Addendum No. 02
ID 5630-06-61
Revised Sheet 28
April 1, 2020

REMOVALS

LOCATION	WIDTH		204.0105 REMOVING PAVEMENT BUTT JOINTS (SY)	204.0115 REMOVING ASPHALTIC SURFACE BUTT JOINTS (SY)	204.0120 REMOVING ASPHALTIC SURFACE MILLING (SY)	SPV.0180.01 REMOVING DISTRESSED PAVEMENT MILLING (SY)	NOTES
	FIRST PASS	SECOND PASS					
CURVE WIDENING							
6+66 to 9+99	2				79		LENGTH FROM PC TO PT PLUS TAPERS
13+27 to 24+73	2				260		
29+67 to 32+58	2				70		
53+31 to 57+10	2				90		
61+44 to 64+96	2				84		
167+13 to 169+58	2				60		
200+38 to 208+01	2				175		
225+27 to 227+87	2				63		
253+52 to 255+59	2				51		
261+20 to 263+72	2				61		
273+52 to 276+00	2				61		
312+50 to 314+56	2				51		
323+24 to 323+93	2				21		
344+04 to 345+60	2				40		
348+22 to 351+65	2				82		
369+37 to 371+90	2				62		
TOTALS			24	25	122358	6021	

ASPHALTIC ITEMS

LOCATION	WIDTH		211.0400 PREPARE FOUNDATION FOR ASPHALTIC SHOULDER (STA)	455.0605 TACK COAT	460.0105.S HMA PERCENT WITHIN LIMITS (PWL) TEST STRIP VOLUMETRICS (EACH)	460.0110.S HMA PERCENT WITHIN LIMITS (PWL) TEST STRIP DENSITY (EACH)	460.5224 HMA PAVEMENT 4 LT 58-28 S (TON)	465.0105 ASPHALTIC SURFACE (TON)	465.0475 ASPHALTIC CENTERLINE RUMBLE STRIPS 2-LANE RURAL (LF)	SPV.0180.02 ASPHALTIC BINDER ENHANCED FRICTION SURFACE TREATMENT (SY)	SPV.0195.01 ASPHALTIC SURFACE WEDGING (TON)
	FIRST PASS	SECOND PASS									
1+75 to 1+83	13.67	13.5	-	2	-	-	4.9	-	8	-	-
1+83 to 123+50	13.67	3.5	-	2571	-	-	7198.5	205.8	12167	-	343
123+50 to 405+92	13.42	13.25	-	5858	-	-	8200.6	468.7	28242	-	155
405+92 to 406+00	13.42	13.25	0	-	-	-	-	-	8	-	-
SIDERoads											
CTHDL				16							
DAHLKE DR		3.5	227								
BLAUDR		3.5	51	4			10.0				
INDIAN FARM RD		3.5	55	4			10.8				
DURNWA RDS GLEN RD		3.5	0	-			-				
PETRA RD		1.75	0	-			-				
OWEN PARK RD		1.75	0	-			-				
MESSER RD		1.75	0	-			-				
PETRA RD (NORTH)		1.75	0	-			-				
WALKER RD		1.75	32	3			3.2				
SHANKS RD		1.75	0	-			-				
BEICH RD		1.75	0	-			-				
OLD CNTY. URD		1.75	36	3			3.6				

CONTINUED ON NEXT PAGE

ALL ITEMS ON THIS PAGE ARE CATEGORY 0010

PROJECT NO: 5630-06-61

HWY: STH 78

COUNTY: COLUMBIA

MISCELLANEOUS QUANTITIES

SHEET 28

E

FILE NAME: _____

PLOT DATE: _____

PLOT BY: _____

ORG DATE: _____

ORIGINATOR: DIST. _____

PLOT SCALE: 1:1

Addendum No. 02
 ID 5630-06-61
 Revised Sheet 29
 April 1, 2020

LOCATION	WIDTH	DEPTH	AREA	PREPARE	FOUNDATION	SHOULDER	211.0400	455.0605	460.0105.S	460.0105.S	460.0110.S	460.0105.S	465.0224	465.0105	465.0475	SPV.0180.02	SPV.0195.01		
	FIRST	SECOND	(SQ)	FOR ASPHALTIC	FOR ASPHALTIC	(STA)	TACK	HMA PERCENT	WITHIN LIMITS (PWL)	HMA PERCENT	WITHIN LIMITS (PWL)	HMA PERCENT	TEST STRIP	TEST STRIP	DENSITY	TEST STRIP	TEST STRIP		
	PASS	PASS		SHOULDER	SHOULDER		COAT	VOLUMETRICS					PAVEMENT	ASPHALTIC	ASPHALTIC	ASPHALTIC	ASPHALTIC		
							(GAL)	(EACH)				(EACH)	4 LT 58-28 S	SURFACE	SURFACE	CENTERLINE	ENHANCED FRICTION	SURFACE	
																2-LANE RURAL	TREATMENT	WEDGING	
																(LF)	(SY)	(TON)	(TON)
DRIVEWAYS																			
73+75 RT	4	3.5	18	-	-	-	2	-	-	-	-	-	3.6	-	-	-	-	-	-
74+60 LT	4	3.5	25	-	-	-	2	-	-	-	-	-	4.9	-	-	-	-	-	-
162+40 LT	4	1.75	22	-	-	-	2	-	-	-	-	-	2.2	-	-	-	-	-	-
109+20 LT	4	1.75	11	-	-	-	1	-	-	-	-	-	1.1	-	-	-	-	-	-
128+25 LT	4	1.75	10	-	-	-	1	-	-	-	-	-	1.0	-	-	-	-	-	-
162+40 LT	4	1.75	24	-	-	-	2	-	-	-	-	-	2.4	-	-	-	-	-	-
206+15 RT	4	1.75	15	-	-	-	2	-	-	-	-	-	1.5	-	-	-	-	-	-
252+85 LT	4	1.75	12	-	-	-	1	-	-	-	-	-	1.2	-	-	-	-	-	-
253+35 RT	4	1.75	12	-	-	-	1	-	-	-	-	-	1.2	-	-	-	-	-	-
272+50 LT	4	1.75	21	-	-	-	2	-	-	-	-	-	2.1	-	-	-	-	-	-
275+50 LT	4	1.75	22	-	-	-	2	-	-	-	-	-	2.2	-	-	-	-	-	-
288+30 RT	4	1.75	11	-	-	-	1	-	-	-	-	-	1.1	-	-	-	-	-	-
315+25 RT	4	1.75	20	-	-	-	2	-	-	-	-	-	2.0	-	-	-	-	-	-
317+25 RT	4	1.75	18	-	-	-	2	-	-	-	-	-	1.8	-	-	-	-	-	-
CURVE WIDENING																			
5+27 to 11+40	2	3.5	79	12.26			6	-	-	-	-	-	15.5	-	-	-	-	-	-
13+27 to 24+73	2	3.5	260	22.92			19	-	-	-	-	-	51.0	-	-	-	-	-	-
29+67 to 32+58	2	3.5	70	5.82			5	-	-	-	-	-	13.8	-	-	-	-	-	-
53+31 to 57+10	2	3.5	90	7.58			7	-	-	-	-	-	17.7	-	-	-	-	-	-
61+44 to 64+96	2	3.5	84	7.04			6	-	-	-	-	-	16.5	-	-	-	-	-	-
167+13 to 169+58	2	3.5	60	4.90			5	-	-	-	-	-	11.8	-	-	-	-	-	-
200+38 to 208+01	2	3.5	175	15.26			13	-	-	-	-	-	34.3	-	-	-	-	-	-
225+27 to 227+87	2	3.5	63	5.20			4	-	-	-	-	-	12.4	-	-	-	-	-	-
253+52 to 255+59	2	3.5	51	4.14			4	-	-	-	-	-	10.0	-	-	-	-	-	-
261+20 to 263+72	2	3.5	61	5.04			5	-	-	-	-	-	12.0	-	-	-	-	-	-
273+52 to 276+00	2	3.5	61	4.96			5	-	-	-	-	-	12.0	-	-	-	-	-	-
312+50 to 314+56	2	3.5	51	4.12			4	-	-	-	-	-	10.0	-	-	-	-	-	-
323+24 to 323+93	2	3.5	21	1.38			2	-	-	-	-	-	4.2	-	-	-	-	-	-
344+04 to 346+60	2	3.5	40	3.12			3	-	-	-	-	-	7.9	-	-	-	-	-	-
348+22 to 351+65	2	3.5	82	6.86			6	-	-	-	-	-	16.1	-	-	-	-	-	-
369+37 to 371+90	2	3.5	62	5.06			5	-	-	-	-	-	12.2	-	-	-	-	-	-
GUARDRAIL REPLACEMENT																			
44+45 to 48+07	2	3.5	107.6	-			8	-	-	-	-	-	21.1	-	-	-	-	-	-
75+41 to 77+53	2	3.5	19.8	-			2	-	-	-	-	-	3.9	-	-	-	-	-	-
170+31 to 172+43	2	3.5	15.3	-			2	-	-	-	-	-	3.1	-	-	-	-	-	-
UNDISTRIBUTED																			
								1		2									
TOTALS							116	8596	1	2	2	15790	675	40425	1771	498			

ALL ITEMS ON THIS PAGE ARE CATEGORY 0010

PROJECT NO: 5630-06-61 COUNTY: COLUMBIA HWY: STH 78 SHEET 29 E

FILE NAME: _____ PLOT DATE: _____ PLOT BY: _____ PLOT NAME: _____ ORG DATE: _____ ORIGINATOR: DIST. _____ PLOT SCALE: 1:1



Proposal Schedule of Items

Proposal ID: 20200414005 Project(s): 5630-06-61

Federal ID(s): WISC 2020128

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0098	648.0100 Locating No-Passing Zones	7.660 MI	_____.	_____.
0100	649.0770 Temporary Marking Raised Pavement Marker Type II	810.000 EACH	_____.	_____.
0102	650.8000 Construction Staking Resurfacing Reference	40,425.000 LF	_____.	_____.
0104	650.9910 Construction Staking Supplemental Control (project) 01. 5630-06-61	LS	LUMP SUM	_____.
0106	650.9920 Construction Staking Slope Stakes	1,073.000 LF	_____.	_____.
0108	690.0150 Sawing Asphalt	1,691.000 LF	_____.	_____.
0110	740.0440 Incentive IRI Ride	30,600.000 DOL	1.00000	30,600.00
0112	SPV.0060 Special 01. Verify Landmark Reference Monuments	3.000 EACH	_____.	_____.
0114	SPV.0060 Special 02. Landmark Reference Monuments Special	2.000 EACH	_____.	_____.
0116	SPV.0180 Special 01. Removing Distressed Pavement Milling	6,021.000 SY	_____.	_____.
0118	SPV.0180 Special 02. Asphaltic Binder Enhanced Friction Surface Treatment	1,771.000 SY	_____.	_____.
0120	SPV.0195 Special 01. Asphaltic Surface Wedging	498.000 TON	_____.	_____.

Section: 0001

Total: _____.

Total Bid: _____.

