



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

April 21, 2020

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #07: 6075-00-74, WISC 2020242
IH 39 - Arlington
Bullen Road to US 51
STH 60
Columbia County

Letting of May 12, 2020

This is Addendum No. 02, which provides for the following:

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
62	Miscellaneous Quantities (Updated Earthwork Summary Table)
126	Earthwork (Updated Earthwork Detail Tables)
127	Earthwork (Updated Earthwork Detail Tables)
128	Earthwork (Updated Earthwork Detail Tables)
129	Earthwork (Updated Earthwork Detail Tables)
130	Earthwork (Updated Earthwork Detail Tables)
131	Earthwork (Updated Earthwork Detail Tables)
132	Earthwork (Updated Earthwork Detail Tables)
133	Earthwork (Updated Earthwork Detail Tables)

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 62, 126-133.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 02
ID 6075-00-74
Revised Sheet 62
April 21, 2020

DIVISION	FROM/TO STATION	LOCATION	205.0100 COMMON EXCAVATION		SALVAGED/UNUSABLE PAVEMENT MATERIAL (3)	AVAILABLE MATERIAL (4)	MASS ORDINATE +/- (5)	WASTE	COMMENT:
			(1)	CUT (2)					
DIVISION 1									
STAGE 1									
STH 60	425+36.17/438+31		5,611		1,118	4,493	4,493	4,493	
Bullen Rd	10+15/10+62.8		161		30	130	130	130	
CTH I	09+19.22/09+85		257		42	214	214	214	
Park St	09+52.12/10+51.71		274		85	189	189	189	
Commercial St N	10+15/10+87.5		349		76	274	274	274	
Commercial St S	09+30/09+85		296		128	168	168	168	
STAGE 1 SUBTOTAL			6,948		1,479	5,468	5,468	5,468	
STAGE 2									
STH 60	438+31/453+76.28		6,306		1,186	5,120	5,120	5,120	
Buena Vista Dr	10+15/10+50		116		35	81	81	81	
Delmonte Rd	09+08.17/10+79		567		137	430	430	430	
STAGE 2 SUBTOTAL			6,989		1,358	5,631	5,631	5,631	
DIVISION 1 SUBTOTAL			13,936		2,837	11,099	11,099	11,099	SEE NOTE 6
GRAND TOTAL			13,936		2,837	11,099	11,099	11,099	
TOTAL COMMON EXC			13,936		2,837	11,099	11,099	11,099	

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
- (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
- (3) SALVAGED/UNUSABLE PAVEMENT MATERIAL
- (4) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
- (5) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF
- (6) Use 11099 CY of material from DIVISION 1. Borrow Excavation item number 208.0100

STH 60 STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	MASS ORDINATE
425+36.17	42536.17	0.00	0.00	0.00	0	0	0	0
425+40	42540.00	3.83	116.86	15.00	8	1	8	7
425+45	42545.00	5.00	119.51	15.00	22	3	30	26
425+50	42550.00	5.00	122.60	15.00	22	3	53	46
425+55	42555.00	5.00	125.68	15.00	23	3	76	66
425+60	42560.00	5.00	130.67	15.00	24	3	99	87
425+65	42565.00	5.00	140.75	15.00	25	3	124	109
425+70	42570.00	5.00	154.76	15.00	27	3	152	134
425+75	42575.00	5.00	165.99	15.00	30	3	182	161
425+80	42580.00	5.00	162.35	15.00	30	3	212	189
425+85	42585.00	5.00	147.70	15.00	29	3	241	215
425+90	42590.00	5.00	131.48	15.00	26	3	266	238
425+95	42595.00	5.00	114.80	15.00	23	3	289	258
426+00	42600.00	5.00	97.75	15.00	20	3	309	275
426+05	42605.00	5.00	80.33	15.00	16	3	325	288
426+10	42610.00	5.00	62.82	0.00	13	1	339	300
426+15	42615.00	5.00	82.50	20.50	13	2	352	312
426+20	42620.00	5.00	104.00	20.50	17	4	369	325
426+25	42625.00	5.00	124.26	20.50	21	4	391	342
426+30	42630.00	5.00	143.55	20.50	25	4	415	363
426+35	42635.00	5.00	132.26	20.50	26	4	441	385
426+40	42640.00	5.00	113.42	20.50	23	4	464	404
426+45	42645.00	5.00	100.69	20.50	20	4	483	420
426+50	42650.00	5.00	94.94	20.50	18	4	502	435
426+55	42655.00	5.00	93.28	20.50	17	4	519	448
426+55.71	42655.71	0.71	93.04	20.50	2	1	521	450
427+00	42700.00	44.29	94.55	20.50	154	34	675	570
427+50	42750.00	50.00	90.00	20.50	171	38	846	703
428+00	42800.00	50.00	93.18	20.50	170	38	1,016	835
428+50	42850.00	50.00	88.31	20.50	168	38	1,184	965
429+00	42900.00	50.00	85.07	20.50	161	38	1,344	1,088
429+50	42950.00	50.00	80.37	20.50	153	38	1,498	1,203
430+00	43000.00	50.00	85.41	20.50	154	38	1,651	1,318
430+50	43050.00	50.00	100.71	20.50	172	38	1,823	1,453
431+00	43100.00	50.00	114.53	20.50	199	38	2,023	1,614
431+30.26	43130.26	30.26	105.20	20.50	123	23	2,146	1,714
431+35	43135.00	4.74	106.61	20.50	19	4	2,164	1,729
431+40	43140.00	5.00	115.07	20.50	21	4	2,185	1,746
431+45	43145.00	5.00	135.64	20.50	23	4	2,208	1,765
431+50	43150.00	5.00	133.37	20.50	25	4	2,233	1,786
431+55	43155.00	5.00	118.56	20.50	23	4	2,256	1,806
431+60	43160.00	5.00	101.76	20.50	20	4	2,277	1,823
431+65	43165.00	5.00	82.95	20.50	17	4	2,294	1,836
431+70	43170.00	5.00	69.78	0.00	14	2	2,308	1,848

(continued on next page)

Addendum No. 02
ID 6075-00-74
Revised Sheet 126
April 21, 2020

STH 60 STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		MASS ORDNATE
			CUT	SALVAGED/UNUSABLE	CUT	SALVAGED/UNUSABLE	CUT	SALVAGED/UNUSABLE	
431+75	43175.00	5.00	91.85	28.50	15	3	2,323	1,860	
431+80	43180.00	5.00	113.42	28.50	19	5	2,342	1,874	
431+85	43185.00	5.00	132.15	28.50	23	5	2,365	1,892	
431+90	43190.00	5.00	144.51	28.50	26	5	2,390	1,912	
431+95	43195.00	5.00	124.05	28.50	25	5	2,415	1,932	
432+00	43200.00	5.00	117.17	28.50	22	5	2,438	1,949	
432+03.19	43203.19	3.19	116.89	28.50	14	3	2,451	1,959	
432+50	43250.00	46.81	132.80	28.50	216	49	2,668	2,126	
433+00	43300.00	50.00	135.83	28.50	249	53	2,917	2,322	
433+50	43350.00	50.00	140.63	28.50	256	53	3,173	2,525	
434+00	43400.00	50.00	144.02	28.50	264	53	3,436	2,736	
434+50	43450.00	50.00	142.31	28.50	265	53	3,701	2,948	
435+00	43500.00	50.00	141.16	28.50	262	53	3,964	3,158	
435+50	43550.00	50.00	139.86	28.50	260	53	4,224	3,365	
436+00	43600.00	50.00	134.09	28.50	254	53	4,478	3,566	
436+50	43650.00	50.00	131.68	28.50	246	53	4,724	3,760	
436+78.6	43678.60	28.60	131.96	28.50	140	30	4,863	3,869	
436+80	43680.00	1.40	132.74	28.50	7	1	4,870	3,875	
436+85	43685.00	5.00	136.53	28.50	25	5	4,895	3,894	
436+90	43690.00	5.00	140.46	28.50	26	5	4,921	3,915	
436+95	43695.00	5.00	145.87	28.50	27	5	4,947	3,936	
437+00	43700.00	5.00	156.56	28.50	28	5	4,975	3,958	
437+05	43705.00	5.00	183.47	28.50	31	5	5,007	3,985	
437+10	43710.00	5.00	193.96	28.50	35	5	5,042	4,014	
437+15	43715.00	5.00	195.19	28.50	36	5	5,078	4,045	
437+20	43720.00	5.00	182.22	28.50	35	5	5,113	4,075	
437+25	43725.00	5.00	153.32	28.50	31	5	5,144	4,101	
437+30	43730.00	5.00	123.61	0.00	26	3	5,169	4,124	
437+35	43735.00	5.00	96.82	28.50	20	3	5,190	4,141	
437+40	43740.00	5.00	91.05	20.50	17	5	5,207	4,154	
437+45	43745.00	5.00	84.98	0.00	16	2	5,223	4,169	
437+50	43750.00	5.00	104.31	20.50	18	2	5,241	4,184	
437+55	43755.00	5.00	129.36	20.50	22	4	5,263	4,202	
437+60	43760.00	5.00	154.03	20.50	26	4	5,289	4,225	
437+65	43765.00	5.00	176.80	20.50	31	4	5,320	4,251	
437+70	43770.00	5.00	161.50	20.50	31	4	5,351	4,279	
437+75	43775.00	5.00	137.47	20.50	28	4	5,379	4,303	
437+80	43780.00	5.00	121.30	20.50	24	4	5,402	4,323	
437+85	43785.00	5.00	111.89	20.50	22	4	5,424	4,341	
437+90	43790.00	5.00	107.14	20.50	20	4	5,444	4,357	
437+95	43795.00	5.00	110.13	20.50	20	4	5,464	4,374	
437+96.21	43796.21	1.21	110.22	20.50	5	1	5,469	4,378	
438+00	43800.00	3.79	115.90	20.50	16	3	5,485	4,391	
438+31	43831.00	31.00	102.85	20.50	126	24	5,611	4,493	

Addendum No. 02
 ID 6075-00-74
 Revised Sheet 127
 April 21, 2020

Addendum No. 02
ID 6075-00-74
Revised Sheet 128
April 21, 2020

BULLEN RD STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	MASS ORDINATE
10+15	1015.00	0.00	17.24	0.00	0	0	0	0
10+20	1020.00	5.00	66.74	14.50	8	1	8	6
10+25	1025.00	5.00	112.42	14.50	17	3	24	20
10+30	1030.00	5.00	112.28	14.50	21	3	45	38
10+35	1035.00	5.00	93.34	14.50	19	3	64	55
10+40	1040.00	5.00	84.55	14.50	16	3	81	69
10+41.86	1041.86	1.86	82.40	14.50	6	1	86	73
10+50	1050.00	8.14	90.76	14.50	26	4	113	95
10+62.8	1062.80	12.80	87.03	14.50	42	7	155	130
Curb Ramps					6	6	161	130

CTH I STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	MASS ORDINATE
09+19.22	919.22	0.00	130.48	16.00	0	0	0	0
09+20	920.00	0.78	130.47	16.00	4	0	4	3
09+25	925.00	5.00	130.88	16.00	24	3	28	25
09+30	930.00	5.00	133.21	16.00	30	3	52	46
09+35	935.00	5.00	108.21	16.00	22	3	75	65
09+40	940.00	5.00	113.19	16.00	20	3	95	83
09+45	945.00	5.00	119.24	16.00	22	3	117	102
09+50	950.00	5.00	125.93	16.00	23	3	139	121
09+55	955.00	5.00	132.80	16.00	24	3	163	142
09+60	960.00	5.00	121.34	16.00	24	3	187	163
09+65	965.00	5.00	100.90	16.00	21	3	208	180
09+70	970.00	5.00	80.62	16.00	17	3	224	194
09+75	975.00	5.00	60.41	16.00	13	3	237	204
09+80	980.00	5.00	40.18	16.00	9	3	247	211
09+85	985.00	5.00	18.97	0.00	5	1	252	215
Curb Ramps					5	5	257	214

Addendum No. 02
 ID 6075-00-74
 Revised Sheet 129
 April 21, 2020

PARK ST STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	MASS ORDINATE
09+52.12	952.12	0.00	99.63	18.00	0	0	0	0
09+60.7	960.70	8.58	100.35	18.00	32	6	32	26
09+65	965.00	4.30	92.16	18.00	15	3	47	39
09+70	970.00	5.00	103.44	18.00	18	3	65	53
09+75	975.00	5.00	93.34	18.00	18	3	83	68
09+80	980.00	5.00	62.42	18.00	14	3	98	79
09+85	985.00	5.00	27.76	18.00	8	3	106	84
10+15	1015.00	30.00	17.63	0.00	25	10	131	99
10+20	1020.00	5.00	55.98	18.00	7	2	138	105
10+25	1025.00	5.00	87.55	18.00	13	3	152	115
10+30	1030.00	5.00	95.24	18.00	17	3	168	128
10+35	1035.00	5.00	92.57	18.00	17	3	186	142
10+37.4	1037.40	2.40	92.98	18.00	8	2	194	149
10+50	1050.00	12.60	99.77	18.00	45	8	239	185
10+51.71	1051.71	1.71	45.68	18.00	5	1	244	189
Curb Ramps					30	30	274	189

COMMERCIAL ST N STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	MASS ORDINATE
10+15	1015.00	0.00	16.90	0.00	0	0	0	0
10+20	1020.00	5.00	47.53	19.50	6	2	6	4
10+25	1025.00	5.00	78.82	19.50	12	4	18	12
10+30	1030.00	5.00	108.85	19.50	17	4	35	26
10+35	1035.00	5.00	135.48	19.50	23	4	58	45
10+40	1040.00	5.00	150.80	19.50	27	4	84	68
10+45	1045.00	5.00	162.41	19.50	29	4	113	93
10+50	1050.00	5.00	152.67	19.50	29	4	142	119
10+55	1055.00	5.00	139.85	19.50	27	4	169	142
10+60	1060.00	5.00	130.83	19.50	25	4	194	164
10+65	1065.00	5.00	124.80	19.50	24	4	218	184
10+70	1070.00	5.00	121.39	19.50	23	4	241	203
10+71.64	1071.64	1.64	120.44	19.50	7	1	248	209
10+87.5	1087.50	15.86	112.63	19.50	68	11	317	266
Curb Ramps					33	25	349	274

COMMERCIAL ST S STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	MASS ORDINATE
09+30	930.00	0.00	96.80	18.50	0	0	0	0
09+43.17	943.17	13.17	97.82	18.50	47	9	47	38
09+45	945.00	1.83	97.76	18.50	7	1	54	44
09+50	950.00	5.00	100.75	18.50	18	3	72	59
09+55	955.00	5.00	102.42	18.50	19	3	91	74
09+60	960.00	5.00	119.52	18.50	21	3	112	91
09+65	965.00	5.00	124.64	18.50	23	3	134	110
09+70	970.00	5.00	117.07	18.50	22	3	157	129
09+75	975.00	5.00	102.48	18.50	20	3	177	146
09+80	980.00	5.00	61.05	18.50	15	3	192	158
09+85	985.00	5.00	18.23	0.00	7	2	200	164
Curb Ramps					96	92	296	188

Addendum No. 02
ID 6075-00-74
Revised Sheet 130
April 21, 2020

STH 60 STAGE 2

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		MASS ORDINATE
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	NOTE 1	
438+31	43831.00	0.00	115.90	20.50	0	0	0	0	0
438+50	43850.00	19.00	102.85	20.50	77	14	77	77	63
439+00	43900.00	50.00	102.83	20.50	190	38	267	267	215
439+50	43950.00	50.00	103.39	20.50	191	38	458	458	368
440+00	44000.00	50.00	108.13	20.50	196	38	654	654	526
440+50	44050.00	50.00	107.59	20.50	200	38	854	854	688
441+00	44100.00	50.00	111.07	20.50	202	38	1,056	1,056	852
441+50	44150.00	50.00	111.37	20.50	206	38	1,262	1,262	1,020
442+00	44200.00	50.00	109.12	20.50	204	38	1,467	1,467	1,186
442+50	44250.00	50.00	106.89	20.50	200	38	1,667	1,667	1,348
443+00	44300.00	50.00	107.52	20.50	199	38	1,865	1,865	1,509
443+50	44350.00	50.00	106.83	20.50	198	38	2,064	2,064	1,669
444+00	44400.00	50.00	103.48	20.50	195	38	2,258	2,258	1,826
444+50	44450.00	50.00	102.29	20.50	191	38	2,449	2,449	1,979
445+00	44500.00	50.00	104.27	20.50	191	38	2,640	2,640	2,132
445+20.07	44520.07	20.07	106.09	20.50	78	15	2,718	2,718	2,195
445+25	44525.00	4.93	105.79	20.50	19	4	2,738	2,738	2,211
445+30	44530.00	5.00	107.66	20.50	20	4	2,757	2,757	2,227
445+35	44535.00	5.00	118.46	20.50	21	4	2,778	2,778	2,244
445+40	44540.00	5.00	112.84	20.50	21	4	2,800	2,800	2,261
445+45	44545.00	5.00	105.43	20.50	20	4	2,820	2,820	2,278
445+50	44550.00	5.00	98.67	20.50	19	4	2,839	2,839	2,293
445+55	44555.00	5.00	90.32	20.50	17	4	2,856	2,856	2,307
445+60	44560.00	5.00	88.44	0.00	17	2	2,873	2,873	2,321
445+65	44565.00	5.00	97.47	20.50	17	2	2,890	2,890	2,337
445+70	44570.00	5.00	105.71	20.50	19	4	2,909	2,909	2,352
445+75	44575.00	5.00	113.07	20.50	20	4	2,929	2,929	2,368
445+80	44580.00	5.00	119.05	20.50	21	4	2,951	2,951	2,386
445+85	44585.00	5.00	110.73	20.50	21	4	2,972	2,972	2,403
445+90	44590.00	5.00	111.58	20.50	21	4	2,993	2,993	2,420
445+95	44595.00	5.00	111.34	20.50	21	4	3,013	3,013	2,437
445+95.06	44595.06	0.06	111.33	20.50	0	0	3,013	3,013	2,437
446+00	44600.00	4.94	110.99	20.50	0	0	3,034	3,034	2,454
446+50	44650.00	50.00	111.45	20.50	206	38	3,240	3,240	2,622
447+00	44700.00	50.00	110.38	20.50	205	38	3,445	3,445	2,789
447+50	44750.00	50.00	112.72	20.50	207	38	3,652	3,652	2,958
448+00	44800.00	50.00	109.16	20.50	205	38	3,857	3,857	3,125
448+50	44850.00	50.00	107.69	20.50	201	38	4,058	4,058	3,288
449+00	44900.00	50.00	108.31	20.50	200	38	4,258	4,258	3,450

(continued on next page)

Addendum No. 02
ID 6075-00-74
Revised Sheet 131
April 21, 2020

STH 60 STAGE 2

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		MASS ORDNATE
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	
449+50	44950.00	50.00	112.65	20.50	205	38	4,463	3,617	
450+00	45000.00	50.00	113.09	20.50	209	38	4,672	3,788	
450+50	45050.00	50.00	111.71	20.50	208	38	4,880	3,958	
451+00	45100.00	50.00	117.52	21.50	212	39	5,092	4,131	
451+50	45150.00	50.00	117.67	22.50	218	41	5,310	4,308	
452+00	45200.00	50.00	120.31	22.50	220	42	5,530	4,487	
452+18.33	45218.33	18.33	119.81	22.50	81	15	5,612	4,553	
452+20	45220.00	1.67	119.89	22.50	7	1	5,619	4,559	
452+25	45225.00	5.00	120.78	22.50	22	4	5,641	4,577	
452+30	45230.00	5.00	122.76	22.50	23	4	5,664	4,596	
452+35	45235.00	5.00	125.65	22.50	23	4	5,687	4,615	
452+40	45240.00	5.00	129.66	22.50	24	4	5,710	4,634	
452+45	45245.00	5.00	134.86	22.50	24	4	5,735	4,654	
452+50	45250.00	5.00	139.82	22.50	25	4	5,760	4,676	
452+55	45255.00	5.00	149.84	22.50	27	4	5,787	4,698	
452+60	45260.00	5.00	165.41	22.50	29	4	5,816	4,723	
452+65	45265.00	5.00	156.23	22.50	30	4	5,846	4,749	
452+70	45270.00	5.00	140.14	22.50	27	4	5,874	4,772	
452+75	45275.00	5.00	124.18	22.50	24	4	5,898	4,793	
452+80	45280.00	5.00	108.28	22.50	22	4	5,920	4,810	
452+85	45285.00	5.00	92.31	22.50	19	4	5,938	4,824	
452+90	45290.00	5.00	76.43	22.50	16	4	5,954	4,836	
452+95	45295.00	5.00	60.70	0.00	13	2	5,967	4,846	
453+00	45300.00	5.00	72.63	22.50	12	2	5,979	4,857	
453+05	45305.00	5.00	93.37	22.50	15	4	5,994	4,868	
453+10	45310.00	5.00	114.02	22.50	19	4	6,013	4,883	
453+15	45315.00	5.00	134.62	22.50	23	4	6,036	4,902	
453+20	45320.00	5.00	155.58	22.50	27	4	6,063	4,924	
453+25	45325.00	5.00	178.32	22.50	31	4	6,094	4,951	
453+30	45330.00	5.00	160.01	22.50	31	4	6,126	4,978	
453+35	45335.00	5.00	144.95	22.50	28	4	6,154	5,002	
453+40	45340.00	5.00	135.98	22.50	26	4	6,180	5,024	
453+45	45345.00	5.00	130.58	22.50	25	4	6,204	5,045	
453+50	45350.00	5.00	127.57	22.50	24	4	6,228	5,065	
453+55	45355.00	5.00	125.91	22.50	23	4	6,252	5,084	
453+56.28	45356.28	1.28	122.95	22.50	6	1	6,258	5,089	
453+76.28	45376.28	20.00	7.01	22.50	48	17	6,306	5,120	

Addendum No. 02
ID 6075-00-74
Revised Sheet 132
April 21, 2020

BUENA VISTA DR STAGE 2

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
			SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	REduced EBS	MASS ORDINATE
				NOTE 1	NOTE 2	NOTE 1	NOTE 1	NOTE 8
10+15	1015.00	0.00	0.00	0	0	0	0	0
10+20	1020.00	5.00	20.50	6	2	6	6	5
10+25	1025.00	5.00	20.50	12	4	12	18	13
10+30	1030.00	5.00	20.50	16	4	16	24	25
10+35	1035.00	5.00	20.50	17	4	17	31	38
10+39.64	1039.64	4.64	20.50	16	4	16	37	50
10+50	1050.00	10.36	20.50	39	8	39	106	81
Curb Ramps				10	10	116		81

DELMONTE RD STAGE 2

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
			SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	CUT	MASS ORDINATE	
				NOTE 1	NOTE 2	NOTE 1	NOTE 1	NOTE 8
09+08.17	908.17	0.00	113.18	0	0	0	0	0
09+19.01	919.01	10.83	116.04	46	8	46	46	38
09+20	920.00	0.99	116.20	4	1	50	50	41
09+25	925.00	5.00	117.18	22	4	72	72	59
09+30	930.00	5.00	118.49	22	4	94	94	77
09+35	935.00	5.00	120.28	22	4	116	116	95
09+40	940.00	5.00	123.53	23	4	138	138	114
09+45	945.00	5.00	129.86	23	4	162	162	134
09+50	950.00	5.00	139.13	25	4	187	187	155
09+55	955.00	5.00	152.04	27	4	214	214	178
09+60	960.00	5.00	131.39	26	4	240	240	201
09+65	965.00	5.00	107.15	22	4	262	262	219
09+70	970.00	5.00	84.18	18	4	280	280	233
09+75	975.00	5.00	61.79	14	4	293	293	243
09+80	980.00	5.00	38.74	9	4	303	303	248
09+85	985.00	5.00	15.56	5	2	308	308	251
10+15	1015.00	30.00	24.61	22	0	330	330	273
10+20	1020.00	5.00	71.00	9	2	339	339	280
10+25	1025.00	5.00	117.38	17	4	356	356	294
10+30	1030.00	5.00	145.57	24	4	381	381	315
10+35	1035.00	5.00	129.08	25	4	406	406	336
10+40	1040.00	5.00	118.47	23	4	429	429	355
10+45	1045.00	5.00	113.87	22	4	450	450	373
10+48.8	1048.80	3.80	113.93	16	3	466	466	386
10+50	1050.00	1.20	114.34	5	1	472	472	390
10+79	1079.00	29.00	0.00	34	34	533	533	430
Curb Ramps						567		430

Addendum No. 02
ID 6075-00-74
Revised Sheet 133
April 21, 2020