



Wisconsin Department of Transportation

April 28, 2020

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #41: 8213-01-70, WISC 2020 288
Thorp – Ingram
Alder Creek Bridge B-54-0133
STH 73
Rusk County

Letting of May 12, 2020

This is Addendum No. 01, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
14	Asphaltic Surface

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
465.0105	Asphaltic Surface	TON	0	280	280

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
460.2000	Incentive Density HMA Pavement	DOL	180	-180	0
460.6244	HMA Pavement 4 MT 58-34 S	TON	280	-280	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
13	Miscellaneous Quantities (Changed HMA Pavement item to Asphaltic Surface)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

8213-01-70

April 28, 2020

Special Provisions

14. Asphaltic Surface, Item 465.0105.

Replace standard spec 465.2(1) with the following:

(1) Under the Asphaltic Surface bid item, submit a mix design. Furnish asphaltic mixture meeting the requirements specified for 4 MT 58-34 S or higher under 460.2; except the engineer will not require the contractor to conform to the quality management program specified under 460.2.8.

Schedule of Items

Attached, dated April 28, 2020, are the revised Schedule of Items Pages 1 – 4.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 13.

END OF ADDENDUM

Addendum No. 01
 ID 8213-01-70
 Revised Sheet 13
 April 28, 2020

ALL ITEMS CATEGORY 010 UNLESS OTHERWISE NOTED

BASE AGGREGATE DENSE

STATION - STATION	LOCATION	305.0110 BASE AGGREGATE DENSE 3/4-INCH (TON)	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH (TON)	312.0110 SELECT CRUSHED MATERIAL (TON)	TOTALS =
7+61 - 9+88	MAINLINE	16	355	440	811
10+23 - 12+60	MAINLINE	19	615	740	1374
		35	970	1180	

WATER

STATION-STATION	LOCATION	624.0100 (MGAL)	TOTALS =
7+61 - 12+60	MAINLINE	33	33

**465.0105
 ASPHALTIC SURFACE**

STATION - STATION	LOCATION	465.0605 TACK COAT (GAL)	465.0105 ASPHALTIC SURFACE (TON)	TOTALS =
7+88 - 9+88	MAINLINE	21	95	116
10+23 - 12+25	MAINLINE	40	185	225
		61	280	

MGS GUARDRAIL

STATION - STATION	LOCATION	614.2500 MGS THRE BEAM TRANSITION (LF)	614.2610 MGS GUARDRAIL TERMINAL EAT (EACH)	TOTALS =
8+83	MAINLINE LT.	-	1	1
8+93	MAINLINE RT.	-	1	1
9+36 - 9+73	MAINLINE LT.	40	-	40
9+45 - 9+83	MAINLINE RT.	40	-	40
10+28 - 10+66	MAINLINE LT.	40	-	40
10+38 - 10+75	MAINLINE RT.	40	-	40
11+19	MAINLINE LT.	-	1	1
11+28	MAINLINE RT.	-	1	1
		160	4	

EARTHWORK SUMMARY

FROM TO STA	LOCATION	205.0100 EXCAVATION COMMON CUT (CY)	AVAILABLE MATERIAL (CY)(1)	UNEXPANDED FILL (CY)	EXPANDED FILL (CY) 1.25(2)	MASS ORDINATE +/- (CY)(3)	208.0100 BORROW (CY)	WASTE (CY)
7+61 - 12+25	MAINLINE	1135	1135	0	0	1135	0	1135
		1135	1135	0	0	1135	0	1135

NOTES:
 1.) AVAILABLE MATERIAL = CUT
 2.) EXPANDED FILL FACTOR = 1.25; EXPANDED FILL = (UNEXPANDED FILL)*1.25
 3.) THE MASS ORDINATE+ OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE CATEGORY.
 MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE CATEGORY.

SILT FENCE

STATION-STATION	LOCATION	628.1504 SILT FENCE (LF)	628.1520 SILT FENCE MAINTENANCE (LF)	TOTALS =
7+61 - 10+01	MAINLINE RT	265	530	795
8+63 - 9+76	MAINLINE LT	120	240	360
10+04 - 11+25	MAINLINE LT	130	260	390
10+35 - 12+60	MAINLINE RT	250	500	750
UNDISTRIBUTED		185	370	555
		950	1,900	

MOBILIZATION EROSION CONTROL

PROJECT	628.1905 MOBILIZATION EROSION CONTROL (EACH)	628.1910 MOBILIZATION'S EMERGENCY EROSION CONTROL (EACH)	TOTALS =
8213-01-70	4	2	6

TEMPORARY DITCH CHECKS

STATION	LOCATION	628.7504 (LF)	TOTALS =
9+52	MAINLINE LT	8	8
11+48	MAINLINE LT	8	16
UNDISTRIBUTED		8	24

FINISHING ITEMS

STATION - STATION	LOCATION	625.0500 SALVAGED TOPSOIL (SY)	627.0200 MULCHING (SY)	629.0210 FERTILIZER TYPE B (CVT)	630.0130 SEEDING MIXTURE NO. 30 (LB)	630.0160 SEEDING MIXTURE NO. 60 (LB)	630.0200 SEEDING TEMPORARY (LB)	630.0500 SEED WATER (MGAL)
7+61 - 12+60	MAINLINE	810	1,920	1.2	32	2	52	50
UNDISTRIBUTED		200	480	0.3	8	1	13	10
		1,010	2,400	1.5	40	3	65	60

*STA. 8+40 - STA. 10+59 RT
 STA. 8+65 - STA. 10+47, LT.
 STA. 10+94 - STA. 12+00, RT.



Proposal Schedule of Items

Proposal ID: 20200512041 Project(s): 8213-01-70

Federal ID(s): WISC 2020288

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0200 Removing Old Structure (station) 01.10+00	LS	LUMP SUM	_____.
0004	205.0100 Excavation Common	1,135.000 CY	_____.	_____.
0006	206.1000 Excavation for Structures Bridges (structure) 01. B-54-133	LS	LUMP SUM	_____.
0008	210.1500 Backfill Structure Type A	270.000 TON	_____.	_____.
0010	213.0100 Finishing Roadway (project) 01.8213-01-70	1.000 EACH	_____.	_____.
0012	305.0110 Base Aggregate Dense 3/4-Inch	35.000 TON	_____.	_____.
0014	305.0120 Base Aggregate Dense 1 1/4-Inch	970.000 TON	_____.	_____.
0016	312.0110 Select Crushed Material	1,180.000 TON	_____.	_____.
0018	455.0605 Tack Coat	61.000 GAL	_____.	_____.
0024	502.0100 Concrete Masonry Bridges	167.000 CY	_____.	_____.
0026	502.3200 Protective Surface Treatment	140.000 SY	_____.	_____.
0028	502.3210 Pigmented Surface Sealer	55.000 SY	_____.	_____.
0030	505.0400 Bar Steel Reinforcement HS Structures	4,510.000 LB	_____.	_____.
0032	505.0600 Bar Steel Reinforcement HS Coated Structures	20,610.000 LB	_____.	_____.
0034	516.0500 Rubberized Membrane Waterproofing	14.000 SY	_____.	_____.
0036	550.0500 Pile Points	10.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200512041 Project(s): 8213-01-70

Federal ID(s): WISC 2020288

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0038	550.1100 Piling Steel HP 10-Inch X 42 Lb	350.000 LF	_____	_____
0040	606.0300 Riprap Heavy	260.000 CY	_____	_____
0042	612.0406 Pipe Underdrain Wrapped 6-Inch	220.000 LF	_____	_____
0044	614.0150 Anchor Assemblies for Steel Plate Beam Guard	4.000 EACH	_____	_____
0046	614.2500 MGS Thrie Beam Transition	160.000 LF	_____	_____
0048	614.2610 MGS Guardrail Terminal EAT	4.000 EACH	_____	_____
0050	618.0100 Maintenance And Repair of Haul Roads (project) 01. 8213-01-70	1.000 EACH	_____	_____
0052	619.1000 Mobilization	1.000 EACH	_____	_____
0054	624.0100 Water	33.000 MGAL	_____	_____
0056	625.0500 Salvaged Topsoil	1,010.000 SY	_____	_____
0058	627.0200 Mulching	2,400.000 SY	_____	_____
0060	628.1504 Silt Fence	950.000 LF	_____	_____
0062	628.1520 Silt Fence Maintenance	1,900.000 LF	_____	_____
0064	628.1905 Mobilizations Erosion Control	4.000 EACH	_____	_____
0066	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____	_____
0068	628.6005 Turbidity Barriers	300.000 SY	_____	_____



Proposal Schedule of Items

Proposal ID: 20200512041 Project(s): 8213-01-70

Federal ID(s): WISC 2020288

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0070	628.7504 Temporary Ditch Checks	24.000 LF	_____.	_____.
0072	629.0210 Fertilizer Type B	1.500 CWT	_____.	_____.
0074	630.0130 Seeding Mixture No. 30	40.000 LB	_____.	_____.
0076	630.0160 Seeding Mixture No. 60	3.000 LB	_____.	_____.
0078	630.0200 Seeding Temporary	65.000 LB	_____.	_____.
0080	630.0500 Seed Water	60.000 MGAL	_____.	_____.
0082	633.5100 Markers Row	13.000 EACH	_____.	_____.
0084	634.0614 Posts Wood 4x6-Inch X 14-FT	2.000 EACH	_____.	_____.
0086	637.2210 Signs Type II Reflective H	11.000 SF	_____.	_____.
0088	638.2602 Removing Signs Type II	3.000 EACH	_____.	_____.
0090	638.3000 Removing Small Sign Supports	3.000 EACH	_____.	_____.
0092	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0094	643.0420 Traffic Control Barricades Type III	1,342.000 DAY	_____.	_____.
0096	643.0705 Traffic Control Warning Lights Type A	2,196.000 DAY	_____.	_____.
0098	643.0900 Traffic Control Signs	13,992.000 DAY	_____.	_____.
0100	643.0920 Traffic Control Covering Signs Type II	8.000 EACH	_____.	_____.
0102	643.5000 Traffic Control	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200512041 Project(s): 8213-01-70
Federal ID(s): WISC 2020288

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0104	645.0111 Geotextile Type DF Schedule A	90.000 SY	_____.	_____.
0106	645.0120 Geotextile Type HR	420.000 SY	_____.	_____.
0108	646.1020 Marking Line Epoxy 4-Inch	871.000 LF	_____.	_____.
0110	650.4500 Construction Staking Subgrade	465.000 LF	_____.	_____.
0112	650.5000 Construction Staking Base	465.000 LF	_____.	_____.
0114	650.6500 Construction Staking Structure Layout (structure) 01. B-54-133	LS	LUMP SUM	_____.
0116	650.9910 Construction Staking Supplemental Control (project) 01. 8213-01-70	LS	LUMP SUM	_____.
0118	650.9920 Construction Staking Slope Stakes	465.000 LF	_____.	_____.
0120	690.0150 Sawing Asphalt	285.000 LF	_____.	_____.
0122	715.0502 Incentive Strength Concrete Structures	1,002.000 DOL	1.00000	1,002.00
0124	465.0105 Asphaltic Surface	280.000 TON	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.