



Wisconsin Department of Transportation

December 2, 2020

Division of Transportation Systems Development
Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

Proposal #22: 6054-06-72, WISC 2021 040
STH 60 - Montello
Columbia Cty Line to B-39-0062
STH 22
Marquette County

6054-06-72, WISC 2021041
STH 60 - Montello
B-39-0062 to 5th Street
STH 22
Marquette County

Letting of December 8, 2020

This is Addendum No. 04, which provides for the following:

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
208.0100	Borrow	TON	0	1,930	1,930
650.9920	Construction Staking Slope Stakes	LF	0	4,339	4,339

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
45	Miscellaneous Quantities (Added Borrow bid item)
47	Miscellaneous Quantities (Corrected an incorrect total on the sheet, the estimate is correct)
50	Miscellaneous Quantities (Added Construction Staking Slope Stakes bid item)

Schedule of Items

Attached, dated December 2, 2020, are the revised Schedule of Items Page 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 45, 47, and 50.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 04
 ID 6054-06-72/73
 Revised Sheet 45
 December 2, 2020

3

STATION	LOCATION	REMARKS	203.0100 EACH	204.0120 SY
REMOVING ASPHALTIC SURFACE MILLING				
PROJECT 6054-06-72				
83+77	CL	24" X 96' CORRUGATED STEEL	1	12,079
112+97	CL	24" X 18" X 55' HE CORRUGATED STEEL	1	53,547
133+88	CL	60" X 84' CORRUGATED STEEL	1	6,990
140+68	CL	30" X 70' CORRUGATED STEEL	1	30,687
295+86	CL	24" X 96' CORRUGATED STEEL	5	103,303
PROJECT 6054-06-73				
388+77	CL	30" X 70' CORRUGATED STEEL	1	16,759
434+66	CL	48" X 76" X 76' HE CORRUGATED STEEL	2	70,010
TOTAL			7	190,072

STATION	LOCATION	REMARKS	204.0115 SY	208.0100 CY
REMOVING SMALL PIPE CULVERTS				
PROJECT 6054-06-72				
83+77	CL	24" X 96' CORRUGATED STEEL	30	842
112+97	CL	24" X 18" X 55' HE CORRUGATED STEEL	35	473
133+88	CL	60" X 84' CORRUGATED STEEL	26	907
140+68	CL	30" X 70' CORRUGATED STEEL	27	681
295+86	CL	24" X 96' CORRUGATED STEEL	24	718
PROJECT 6054-06-73				
388+77	CL	30" X 70' CORRUGATED STEEL	26	648
434+66	CL	48" X 76" X 76' HE CORRUGATED STEEL	29	1245
TOTAL			204,0115	4866

STATION	LOCATION	REMARKS	204.0165 LF	208.0100 CY
REMOVING ASPHALTIC SURFACE BUTT JOINT				
PROJECT 6054-06-72				
86+64	LT	CTH CM	552	590
85+85	RT	BARRY RD	639	400
173+64	RT	GROUSE RD	670	200
174+42	RT	GROUSE RD	606	570
198+75	LT	16TH DR	114	1760
199+16	RT	17TH RD	129	
PROJECT 6054-06-73				
367+60	LT	CTH O	302	120
365+78	RT	WILDERNESS RD	393	50
TOTAL			3,405	1930

STATION	LOCATION	REMARKS	204.0185 CY	208.0100 CY
REMOVING GUARDRAIL				
PROJECT 6054-06-72				
86+64	LT	CTH B	552	590
85+85	RT	16TH CT	639	400
173+64	RT	15TH LN	670	200
174+42	RT	LOWER LOCKS RD	606	570
198+75	LT	FOX LN	114	1760
199+16	RT	CTH XX	129	
PROJECT 6054-06-73				
367+60	LT	E 5TH ST	302	120
365+78	RT		393	50
TOTAL			3,405	1930

STATION	LOCATION	REMARKS	204.0185 CY	208.0100 CY
REMOVING MASONRY				
PROJECT 6054-06-72				
133+88	LT-RT	FIELD STONE ENDWALL	4	170
PROJECT 6054-06-73				
388+77	LT-RT	FIELD STONE ENDWALL	2	170
TOTAL			6	340

STATION	LOCATION	REMARKS	204.0185 CY	208.0100 CY
COMMON EXCAVATION				
PROJECT 6054-06-72				
83+77	SHOULDERS		842	
112+97	MAINLINE		473	
133+88	SHOULDERS		907	
140+68	MAINLINE		681	
295+86	MAINLINE		718	
PROJECT 6054-06-73				
388+77	SHOULDERS		648	
434+66	MAINLINE		1245	
TOTAL			4866	208,0100

STATION	LOCATION	REMARKS	204.0185 CY	208.0100 CY
BORROW				
PROJECT 6054-06-72				
87+35	RT		590	
87+98	LT		400	
175+42	RT		200	
174+87	LT/RT		570	
PROJECT 6054-06-73				
366+50	RT		120	
367+87	LT		50	
TOTAL			1930	208,0100

Addendum No. 04
 ID 6054-06-72/73
 Revised Sheet 47
 December 2, 2020

CROSS DRAIN & SIDE ROAD CULVERT PIPES

STATION	LOCATION	CP CLASS III-B NON-METAL		CPRC CLASS III		CPRC CLASS IV		APRON ENDWALLS FOR CULVERT PIPE		APRON ENDWALLS FOR CULVERT PIPE RC		RIPRAP MEDIUM	GEOTEXTILE TYPE HR	LANE SHIFT
		24-INCH LF	30-INCH LF	520.3624 LF	522.0160 LF	522.2324 LF	520.1024 LF	520.1030 LF	522.1060 LF	522.2624 LF	522.2648 LF			
PROJECT 6054-06-72														
83+77	CL	90	--	--	--	--	--	2	--	--	--	1	4	1
112+97	CL	--	--	53	--	--	--	--	--	2	--	2	6	--
133+88	CL	--	77	--	--	--	--	--	2	--	--	--	--	1
140+68	CL	--	70	--	--	--	--	--	2	--	--	--	--	1
200+30	CL	--	--	--	--	--	--	--	--	--	--	--	--	--
295+86	CL	77	--	--	53	--	--	2	--	2	--	1	4	--
TOTALS		167	126	77	53	63	63	4	4	4	4	11	34	4
PROJECT 6054-06-73														
388+77	CL	--	56	--	--	--	--	2	--	--	--	2	5	--
434+66	CL	--	56	--	--	63	63	2	--	2	--	7	20	1
TOTALS		167	126	77	53	63	63	4	4	4	4	11	34	4

MGS GUARDRAIL

STATION - STATION	LOCATION	614.2610 MGS GUARDRAIL		614.0345 MGS BEAM GUARD		REMARKS
		LF	EACH	LF	RADIUS	
87+48-27 - 94+51.3	LT	603	2	--	--	--
86+85.16 - 93+30.6	RT	545	2	--	--	--
174+37.7 - 8+33 RT	LT	688	2	75	75	CTH O
174+91.8 - 181+72.2	RT	576	2	--	--	--
TOTALS		2412	8	75	75	--
TOTALS		396	2	--	--	--
367+17.3 - 372+11	RT	385	2	--	--	--
365+98.7 - 370+86	RT	781	4	--	--	--
TOTALS		3193	12	75	75	--



BARRIER SYSTEM GRADING SHAPING FINISHING

STATION - STATION	LOCATION	614.0010 BARRIER SYSTEM		628.2023 EMAT		*TOP SOIL SY	*FERTILIZER TYPE B CWT	*SEED MIXTURE NO 20 LB	*EARTHWORK CUT (CY)	*EARTHWORK FILL (CY)	REMARKS
		GRADING SHAPING FINISHING EACH	CLASS II TYPE B SY	CLASS II TYPE B SY	NO 20 LB						
PROJECT 6054-06-72											
85+67 - 87+35	RT	1	134	134	0.08	134	0.08	3.63	6	1099	--
92+80 - 94+33	RT	1	138	138	0.09	138	0.09	3.71	--	--	--
86+30 - 87+98	LT	1	52	52	0.03	52	0.03	1.41	--	--	--
94+01 - 95+62	LT	1	64	64	0.04	64	0.04	1.73	--	--	--
173+20 - 174+87	LT	1	68	68	0.04	68	0.04	1.83	3	805	CTH O
7+31 - 8+85	RT	1	446	446	0.28	446	0.28	12.05	0	509	CTH O
173+73 - 175+42	RT	1	49	49	0.03	49	0.03	1.32	--	--	--
181+22 - 182+92	RT	1	73	73	0.05	73	0.05	1.97	--	--	--
TOTALS		8	1024	1024	0.64	1024	0.64	27.65	28	319	--
PROJECT 6054-06-73											
364+80 - 366+49	RT	1	149	149	0.09	149	0.09	4.01	28	319	--
370+37 - 372+04	RT	1	128	128	0.08	128	0.08	3.47	--	--	--
366+00 - 367+67	LT	1	120	120	0.08	120	0.08	3.25	--	--	--
371+62 - 373+29	LT	1	143	143	0.09	143	0.09	3.87	--	--	--
TOTALS		4	540	540	0.34	540	0.34	14.60	--	--	--
TOTALS		12	1664	1664	0.98	1664	0.98	42.25	--	--	--

* FOR INFORMATION ONLY

LOCATING NO-PASSING ZONES

STATION - STATION	648.0100 MILES
PROJECT 6054-06-72	5.3
PROJECT 6054-06-73	5.3
TOTAL	10.7

PAVEMENT MARKING

STATION - STATION	LOCATION	646.1020		646.1040		646.3040		649.0120	
		MARKING LINE EPOXY 4-INCH YELLOW LF	MARKING LINE GROOVED WET REF EPOXY 4-INCH WHITE LF	MARKING LINE GROOVED WET REF EPOXY 8-INCH WHITE LF	MARKING LINE TEMPORARY MARKING LINE EPOXY YELLOW LF				
PROJECT 6054-06-72 0+26 - 297+76	LT-RT	36,245	58,400	---	36,245				
PROJECT 6054-06-73 297+76 - 555+28	LT-RT	26,360	50,904	106	26,360				
SUB TOTALS		62,605	109,304	106	62,605				

SAWING PAVEMENT

STATION	LOCATION	690.0150 LF
PROJECT 6054-06-72		
0+26	BEGIN PROJECT	30
83+77	CROSS DRAIN	30
112+97	CROSS DRAIN	30
133+88	CROSS DRAIN	30
140+68	CROSS DRAIN	30
295+86	CROSS DRAIN	30
		180
PROJECT 6054-06-73		
388+77	CROSS DRAIN	30
434+66	CROSS DRAIN	30
562+88	END PROJECT	30
		90
TOTAL		270

Addendum No. 04
ID 6054-06-72/73
Revised Sheet 50
December 2, 2020

CONSTRUCTION STAKING

STATION - STATION	650.6000 PIPE CULVERTS EACH	650.8000 RESURFACING REFERENCE LF	650.9920 SLOPE STAKES LF
PROJECT 6054-06-72			
83+77	1	---	---
112+97	1	---	---
133+88	1	---	---
140+68	1	---	---
295+86	1	---	---
	5	29,750	3,271
PROJECT 6054-06-73			
388+77	1	---	---
434+66	2	25,752	1,068
TOTALS	7	55,502	4,339



Proposal Schedule of Items

Proposal ID: 20201208022 Project(s): 6054-06-72, 6054-06-73

Federal ID(s): WISC 2021040, WISC 2021041

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0132	740.0440 Incentive IRI Ride	32,280.000 DOL	1.00000	32,280.00
0134	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,260.000 HRS	5.00000	6,300.00
0136	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	2,000.000 HRS	5.00000	10,000.00
0138	SPV.0060 Special 01. Lane Shift	4.000 EACH	_____	_____
0140	SPV.0090 Special 01. Culvert Pipe Reinforced Concrete Class IV 48X76-Inch HE	63.000 LF	_____	_____
0142	SPV.0170 Special 01. Regrade Cattle Pass	3.600 STA	_____	_____
0144	520.1024 Apron Endwalls for Culvert Pipe 24-Inch	4.000 EACH	_____	_____
0146	520.1030 Apron Endwalls for Culvert Pipe 30-Inch	4.000 EACH	_____	_____
0148	520.3624 Culvert Pipe Class III-B Non-metal 24-Inch	167.000 LF	_____	_____
0150	520.3630 Culvert Pipe Class III-B Non-metal 30-Inch	126.000 LF	_____	_____
0152	305.0120 Base Aggregate Dense 1 1/4-Inch	2,944.000 TON	_____	_____
0154	305.0500 Shaping Shoulders	362.000 STA	_____	_____
0156	208.0100 Borrow	1,930.000 CY	_____	_____
0158	650.9920 Construction Staking Slope Stakes	4,339.000 LF	_____	_____
Section: 0001			Total:	_____
			Total Bid:	_____

