



## Wisconsin Department of Transportation

---

January 7, 2021

**Division of Transportation Systems  
Development**

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #05: 5310-02-76, WISC 2021 077  
Spring Green - Madison  
Walter Road to CTH KP  
USH 14  
Dane County**

### Letting of January 12, 2021

This is Addendum No. 03, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
7	Utilities

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 03**

**5310-02-76**

**January 7, 2021**

**Special Provisions**

**7. Utilities.**

*Add the following after paragraph two:*

Some of the utility work described below is dependent on prior work being performed by the contractor at a specific site. In such situations, provide the engineer and the affected utility a good faith notice of when the utility is to start work at the site. Provide this notice 14 to 16 calendar days in advance of when the prior work will be completed and the site will be available to the utility owner. Follow-up with a confirmation notice to the engineer and the utility owner not less than three working days before the site will be ready for the utility owner to begin its work.

*Replace entire section titled **Mazomanie Electric Utility** with the following:*

**Mazomanie Electric Utility** has underground facilities within the project limits. These facilities had been relocated from overhead in 2019-2020 and now follow along the south R/W line underground with crossings at approximately 5+75, 18+40, 25+00, 30+40, 33+00, 36+15, 40+30, and 46+25. Prior to construction, Mazomanie Electric Utility will lower electric at Inlet T17.2 by 2', will lower electric at Inlet T16.2 electric by 1', will lower electric at Inlet T11.3 by 1', will raise electric at inlet 11.4 by less than a foot, and will raise electric at Station 30+40 by 1'. This work is anticipated to be completed prior to construction

During construction, Mazomanie Electric Utility will move underground electric at Manhole 18.1 by 5' south at the existing depth, will raise electric between manhole 15 and inlet 15.3 by 1', and will raise underground electric between inlets 9.1 and 9.2 electric by 1.5'. This work is anticipated to take less than one working day to complete at each of the three locations.

Field contact for Mazomanie Electric Utility is Shawn Dilley, 608-767-2561, mobile 608-287-4336, sdilley@blackearthwisconsin.com.

END OF ADDENDUM