



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

January 6, 2021

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #14: 6998-05-05, WISC 2021 082
City Waupun, S Madison Street
Doty Street To E Lincoln Street
Local Street
Dodge County

6998-05-06
City Waupun, S Madison Street
Doty Street To E Lincoln Street
Local Street
Dodge County

Letting of January 12, 2021

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
455.0605	Tack Coat	GAL	0	65	65

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
101	Miscellaneous Quantities (Added Tack Coat)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01
6998-05-05, 6998-05-06
January 6, 2021

Schedule of Items

Attached, dated January 6, 2021, are the revised Schedule of Items Page 9.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 101

END OF ADDENDUM

CONCRETE PAVEMENT 8-INCH

STATION-LOCATION	SY
100+00 - 113+00	6,740
TOTAL	6,740

DRIVEWAY ITEMS

STATION	LOCATION	SY	TON
100+31	RT	10	-
101+29	LT	20	-
102+16	LT	10	-
102+65	LT	21	-
102+74	RT	11	2.0
103+34	LT	53	-
104+02	RT	21	-
104+40	LT	33	2.0
104+63	RT	11	2.0
105+49	RT	18	4.0
105+85	LT	16	-
108+07	RT	25	-
108+84	RT	21	-
109+43	RT	29	-
110+94	RT	13	-
111+27	LT	11	4.0
111+67	RT	26	-
112+64	RT	11	2.0
PROJECT 6998-05-05 SUBTOTALS		360	16

STATION-LOCATION	SY
96+95	2
PROJECT 6998-05-05 SUBTOTALS	2
96+95	3
PROJECT 6998-05-06 SUBTOTALS	5
TOTALS	365

DRILLED TIE BARS AND DRILLED DOWEL BARS

STATION-LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	COMMENTS
99+80	6	--	MADISON ST SOUTH LIMITS
113+00	6	32	MADISON ST NORTH LIMITS
209+25	6	--	DOTY ST WEST LIMITS
220+75	6	--	DOTY ST EAST LIMITS
230+75	6	--	PARK AVE EAST LIMITS
239+25	6	--	PARK AVE WEST LIMITS
PROJECT 6998-05-05 SUBTOTALS	36	32	

STATION-LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	COMMENTS
95+61-95+75	12	--	C&G FOR LATERAL REPLACEMENT
95+88-95+98	6	--	C&G FOR CURB RAMP REPLACEMENT
96+42-96+50	6	--	C&G FOR CURB RAMP REPLACEMENT
96+99	3	--	C&G FOR LATERAL REPLACEMENT
97+36	3	--	C&G FOR LATERAL REPLACEMENT
98+34	3	--	C&G FOR LATERAL REPLACEMENT
98+44	3	--	C&G FOR LATERAL REPLACEMENT
PROJECT 6998-05-06 SUBTOTALS	36	--	

STATION-LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	COMMENTS
96+90	3	--	C&G FOR LATERAL REPLACEMENT
97+26	3	--	C&G FOR LATERAL REPLACEMENT
98+24	3	--	C&G FOR LATERAL REPLACEMENT
98+34	3	--	C&G FOR LATERAL REPLACEMENT
PROJECT 6998-05-06 SUBTOTALS	12	--	

STATION-LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	COMMENTS
PROJECT 6998-05-06 SUBTOTALS	48	--	
TOTALS	84	32	

ASPHALTIC SURFACE ITEMS

STATION-LOCATION	TACK COAT GAL	ASPHALTIC SURFACE TON
99+80-100+00	5	30
209+25-209+60	4	18
220+51-220+75	4	17
230+51-230+75	4	16
239+25-239+49	4	17
PROJECT 6998-05-05 SUBTOTALS	21	98

STATION-LOCATION	TACK COAT GAL	ASPHALTIC SURFACE TON
95+61-99+80	23	128
PROJECT 6998-05-06 SUBTOTALS	23	128
96+06-99+80	21	114
PROJECT 6998-05-06 SUBTOTALS	21	114
TOTAL	65	340

TACK COAT CALCULATIONS BASED ON 0.050 GAL/SY ON PREVIOUSLY PLACED LOWER LAYERS
 ASPHALTIC SURFACE WEIGHT CALCULATIONS BASED ON 112 LB/SY/IN.

Addendum No. 01
 ID 6998-05-05/06
 Revised Sheet 101
 January 6, 2021



Proposal Schedule of Items

Proposal ID: 20210112014 Project(s): 6998-05-05, 6998-05-06

Federal ID(s): WISC 2021082, N/A

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0256	SPV.0060 Special 25. Sanitary Sewer Outside Drop Manholes 4-FT Diameter with Casting	2.000 EACH	_____.	_____.
0258	SPV.0090 Special 01. Concrete Curb Pedestrian Decorative	59.000 LF	_____.	_____.
0260	SPV.0090 Special 02. Storm Sewer Lateral PVC 6-Inch	72.000 LF	_____.	_____.
0262	SPV.0090 Special 03. Water Main PVC 6-Inch	95.000 LF	_____.	_____.
0264	SPV.0090 Special 04. Water Main PVC 8-Inch	668.000 LF	_____.	_____.
0266	SPV.0090 Special 05. Water Main PVC 10-Inch	1,948.000 LF	_____.	_____.
0268	SPV.0090 Special 06. Water Service PE 1 1/4-Inch	1,291.000 LF	_____.	_____.
0270	SPV.0090 Special 07. Sanitary Sewer PVC 8-Inch	1,837.000 LF	_____.	_____.
0272	SPV.0090 Special 08. Sanitary Sewer Lateral PVC 6-Inch	1,280.000 LF	_____.	_____.
0274	SPV.0105 Special 01. Abandon Water Main	LS	LUMP SUM	_____.
0276	SPV.0180 Special 01. Preparing Topsoil for Lawn Type Turf	4,070.000 SY	_____.	_____.
0278	455.0605 Tack Coat	65.000 GAL	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.