



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

December 23, 2020

NOTICE TO ALL CONTRACTORS:

Proposal #22: 1470-25-71, WISC 20210 89
SCL - Kewaunee
SCL – South City Limits Kewaunee
STH 42
Kewaunee County

Letting of January 12, 2021

This is Addendum No. 01, which provides for the following:

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
30	Miscellaneous Quantities – Earthwork Summary. Quantities for Mass Ordinate and Waste were changed. Comment/Note (6) was modified and added for BG8.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 30.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 01
ID 1470-25-71
Revised Sheet 30
December 23, 2020

DIVISION	FROM/TO STATION	LOCATION	205.0100 COMMON EXCAVATION		SALVAGED/UNUSABLE PAVEMENT MATERIAL (4)	AVAILABLE MATERIAL (5)	REDUCED EBS IN FILL (9)	SPV.0035.01 FOUNDATION BACKFILL		UNEXPANDED FILL	EXPANDED FILL (13)	MASS ORDINATE +/- (14)	WASTE	COMMENT:
			CUT (2)	EBS EXCAVATION (3)				EXPANDED EBS BACKFILL (11)	FACTOR					
DIVISION 1														
G1B5	100+00/103+03	STH 42	440	246	90	350	197	320	1.30	225	281	315		(7)
BG2	115+88/125+05	STH 42	223	0	0	223	0	0		168	210	13		
BG3	132+72/142+85	STH 42	313	0	0	313	0	0		147	184	129		
PIPE EXTENSION	160+00/160+50	STH 42	0	0	0	0	0	0		15	19	-19		(6)
BG4/C-31-57	179+57/187+40	STH 42	912	0	135	777	0	0		322	403	375		
BG5	206+88/216+20	STH 42	243	0	0	243	0	0		70	88	156		
BG6	233+94/243+58	STH 42	226	0	0	226	0	0		144	180	46		
BG7	293+05/304+20	STH 42	310	0	0	310	0	0		60	75	235		
BG8	365+28/372+78	STH 42	186	0	0	186	0	0		343	429	-243		(6)
C-31-56	401+93/405+10	STH 42	512	0	86	426	0	0		153	191	235		
DIVISION 1 SUBTOTAL			3,365	246	311	3,054	197	320		1,647	2,059	1,241		
GRAND TOTAL			3,365	246	311	3,054	197	320		1,647	2,059	1,241		
TOTAL COMMON EXC			3,611											

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
- (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
- (3) EBS EXCAVATION TO BE BACKFILLED WITH FOUNDATION BACKFILL.
- (4) SALVAGED/UNUSABLE PAVEMENT MATERIAL TO BE HAULED OFFSITE.
- (5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
- (6) USE ACCEPTABLE WASTE AS FILL FROM OTHER EARTHWORK AREAS
- (7) INCLUDES QTY FOR DRIVEWAY EXCAVATION AT GIBS (NORTH AND SOUTH DWYS)
- (9) REDUCED EBS IN FILL - EXCAVATED EBS MATERIAL IS USABLE IN FILLS OUTSIDE THE 1:1 SLOPE. EBS IN FILL REDUCTION FACTOR = 0.80
- (11) EXPANDED EBS BACKFILL - THIS IS TO BE FILLED WITH FOUNDATION BACKFILL MATERIAL. EBS BACKFILL FACTOR = 1.30. ITEM SPV.0035.01 FOUNDATION BACKFILL.
- (13) EXPANDED FILL FACTOR = 1.25. EXPANDED FILL = UNEXPANDED FILL * FILL FACTOR
- (14) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS QUANTITY INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION. MASS ORDINATE = [(CUT - SALVAGED PAYT) - (FILL - REDUCED EBS IN FILL) * FILL FACTOR]