



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

December 16, 2020

### NOTICE TO ALL CONTRACTORS:

**Proposal #28: 1160-00-79, WISC 2021 094**  
**Packwaukee – Plainfield**  
**STH 73 Interchange**  
**IH 39**  
**Waushara County**

**6321-00-71, WISC 2021 095**  
**Plainfield – Wisconsin Rapids**  
**5th Ave to 4th Court**  
**STH 73**  
**Waushara County**

### Letting of January 12, 2021

This is Addendum No. 01, which provides for the following:

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
77	Miscellaneous Quantities - Revising notes for earthwork

#### **Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 77

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

Addendum No. 01  
 ID 1160-00-79 &  
 ID 6321-00-71  
 Revised Sheet 77  
 December 16, 2020

Division	Project ID	From/To Station	Location	Common Excavation (1) (Item# 205.0100)		Available Material (2)	Unexpanded Fill	Expanded Fill (3)		Mass Ordinate +/- (4)	Waste	Borrow (Item #208.0100)	Comment:
				Cut	Fill			Factor	Factor				
1	6321-00-71	3+74 to 55+00	STH73 Temp Pmnt	817	817	817	831	1,038	1,038	-221	-221	221	Includes sidereads
Division 1 Subtotal				817	817	817	831	1,038	1,038	-221	-221	221	
2	6321-00-71	6+35 to 25+00	STH73	1,259	1,259	1,259	182	227	1,032	1,032	0	0	
	1160-00-79	25+00 to 35+26	STH73	436	436	436	2	2	434	434	0	0	
	6321-00-71	35+26 to 50+80	STH73	809	809	809	33	42	767	767	0	0	
	6321-00-71	6+00 to 55+00	STH73 Temp Pmnt	1,006	1,006	1,006	558	698	308	308	0	0	Includes sidereads
	6321-00-71	158+48 to 159+00	4th Ct	38	38	38	31	39	0	0	0	0	
	1160-00-79	49+53 to 53+00	Ramp B	487	487	487	3	4	484	484	0	0	
	1160-00-79	53+62 to 54+00	Ramp C	130	130	130	130	130	0	0	0	0	
Division 2 Subtotal				4,166	4,166	4,166	809	1,011	3,155	3,155	0	0	
3	6321-00-71	6+35 to 25+00	STH73	1,918	1,918	1,918	33	42	1,876	1,876	0	0	
	1160-00-79	25+00 to 35+26	STH73	1,259	1,259	1,259	2	3	1,256	1,256	0	0	
	6321-00-71	35+26 to 50+80	STH73	1,436	1,436	1,436	141	176	1,260	1,260	0	0	
	1160-00-79	54+00 to 55+36	Ramp A	228	228	228	43	54	174	174	0	0	
	1160-00-79	56+50 to 68+50	Ramp D	2,072	2,072	2,072	81	101	1,971	1,971	0	0	
Division 3 Subtotal				6,912	6,912	6,912	300	375	6,537	6,537	0	0	
4	6321-00-71	63+50 to 65+70	5th Ave	0	0	0	0	0	0	0	0	0	
Division 4 Subtotal				0	0	0	0	0	0	0	0	0	
Project Subtotal 1160-00-79				4,612	4,612	4,612	130	163	4,449	4,449	0	0	
Project Subtotal 6321-00-71				7,284	7,284	7,284	1,809	2,262	5,022	5,022	0	221	
Grand Total				11,896	11,896	11,896	1,939	2,424	9,472	9,472	0	221	
Total Common Exc				11,896	11,896	11,896	1,939	2,424	9,472	9,472	0	221	

1) Common Excavation is the sum of the Cut and EBS Excavation columns. Item number 205.0100  
 2) Available Material = Common Excavation  
 3) Expanded Fill Factor = 1.25  
 Depending on selections:  
 Expanded Fill = (Unexpanded Fill - Rock\* Rock Factor - Reduced Marsh - Reduced EBS) \* Fill Factor  
 Expanded Fill = (Unexpanded Fill - Rock\* Rock Factor - Reduced Marsh) \* Fill Factor  
 Expanded Fill = (Unexpanded Fill - Rock\* Rock Factor) \* Fill Factor  
 4) The Mass Ordinate + or - Qty calculated for the Division. Plus quantity indicates an excess of material within the Division. Minus indicates a shortage of material within the Division.