



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

March 3, 2021

### NOTICE TO ALL CONTRACTORS:

**Proposal #03: 3804-00-74, WISC 2021 218**  
**Town of Lowell, Bobolink Rd**  
**CPRS Rail Road Bridge, B-14-0225**  
**Local Street**  
**Dodge County**

### Letting of March 9, 2021

This is Addendum No. 02, which provides for the following:

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
201.0105	Clearing	STA	0	4	4
201.0205	Grubbing	STA	0	4	4

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
6	Miscellaneous Quantities (Added items)

#### **Schedule of Items**

Attached, dated March 3, 2021, are the revised Schedule of Items Page 5.

#### **Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 6

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

BOBOLINK ROAD EARTHWORK SUMMARY

From/To Station	Location	Common Excavation (1)		Unexpanded Fill		Expanded Fill		Mass Ordinate +/- (3)	Waste (4)	Borrow	Comment:
		(item # 205.0100)	Cut	(item # 205.0100)	Factor 1.30	(2)	Factor 1.30				
7+00 to 13+00	PROJECT LIMITS	205		3263		4242		-4037		4037	(item #208.0100)

- 1) Common Excavation is the Cut. Item number 205.0100.
- 2) Expanded Fill. Factor = 1.30; Expanded Fill = Unexpanded Fill \* Fill Factor
- 3) All quantities shown in CY.
- 4) The Mass Ordinate + or - Qty calculated for the Division. Plus quantity indicates an excess of material on the project.

CLEARING AND GRUBBING

STA	TO STA	OFFSET	STA	STA
8+00	-	12+00	LT & RT	4

TOTALS 4 4 4

Note: Grade around tree at STA 7+25 RT

GUARDRAIL

STATION	TO	STATION	OFFSET	EACH
8+13	-	9+04	LT	1
8+30	-	9+21	RT	1
10+80	-	11+70	LT	1
10+96	-	11+87	RT	1
TOTALS				4

PAVING AND BASE QUANTITIES

STA	TO STA	OFFSET	TON	TON	SY	GAL	TON	MGAL
7+00	--	8+93	LT/RT	580	-	37	117	9.4
8+93	--	9+23	LT/RT	45	58	-	-	0.8
10+77	--	11+07	LT/RT	45	58	-	-	0.8
11+07	--	13+00	LT/RT	605	-	35	111	9.9
UNDISTRIBUTED				14	65	4	11	1.2
TOTALS			129	1,340	123	76	239	23

STAKING ITEMS

FINISHING ROADWAY (ID 3804-00-74)	MAINTENANCE AND REPAIR OF HAUL ROADS (ID 3804-00-74)	CONSTRUCTION STAKING SUBGRADE	CONSTRUCTION STAKING BASE	CONSTRUCTION STAKING CONCRETE PAVEMENT	CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (ID 3804-00-74)	CONSTRUCTION STAKING SLOPE STAKES
213.0100.01	618.0100.01	650.4500	650.5000	650.7000	650.9910.01	650.9920
LOCATION EACH	CATEGORY EACH	CONSTRUCTION STAKING SUBGRADE	CONSTRUCTION STAKING BASE	CONSTRUCTION STAKING CONCRETE PAVEMENT	CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (ID 3804-00-74)	CONSTRUCTION STAKING SLOPE STAKES
MAINLINE 1	0030 1	LF	LF	LF	LS	LF
TOTAL 1	TOTAL 1	516	516	44	1	516
		---	---	---	---	---
		516	516	44	1	516

ALL QUANTITIES CATEGORY 0010 UNLESS OTHERWISE NOTED



Proposal Schedule of Items

Proposal ID: 20210309003 Project(s): 3804-00-74

Federal ID(s): WISC 2021218

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0130	715.0502 Incentive Strength Concrete Structures	3,516.000 DOL	1.00000	3,516.00
0132	801.0117 Railroad Flagging Reimbursement	15,000.000 DOL	1.00000	15,000.00
0134	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,200.000 HRS	5.00000	6,000.00
0136	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0138	SPV.0105 Special 01. Settlement Monitoring	LS	LUMP SUM	_____.
0140	SPV.0165 Special 01. Temporary Shoring Railroad	850.000 SF	_____.	_____.
0142	201.0105 Clearing	4.000 STA	_____.	_____.
0144	201.0205 Grubbing	4.000 STA	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
				<b>Total Bid:</b> _____.

