



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

March 3, 2021

NOTICE TO ALL CONTRACTORS:

Proposal #23: 7823-03-70, WISC 2021 237
Fall Creek – North County Line
Fall Creek Bridge B-18-0237
CTH K
Eau Claire County

Letting of March 9, 2021

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0420	Traffic Control Barricades Type III	DAY	1,425	665	2,090
643.0705	Traffic Control Warning Lights Type A	DAY	2,250	1,050	3,300
643.0900	Traffic Control Signs	DAY	13,875	6,475	20,350

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
16	Miscellaneous Quantities: Revised traffic control quantities

Other

Revise Contract Completion Time from 40 working days to 60 working days (an increase of 20 working days).

Schedule of Items

Attached, dated March 3, 2021, are the revised Schedule of Items Pages 4 and 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 16.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 01
 ID 7823-03-70
 Revised Sheet 16
 March 3, 2021

SIGNAGE

STATION	LOCATION	EACH	SF	EACH	MOVING SIGNALS TYPE II	REMOVING SIGNALS TYPE II	REMOVING SIGNALS TYPE II	REMOVING SMALL SIGN SUPPORTS	MOVING SMALL SIGN SUPPORTS	SIGNAGE TYPE
8+53	RT	--	--	3	--	--	--	--	1	"BEAVER CREEK RESERVE" SIGNS
9+46	LT	1	3	--	--	--	--	--	--	W5-52L
9+50	RT	1	3	--	--	--	--	--	--	W5-52R
9+64	LT	--	--	--	1	1	1	1	--	W5-52L
9+64	RT	--	--	--	1	1	1	1	--	W5-52R
10+39	LT	--	--	--	1	1	1	1	--	W5-52L
10+39	RT	--	--	--	1	1	1	1	--	W5-52R
10+49	LT	1	3	--	--	--	--	--	--	W5-52L
10+37	RT	1	3	--	--	--	--	--	--	W5-52L
TOTALS		4	12	3	4	4	4	4	1	

NOTE: EAU CLAIRE COUNTY TO REMOVE THE PLOW UP AND PLOW DOWN SIGNS AT THE ENDS OF THE GUARDRAIL PRIOR TO CONSTRUCTION.

TRAFFIC CONTROL ITEMS

LOCATION	BARRICADES TYPE III	NO.	DAY	NO.	DAY	NO.	DAY
643.0420	643.0705	643.0900					
DURATION	WARNING LIGHTS TYPE A	SIGNS					
DAYS	NO.	NO.	DAY	NO.	DAY	NO.	DAY
110	30	15	3,300	15	1,650	170	18,700
110	--	--	--	--	--	--	--
PER SDD "BARRICADES AND SIGNS FOR MAINTENANCE CLOSURES"							
PER DETOUR PLAN							
TOTALS		2,090	3,300	20,350			

TRAFFIC CONTROL PLACEMENT SUBJECT TO ENGINEER APPROVAL

ALL QUANTITIES CATEGORY 0010 UNLESS OTHERWISE NOTED

PROJECT NO: 7823-03-70

HWY: CTH K

COUNTY: EAU CLAIRE

MISCELLANEOUS QUANTITIES

SHEET NO: 16

E



Proposal Schedule of Items

Proposal ID: 20210309023 Project(s): 7823-03-70

Federal ID(s): WISC 2021237

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	628.2027 Erosion Mat Class II Type C	240.000 SY	_____.	_____.
0098	628.6005 Turbidity Barriers	170.000 SY	_____.	_____.
0100	628.7504 Temporary Ditch Checks	50.000 LF	_____.	_____.
0102	629.0210 Fertilizer Type B	0.300 CWT	_____.	_____.
0104	630.0120 Seeding Mixture No. 20	13.000 LB	_____.	_____.
0106	630.0200 Seeding Temporary	13.000 LB	_____.	_____.
0108	630.0500 Seed Water	11.000 MGAL	_____.	_____.
0110	631.0300 Sod Water	4.000 MGAL	_____.	_____.
0112	631.1000 Sod Lawn	20.000 SY	_____.	_____.
0114	634.0612 Posts Wood 4x6-Inch X 12-FT	4.000 EACH	_____.	_____.
0116	637.2230 Signs Type II Reflective F	12.000 SF	_____.	_____.
0118	638.2102 Moving Signs Type II	3.000 EACH	_____.	_____.
0120	638.2602 Removing Signs Type II	4.000 EACH	_____.	_____.
0122	638.3000 Removing Small Sign Supports	4.000 EACH	_____.	_____.
0124	638.4000 Moving Small Sign Supports	1.000 EACH	_____.	_____.
0126	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0128	643.0420 Traffic Control Barricades Type III	2,090.000 DAY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210309023 Project(s): 7823-03-70

Federal ID(s): WISC 2021237

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0130	643.0705 Traffic Control Warning Lights Type A	3,300.000 DAY	_____.	_____.
0132	643.0900 Traffic Control Signs	20,350.000 DAY	_____.	_____.
0134	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0136	645.0111 Geotextile Type DF Schedule A	100.000 SY	_____.	_____.
0138	645.0120 Geotextile Type HR	840.000 SY	_____.	_____.
0140	645.0130 Geotextile Type R	15.000 SY	_____.	_____.
0142	646.1020 Marking Line Epoxy 4-Inch	445.000 LF	_____.	_____.
0144	650.4500 Construction Staking Subgrade	340.000 LF	_____.	_____.
0146	650.5000 Construction Staking Base	340.000 LF	_____.	_____.
0148	650.5500 Construction Staking Curb Gutter and Curb & Gutter	60.000 LF	_____.	_____.
0150	650.6500 Construction Staking Structure Layout (structure) 01.B-18-237	LS	LUMP SUM	_____.
0152	650.9910 Construction Staking Supplemental Control (project) 01.7823-03-70	LS	LUMP SUM	_____.
0154	650.9920 Construction Staking Slope Stakes	340.000 LF	_____.	_____.
0156	690.0150 Sawing Asphalt	126.000 LF	_____.	_____.
0158	715.0502 Incentive Strength Concrete Structures	1,392.000 DOL	1.00000	1,392.00
0160	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,200.000 HRS	5.00000	6,000.00

