



# Wisconsin Department of Transportation

February 23, 2021

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #24: 7823-07-72, WISC 2021 238**  
**Fall Creek - NCL**  
**Boardwalk Street to CTH N**  
**CTH D**  
**Eau Claire County**

### Letting of March 9, 2021

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
15	Pulverize and Relay, Item 325.0100

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0300	Traffic Control Drums	DAY	1,788	1,100	2,888
643.0900	Traffic Control Signs	DAY	1,694	8	1,702

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
42	Traffic Control Summary – added applicable Standard Detail Drawing codes and revised estimated traffic control quantities for project-wide pulverize and relay operations.
63	Miscellaneous Quantities – revised traffic control quantities for drums and signs.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**7823-07-72**

**February 23, 2021**

**Special Provisions**

**3. Prosecution and Progress**

*Replace paragraph four with the following:*

The schedule of operations as required under standard spec 108.4.2 of the standard specs shall provide for HMA paving to commence on CTH D within ten calendar days of the commencement of pulverize and relay.

**15. Pulverize and Relay, Item 325.0100**

*Replace the second section referring to 325.3(1) with the following:*

*Replace standard spec 325.3(1) with the following:*

- (1) Pulverize the full depth of the existing asphaltic pavement until 97 percent or more will pass the 2-inch sieve. Also pulverize the existing base to the depth the plans show and mix with the pulverized asphaltic pavement and base aggregate special top layer. Windrow material as construction operations dictate. Remove existing shoulders adjacent to surfaces to be reclaimed as the plans show. Shoulders may be removed prior to and during reclamation. Remove the existing shoulders to the depths and limits shown on the plans. Keep excavated shoulders closed until shoulders are backfilled. Backfill shoulders within 48 hours from the time of shoulder removal. Dispose of existing shoulder material in accordance with standard spec 205.3.12.

*Replace the fifth section referring to 325.4(1) and replace with the following:*

*Replace standard spec 325.4(1) with the following:*

- (1) The department will measure Pulverize and Relay by the square yard acceptably completed, measured using the centerline length and the width from outside to outside of completed base, but limited to the width the plans show or the engineer directs. The removal and backfilling of shoulders where shown as incidental on the plans, the moving of pulverized material along the project as the plans show, and the moving of pulverized material to allow subgrade work at locations shown on the plans will not be measured for payment and are incidental to pulverize and relay.

**Schedule of Items**

Attached, dated February 23, 2021, are the revised Schedule of Items Page 5.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 42, 63.

END OF ADDENDUM

ESTIMATED WORK ZONE DISTRIBUTION OF TEMPORARY TRAFFIC CONTROL SIGNING AND DEVICES

WORK ZONE	APPLICABLE STANDARD DETAIL DRAWINGS	ROAD WORK AHEAD W20-1A (DAYS)	ROAD WORK NEXT 3 MILES G20-1 (DAYS)	END ROAD WORK G20-2A (DAYS)	ROAD WORK 250 FT W20-1H (DAYS)	ONE LANE ROAD AHEAD W20-1A (DAYS)	RUMBLE STRIPS AHEAD W21-65 (DAYS)	FLAGGER W20-7A (DAYS)	BE PREPARED TO STOP W3-1 (DAYS)	LOOSE GRAVEL W8-7 (DAYS)	SHOULDER DROP-OFF W8-9A (DAYS)	LANE DROP-OFF W8-17 (DAYS)	UNEVEN LANES W8-11 (DAYS)	SHOULDER WORK W21-5 (DAYS)	ROAD CLOSED R11-2 (DAYS)	LANE CLOSED R11-2L (DAYS)	TYPE III BARRICADE (DAYS)	TYPE A WARNING LIGHT (DAYS)	TRAFFIC CONTROL DRUMS (DAYS)	TRAFFIC CONTROL CONES 42" (DAYS)
ADVANCE WARNING SIGNS PROJECT-WIDE	A,H	500	100	150	250	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
PULVERIZE & RELAY HVA PAVING PROJECT-WIDE	B,C,D,E,G	...	...	...	...	36	36	36	...	162	4	...	108	4	...	...	...	...	1100	...
CTH D CURB & GUTTER STA 34+25 - STA 37+00 STA 86+00 - STA 88+50	B,C,G	...	...	...	...	8	8	8	...	...	...	...	...	16	...	...	...	...	496	...
CTH D CULVERT REMOVAL & REPLACEMENT	C	...	...	...	...	4	4	4	...	...	...	...	...	...	...	...	...	...	10	...
GREEN MEADOW ROAD INTERSECTION GRADING & CTH D DITCHING	B,F,G	...	...	...	...	10	10	10	...	...	...	...	...	10	10	...	43	55	310	...
PROFILE CORRECTION STA 85+75 - STA 89+25	C,E,G	...	...	...	...	8	8	8	...	...	...	24	...	...	...	...	...	...	...	420
BRIDGE RAILING BEAM GUARD & CRASH CUSHIONS STA 95+00 - STA 101+00	B,C,G	...	...	...	...	16	16	16	...	...	...	...	...	16	...	...	...	...	400	...
BEAM GUARD STA 106+00 LT - STA 117+00 RT	B,C,G	...	...	...	...	10	10	10	...	...	...	...	...	10	...	...	...	...	310	...
CTH D RECONSTRUCTION STA 130+25 - STA 131+75	C,E,G	...	...	...	...	4	4	4	4	...	...	4	...	...	...	2	6	8	6	18
SHOULDER WIDENING STA 148+50 LT - STA 154+00 RT	B,C,E,G	...	...	...	...	8	8	8	...	...	8	...	...	8	...	...	...	...	256	...
TOTAL DAYS		500	100	150	250	104	104	104	4	162	12	4	132	64	10	2	51	63	2888	438

KEY	STANDARD DETAIL DRAWING
A	TRAFFIC CONTROL ADVANCE WARNING SIGNS AS M.P.H. OR GREATER, TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC
B	TRAFFIC CONTROL WORK ON SHOULDER OR PARKING LANE UNDIVIDED ROADWAY
C	TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION
D	TRAFFIC CONTROL SIGNING ON ROADWAYS WITH LOOSE GRAVEL
E	TRAFFIC CONTROL DROP-OFF SIGNING
F	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
G	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS

Addendum No. 01  
ID 7823-07-72  
Revised Sheet 42  
February 23, 2021

TRAFFIC CONTROL

643.0300 643.1070 643.0420 643.0705 643.0900

Table with columns: PROJECT ID, ROADWAY, LOCATION, USAGE, DURATION, DRUMS, CONES, BARRICADES, WARNING LIGHTS, SIGNS, REFERENCE. Includes sub-totals for PROJECT 7823-07-72 and TOTAL.

LOCATING NO-PASSING ZONES

Table with columns: PROJECT ID, STATION TO, STATION FROM, LOCATION, MI. Includes sub-totals for PROJECT 7823-07-72 and TOTAL.

CONSTRUCTION STAKING

Table with columns: PROJECT ID, STATION TO, STATION FROM, LOCATION, CONSTRUCTION STAKING, CURB & GUTTER, SUBGRADE, CONSTRUCTION STAKING, PIPE, CULVERTS, CONSTRUCTION STAKING, RESURFACING, CONSTRUCTION STAKING, SUPPLEMENTAL, CONSTRUCTION STAKING, SLOPE/STAKES. Includes sub-totals for PROJECT 7823-07-72 and TOTAL.

Addendum No. 01 ID 7823-07-72 Revised Sheet 63 February 23, 2021

Summary table with columns: PROJECT NO: 7823-07-72, HWY: CTH D, COUNTY: EAU CLAIRE, MISCELLANEOUS QUANTITIES, SHEET: 63, E.

FILE NAME: PLOT DATE: PLOT BY: PLOT NAME: COUNTY: EAU CLAIRE ORG DATE: ORIGINATOR: DIST: PLOT SCALE: 1:1



Proposal Schedule of Items

Proposal ID: 20210309024 Project(s): 7823-07-72

Federal ID(s): WISC 2021238

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0128	630.0500 Seed Water	105.000 MGAL	_____.	_____.
0130	633.5200 Markers Culvert End	2.000 EACH	_____.	_____.
0132	634.0614 Posts Wood 4x6-Inch X 14-FT	16.000 EACH	_____.	_____.
0134	634.0616 Posts Wood 4x6-Inch X 16-FT	45.000 EACH	_____.	_____.
0136	634.0618 Posts Wood 4x6-Inch X 18-FT	13.000 EACH	_____.	_____.
0138	634.0812 Posts Tubular Steel 2x2-Inch X 12-FT	8.000 EACH	_____.	_____.
0140	637.2210 Signs Type II Reflective H	99.000 SF	_____.	_____.
0142	637.2230 Signs Type II Reflective F	322.000 SF	_____.	_____.
0144	638.2102 Moving Signs Type II	9.000 EACH	_____.	_____.
0146	638.2602 Removing Signs Type II	62.000 EACH	_____.	_____.
0148	638.3000 Removing Small Sign Supports	46.000 EACH	_____.	_____.
0150	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0152	643.0300 Traffic Control Drums	2,888.000 DAY	_____.	_____.
0154	643.0420 Traffic Control Barricades Type III	51.000 DAY	_____.	_____.
0156	643.0705 Traffic Control Warning Lights Type A	63.000 DAY	_____.	_____.
0158	643.0900 Traffic Control Signs	1,702.000 DAY	_____.	_____.
0160	643.1070 Traffic Control Cones 42-Inch	438.000 DAY	_____.	_____.

