



Wisconsin Department of Transportation

April 2, 2021

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #07: 2110-00-73, WISC 2021260
W Lincoln Avenue
Intersect W/ 84th, 76th & 71st Str
LOC STR
Milwaukee County

Letting of April 13, 2021

This is Addendum No. 01, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
45	Notice to Contractor, Hazardous Materials Soil Boring Coordination
46	Field Facilities Office Space, Item SPV.0060.17
47	Marking Grooved Preformed Thermoplastic Arrows Type 2, Item SPV.0060.15; Marking Grooved Preformed Thermoplastic Stop Line 18-Inch, Item SPV.0090.03; Marking Grooved Preformed Thermoplastic Crosswalk Block Style 24-Inch, Item SPV.0090.04; Marking Diagonal Grooved Preformed Thermoplastic 12-Inch, Item SPV.0090.05.

Deleted Special Provisions	
Article No.	Description
15	Field Office
35	Marking Grooved Preformed Thermoplastic Arrows Type 2, Item SPV.0060.15; Marking Grooved Thermoplastic Stop Line 18-Inch, Item SPV.0090.03; Marking Grooved Thermoplastic Stop Line Crosswalk Block Style 24-Inch, Item SPV.0090.04; Marking Diagonal Grooved Preformed Thermoplastic 12-Inch, Item SPV.0090.05.

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
SPV.0060.17	Field Facilities Office Space	EACH	0	1	1

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
642.5001	Field Office Type B	EACH	1	0	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
86	Miscellaneous Quantities (removed item 642.5001 and added item SPV.0060.17)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

2110-00-73

April 2, 2021

Special Provisions

35. DELETED

45. Notice to Contractor, Hazardous Materials Soil Boring Coordination.

The department's environmental consultant will be conducting soil borings within the temporary limited easement at the southeast corner of the W. Lincoln Avenue/S. 84th Street intersection during construction. Coordinate with the environmental consultant to arrange an acceptable time for the borings to be completed. Clearly mark the temporary limited easement boundaries prior to the consultant arriving on site. Notify the engineer at least 10 business days prior to the southeast corner of the intersection becoming available for use. The environmental consultant is as follows:

Consultant: TRC Environmental Corporation
Address: 150 N. Patrick Blvd., Ste. 180, Brookfield, WI 53045
Contact: Bryan Bergmann
Phone: (262) 901-2126 office, (262) 227-9210 cell
Fax: (262) 879-1220
E-mail: bbergmann@trccompanies.com

46. Field Facilities Office Space, Item SPV.0060.17.

A Description

This special provision describes furnishing, equipping, and maintaining a field office as required in the contract at engineer-approved locations conforming to standard spec 642 and as follows.

B Materials

Provide Field Facilities Office Space conforming to standard spec 642.2.1 except delete paragraphs (1), (7), and (9).

Replace standard spec 642.2.1(4) with the following:

Provide and maintain suitable interior sanitary facilities conforming to State and local health requirements, in clean and good working condition, and stock with sanitary supplies for the duration of the contract. Furnish office space in an existing office building or existing building converted to office space with a minimum of 600 square feet. The facility shall have no fee parking with a minimum parking for 10 cars. The space shall include a meeting room with a minimum of 150 square feet. The exterior door(s) shall have locks in good working order and keys provided for all field staff. The office space shall be located within 2 miles of the construction project.

Equip the office as specified in standard spec 642.2.2.1 except delete paragraph (1) and (4) and add the following:

1. 3 suitable office desks with drawers and locks.
2. 3 ergonomically correct office chairs in working condition with at a minimum: 5-legged base with casters, seat adjustable from 15 to 22 inches from the floor with a seamless waterfall, rounded, front edge, and high backrest with no arms or adjustable arms.
3. 4 six-foot folding tables.
4. 1 ten-foot folding table.
5. 3 two-drawer file cabinets.

- 6. 3 four-shelf bookcases.
- 7. 10 folding chairs.

Provide for the professional cleaning of the field office during regular business hours twice monthly. Provide clearly marked recycling and waste receptacles within the field office, and separate recycling and waste dumpsters near the field office. Cover outdoor containers to keep out rain, snow, and wind-driven debris. Provide regularly scheduled recycling and waste pick-up.

C Construction

Conform to standard spec 642.3 except delete paragraph (2).

D Measurement

The department will measure the Field Facilities Office Space as each office acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.17	Field Facilities Office Space	EACH

Payment is full compensation for providing, equipping, securing, and maintaining the facility; for parking, for telecommunications equipment, installation, and service fees; and for providing bottled water, utilities, fuel, ventilation, and toilet facilities as required, either independently or jointly with the field laboratory, for the time specified in 642.3.

The department will pay for the cost of telecommunications usage fees incurred by department staff.

47. Marking Grooved Preformed Thermoplastic Arrows Type 2, Item SPV.0060.15; Marking Grooved Preformed Thermoplastic Stop Line 18-Inch, Item SPV.0090.03; Marking Grooved Preformed Thermoplastic Crosswalk Block Style 24-Inch, Item SPV.0090.04; Marking Diagonal Grooved Preformed Thermoplastic 12-Inch, Item SPV.0090.05.

A Description

This special provision describes furnishing, grooving and installing preformed thermoplastic pavement markings as shown on the plans, according to standard spec 646, and as hereinafter provided.

B Materials

Furnish preformed thermoplastic pavement markings per manufacturer's recommendations and that meet the approval of the engineer. Marking materials shall be free of volatile organic compounds.

Furnish a copy of the manufacturer's specifications and recommendations to the engineer before preparing the pavement marking grooves.

C Construction

C.1 General

For quality assurance, provide the engineer evidence of manufacturer training in the proper placement and installation of preformed thermoplastic pavement marking.

Plane the grooved areas per manufacturer's recommendations. Use grooving equipment with a free-floating, independent cutting head. Plane a minimum number of passes to create a grooved surface.

C.2 Grooving

Replace standard spec 646.3.2.3.1(1) and (2) with the following:

- (1) Cut the groove to a depth of 120 mils ± 10 mils from the pavement surface or, if tined, from the high point of the tined surface. To measure the depth, the contractor may use a depth plate placed in the groove and a straightedge placed across the plate and groove, or the contractor may use a straightedge placed perpendicular to the groove. The department may periodically check groove depths.

- (2) Groove between 0 and 4 inches wider than the perimeter of the pavement marking. Achieve straight alignment with the grooving equipment, not to exceed 3/8 inch variation in any 40-foot length of marking. Use a high-pressure air blower to clean the groove.

C.3 Marking Application

Prepare the pavement surface and apply the pavement markings per manufacturer specifications.

Apply the pavement markings when the ambient temperature is above 32 degrees F. Prior to placing the markings, heat the pavement surface to at least 300 degrees F within the targeted area of the marking and at least 3 inches beyond the perimeter of the marking.

D Measurement

The department will measure Marking Grooved Preformed Thermoplastic by the unit, acceptably placed, or in length by the linear foot of line, placed according to the contract and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.15	Marking Grooved Preformed Thermoplastic Arrows Type 2	EACH
SPV.0090.03	Marking Grooved Preformed Thermoplastic Stop Line 18-Inch	LF
SPV.0090.04	Marking Grooved Preformed Thermoplastic Crosswalk Block Style 24-Inch	LF
SPV.0090.05	Marking Diagonal Grooved Preformed Thermoplastic 12-Inch	LF

Payment is full compensation for cleaning and preparing the pavement surface; furnishing and installing the material; and for removing existing or temporary pavement markings located within the limits of the grooved in permanent markings, if necessary.

Schedule of Items

Attached, dated April 2, 2021, are the revised Schedule of Items Pages 1 – 11.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 86

END OF ADDENDUM

DETECTABLE WARNING FIELDS	
602.0505 CURB RAMP	602.0605
DETECTABLE WARNING FIELD	
YELLOW SF	RADIAL YELLOW SF
LOCATION STATION TO STATION	
84TH ST 103+70 - 109+56	40 23
76TH ST 130+38 - 136+05	40 21
71ST ST 146+22 - 151+87	40 46
PROJECT TOTALS	120 90

PROJECT WIDE ITEMS			
211.0300 PREPARE FOUNDATION FOR CONCRETE BASE	213.0100 FINISHING ROADWAY	619.1000 MOBILIZATION	643.5000 TRAFFIC CONTROL (2110-00-73)
2110-00-73 LS	2110-00-73 EACH	2110-00-73 EACH	2110-00-73 EACH
1	1	1	1
PROJECT TOTALS	1	1	1

SPV/0060.17
 FIELD FACILITIES OFFICE SPACE
 EACH 1

LANDMARK REFERENCE MONUMENTS	
621.0100 EACH	
LOCATION	
LINCOLN AVE / 84TH ST	1
LINCOLN AVE / 76TH ST	1
PROJECT TOTALS	2

RESTORATION ITEMS		
625.0100 TOPSOIL SY	631.0300 SOD WATER MGAL	631.1000 SOD LAWN SY
LOCATION STATION TO STATION		
84TH ST 103+70 - 109+56	32 0.7	32
76TH ST 130+38 - 136+05	19 0.01	19
71ST ST 146+22 - 151+87	41 0.03	41
PROJECT TOTALS	92 0.1	92 2.1

EROSION CONTROL		
628.1905 MOBILIZATIONS EROSION CONTROL EACH	628.1910 MOBILIZATIONS EROSION CONTROL EACH	628.7015 INLET PROTECTION TYPE C EACH
LOCATION STATION TO STATION		
84TH ST 103+70 - 109+56	2	1
76TH ST 130+38 - 136+05	2	1
71ST ST 146+22 - 151+87	2	1
PROJECT TOTALS	6	3

TEMPORARY PEDESTRIAN ACCOMMODATIONS		
644.1430 TEMPORARY PEDESTRIAN SURFACE PLATE SF	644.1601 TEMPORARY PEDESTRIAN CURB RAMP DAY LF	644.1810 TEMPORARY PEDESTRIAN BARRICADE LF
LOCATION STATION TO STATION		
84TH ST 103+70 - 109+56	160 30	400
76TH ST 130+38 - 136+05	240 43	530
71ST ST 146+22 - 151+87	80 20	340
PROJECT TOTALS	480 93	1,270

Addendum No. 01
 ID 2110-00-73
 Revised Sheet 86
 April 2, 2021



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0100 Removing Concrete Pavement	121.000 SY	_____.	_____.
0004	204.0110 Removing Asphaltic Surface	94.000 SY	_____.	_____.
0006	204.0115 Removing Asphaltic Surface Butt Joints	134.000 SY	_____.	_____.
0008	204.0120 Removing Asphaltic Surface Milling	12,131.000 SY	_____.	_____.
0010	204.0130 Removing Curb	5.000 LF	_____.	_____.
0012	204.0150 Removing Curb & Gutter	737.000 LF	_____.	_____.
0014	204.0155 Removing Concrete Sidewalk	473.000 SY	_____.	_____.
0016	204.0195 Removing Concrete Bases	17.000 EACH	_____.	_____.
0018	204.9105.S Removing (item description) 01. Traffic Signals (W. Lincoln Ave & S. 84th St)	LS	LUMP SUM	_____.
0020	204.9105.S Removing (item description) 02. Traffic Signals (W. Lincoln Ave & S. 76th St)	LS	LUMP SUM	_____.
0022	204.9105.S Removing (item description) 03. Traffic Signals (W. Lincoln Ave & S. 71st St)	LS	LUMP SUM	_____.
0024	205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	10.000 TON	_____.	_____.
0026	211.0300 Prepare Foundation for Concrete Base (project) 01. 2110-00-73	LS	LUMP SUM	_____.
0028	213.0100 Finishing Roadway (project) 01. 2110-00-73	1.000 EACH	_____.	_____.
0030	305.0120 Base Aggregate Dense 1 1/4-Inch	218.000 TON	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	320.0145 Concrete Base 8-Inch	44.000 SY	_____.	_____.
0034	415.0100 Concrete Pavement 10-Inch	43.000 SY	_____.	_____.
0036	416.0170 Concrete Driveway 7-Inch	12.000 SY	_____.	_____.
0038	416.0610 Drilled Tie Bars	379.000 EACH	_____.	_____.
0040	416.0620 Drilled Dowel Bars	16.000 EACH	_____.	_____.
0042	455.0605 Tack Coat	865.000 GAL	_____.	_____.
0044	460.2000 Incentive Density HMA Pavement	910.000 DOL	1.00000	910.00
0046	460.6224 HMA Pavement 4 MT 58-28 S	1,415.000 TON	_____.	_____.
0048	465.0125 Asphaltic Surface Temporary	40.000 TON	_____.	_____.
0050	601.0331 Concrete Curb & Gutter 31-Inch	158.000 LF	_____.	_____.
0052	601.0600 Concrete Curb Pedestrian	127.000 LF	_____.	_____.
0054	602.0410 Concrete Sidewalk 5-Inch	2,557.000 SF	_____.	_____.
0056	602.0420 Concrete Sidewalk 7-Inch	1,350.000 SF	_____.	_____.
0058	602.0505 Curb Ramp Detectable Warning Field Yellow	120.000 SF	_____.	_____.
0060	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	90.000 SF	_____.	_____.
0062	611.0648 Inlet Covers Type R	7.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	619.1000 Mobilization	1.000 EACH	_____.	_____.
0066	621.0100 Landmark Reference Monuments	2.000 EACH	_____.	_____.
0068	625.0100 Topsoil	92.000 SY	_____.	_____.
0070	628.1905 Mobilizations Erosion Control	6.000 EACH	_____.	_____.
0072	628.1910 Mobilizations Emergency Erosion Control	3.000 EACH	_____.	_____.
0074	628.7015 Inlet Protection Type C	21.000 EACH	_____.	_____.
0076	629.0210 Fertilizer Type B	0.100 CWT	_____.	_____.
0078	631.0300 Sod Water	2.100 MGAL	_____.	_____.
0080	631.1000 Sod Lawn	92.000 SY	_____.	_____.
0082	637.2210 Signs Type II Reflective H	180.000 SF	_____.	_____.
0084	637.2215 Signs Type II Reflective H Folding	89.520 SF	_____.	_____.
0086	637.2230 Signs Type II Reflective F	9.000 SF	_____.	_____.
0088	638.2102 Moving Signs Type II	8.000 EACH	_____.	_____.
0090	638.2602 Removing Signs Type II	30.000 EACH	_____.	_____.
0092	638.3000 Removing Small Sign Supports	2.000 EACH	_____.	_____.
0096	643.0300 Traffic Control Drums	12,759.000 DAY	_____.	_____.
0098	643.0410 Traffic Control Barricades Type II	540.000 DAY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0100	643.0420 Traffic Control Barricades Type III	3,755.000 DAY	_____.	_____.
0102	643.0500 Traffic Control Flexible Tubular Marker Posts	658.000 EACH	_____.	_____.
0104	643.0600 Traffic Control Flexible Tubular Marker Bases	658.000 EACH	_____.	_____.
0106	643.0705 Traffic Control Warning Lights Type A	8,050.000 DAY	_____.	_____.
0108	643.0715 Traffic Control Warning Lights Type C	4,945.000 DAY	_____.	_____.
0110	643.0800 Traffic Control Arrow Boards	393.000 DAY	_____.	_____.
0112	643.0900 Traffic Control Signs	8,511.000 DAY	_____.	_____.
0114	643.0920 Traffic Control Covering Signs Type II	7.000 EACH	_____.	_____.
0116	643.1000 Traffic Control Signs Fixed Message	42.000 SF	_____.	_____.
0118	643.1050 Traffic Control Signs PCMS	10.000 DAY	_____.	_____.
0120	643.1070 Traffic Control Cones 42-Inch	768.000 DAY	_____.	_____.
0122	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0124	644.1430 Temporary Pedestrian Surface Plate	480.000 SF	_____.	_____.
0126	644.1601 Temporary Pedestrian Curb Ramp	93.000 DAY	_____.	_____.
0128	644.1810 Temporary Pedestrian Barricade	1,270.000 LF	_____.	_____.
0130	646.1050 Marking Line Grooved Permanent Tape 4-Inch	10,910.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0132	646.3050 Marking Line Grooved Permanent Tape 8-Inch	690.000 LF	_____.	_____.
0134	646.9000 Marking Removal Line 4-Inch	5,180.000 LF	_____.	_____.
0136	646.9200 Marking Removal Line Wide	105.000 LF	_____.	_____.
0138	649.0105 Temporary Marking Line Paint 4-Inch	5,700.000 LF	_____.	_____.
0140	649.0150 Temporary Marking Line Removable Tape 4-Inch	25,590.000 LF	_____.	_____.
0142	649.0205 Temporary Marking Line Paint 8-Inch	390.000 LF	_____.	_____.
0144	649.0250 Temporary Marking Line Removable Tape 8-Inch	921.000 LF	_____.	_____.
0146	649.0550 Temporary Marking Arrow Removable Tape	11.000 EACH	_____.	_____.
0148	649.0805 Temporary Marking Stop Line Paint 18-Inch	33.000 LF	_____.	_____.
0150	649.0850 Temporary Marking Stop Line Removable Tape 18-Inch	194.000 LF	_____.	_____.
0152	649.0960 Temporary Marking Removable Mask Out Tape 6-Inch	1,053.000 LF	_____.	_____.
0154	650.5000 Construction Staking Base	67.000 LF	_____.	_____.
0156	650.5500 Construction Staking Curb Gutter and Curb & Gutter	487.000 LF	_____.	_____.
0158	650.7000 Construction Staking Concrete Pavement	39.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0160	650.8000 Construction Staking Resurfacing Reference	1,718.000 LF	_____.	_____.
0162	650.8500 Construction Staking Electrical Installations (project) 01. 2110-00-73	LS	LUMP SUM	_____.
0164	650.9000 Construction Staking Curb Ramps	20.000 EACH	_____.	_____.
0166	650.9910 Construction Staking Supplemental Control (project) 01. 2110-00-73	LS	LUMP SUM	_____.
0168	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	299.000 LF	_____.	_____.
0170	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	186.000 LF	_____.	_____.
0172	652.0615 Conduit Special 3-Inch	1,870.000 LF	_____.	_____.
0174	653.0140 Pull Boxes Steel 24x42-Inch	18.000 EACH	_____.	_____.
0176	653.0905 Removing Pull Boxes	9.000 EACH	_____.	_____.
0178	654.0101 Concrete Bases Type 1	13.000 EACH	_____.	_____.
0180	654.0102 Concrete Bases Type 2	7.000 EACH	_____.	_____.
0182	654.0120 Concrete Bases Type 10-Special	6.000 EACH	_____.	_____.
0184	654.0205 Concrete Control Cabinet Bases Type 7	3.000 EACH	_____.	_____.
0186	655.0230 Cable Traffic Signal 5-14 AWG	1,862.000 LF	_____.	_____.
0188	655.0240 Cable Traffic Signal 7-14 AWG	939.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0190	655.0260 Cable Traffic Signal 12-14 AWG	3,036.000 LF	_____.	_____.
0192	655.0320 Cable Type UF 2-10 AWG Grounded	1,259.000 LF	_____.	_____.
0194	655.0515 Electrical Wire Traffic Signals 10 AWG	2,503.000 LF	_____.	_____.
0196	655.0610 Electrical Wire Lighting 12 AWG	1,566.000 LF	_____.	_____.
0198	656.0200 Electrical Service Meter Breaker Pedestal (location) 01. W. Lincoln Ave & S. 84th St	LS	LUMP SUM	_____.
0200	656.0200 Electrical Service Meter Breaker Pedestal (location) 02. W. Lincoln Ave & S. 76th St	LS	LUMP SUM	_____.
0202	656.0200 Electrical Service Meter Breaker Pedestal (location) 03. W. Lincoln Ave & S. 71st St	LS	LUMP SUM	_____.
0204	657.0100 Pedestal Bases	13.000 EACH	_____.	_____.
0206	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	7.000 EACH	_____.	_____.
0208	657.0310 Poles Type 3	7.000 EACH	_____.	_____.
0210	657.0352 Poles Type 10-Special	6.000 EACH	_____.	_____.
0212	657.0405 Traffic Signal Standards Aluminum 3.5-FT	2.000 EACH	_____.	_____.
0214	657.0420 Traffic Signal Standards Aluminum 13-FT	5.000 EACH	_____.	_____.
0216	657.0425 Traffic Signal Standards Aluminum 15-FT	6.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0218	657.0541 Monotube Arms 40-FT-Special	6.000 EACH	_____.	_____.
0220	657.0595 Trombone Arms 25-FT	4.000 EACH	_____.	_____.
0222	657.0609 Luminaire Arms Single Member 4-Inch Clamp 6-FT	7.000 EACH	_____.	_____.
0224	657.0815 Luminaire Arms Steel 15-FT	6.000 EACH	_____.	_____.
0226	658.0173 Traffic Signal Face 3S 12-Inch	36.000 EACH	_____.	_____.
0228	658.0174 Traffic Signal Face 4S 12-Inch	12.000 EACH	_____.	_____.
0230	658.0416 Pedestrian Signal Face 16-Inch	24.000 EACH	_____.	_____.
0232	658.0500 Pedestrian Push Buttons	24.000 EACH	_____.	_____.
0234	658.5069 Signal Mounting Hardware (location) 01. W. Lincoln Ave & S. 84th St	LS	LUMP SUM	_____.
0236	658.5069 Signal Mounting Hardware (location) 02. W. Lincoln Ave & S. 76th St	LS	LUMP SUM	_____.
0238	658.5069 Signal Mounting Hardware (location) 03. W. Lincoln Ave & S. 71st St	LS	LUMP SUM	_____.
0240	659.1125 Luminaires Utility LED C	12.000 EACH	_____.	_____.
0242	661.0200 Temporary Traffic Signals for Intersections (location) 01. W. Lincoln Ave & S. 84th St	LS	LUMP SUM	_____.
0244	661.0200 Temporary Traffic Signals for Intersections (location) 02. W. Lincoln Ave & S. 76th St	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0246	690.0150 Sawing Asphalt	770.000 LF	_____.	_____.
0248	690.0250 Sawing Concrete	785.000 LF	_____.	_____.
0250	715.0415 Incentive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0252	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,400.000 HRS	5.00000	7,000.00
0254	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	900.000 HRS	5.00000	4,500.00
0256	SPV.0060 Special 01. Removing Lighting Units	10.000 EACH	_____.	_____.
0258	SPV.0060 Special 02. Traffic Signal Controller & Cabinet	3.000 EACH	_____.	_____.
0260	SPV.0060 Special 03. Internal Sanitary Manhole Seal	7.000 EACH	_____.	_____.
0262	SPV.0060 Special 04. Adjust Sanitary Manhole Frame	2.000 EACH	_____.	_____.
0264	SPV.0060 Special 05. Building Sanitary Sewer Reconnect, 6-Inch	3.000 EACH	_____.	_____.
0266	SPV.0060 Special 06. Round Steel Sign Post System	5.000 EACH	_____.	_____.
0268	SPV.0060 Special 07. Adjust Water Valve Box	20.000 EACH	_____.	_____.
0270	SPV.0060 Special 08. Catch Basin Replacement	1.000 EACH	_____.	_____.
0272	SPV.0060 Special 09. Adjust Storm Manhole Frame	2.000 EACH	_____.	_____.
0274	SPV.0060 Special 10. Adjust Catch Basin Frame	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0276	SPV.0060 Special 11. Storm Manhole Frame With 8-Hole Lid	5.000 EACH	_____.	_____.
0278	SPV.0060 Special 12. Sanitary Manhole Frame With Solid Gasketed Lids	6.000 EACH	_____.	_____.
0280	SPV.0060 Special 13. Sanitary Structure Miscellaneous Inside Repair	3.000 EACH	_____.	_____.
0282	SPV.0060 Special 14. Storm Structure Miscellaneous Inside Repair	20.000 EACH	_____.	_____.
0284	SPV.0060 Special 15. Marking Grooved Preformed Thermoplastic Arrows Type 2	12.000 EACH	_____.	_____.
0286	SPV.0060 Special 16. Utility Line Opening	16.000 EACH	_____.	_____.
0288	SPV.0090 Special 01. Concrete Curb & Gutter 25-Inch	330.000 LF	_____.	_____.
0290	SPV.0090 Special 02. Sanitary Sewer Relay, SDR 35 PVC SP, 8-Inch	93.300 LF	_____.	_____.
0292	SPV.0090 Special 03. Marking Grooved Preformed Thermoplastic Stop Line 18-Inch	325.000 LF	_____.	_____.
0294	SPV.0090 Special 04. Marking Grooved Preformed Thermoplastic Crosswalk Block Style 24-Inch	936.000 LF	_____.	_____.
0296	SPV.0090 Special 05. Marking Diagonal Grooved Preformed Thermoplastic 12-Inch	465.000 LF	_____.	_____.
0298	SPV.0105 Special 01. Video Vehicle Detection System (W. Lincoln Ave & S. 84th St)	LS	LUMP SUM	_____.
0300	SPV.0105 Special 02. Video Vehicle Detection System (W. Lincoln Ave & S. 76th St)	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20210413007 Project(s): 2110-00-73

Federal ID(s): WISC 2021260

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0302	SPV.0105 Special 03. Video Vehicle Detection System (W. Lincoln Ave & S. 71st St)	LS	LUMP SUM	_____.
0304	SPV.0105 Special 04. Emergency Vehicle Preemption System (W. Lincoln Ave & S. 84th St)	LS	LUMP SUM	_____.
0306	SPV.0105 Special 05. Emergency Vehicle Preemption System (W. Lincoln Ave & S. 76th St)	LS	LUMP SUM	_____.
0308	SPV.0105 Special 06. Emergency Vehicle Preemption System (W. Lincoln Ave & S. 71st St)	LS	LUMP SUM	_____.
0310	SPV.0200 Special 01. Rebuild Sanitary Manhole	3.000 VF	_____.	_____.
0312	SPV.0200 Special 02. Sanitary Manhole, 48 Inch Diameter	38.000 VF	_____.	_____.
0314	SPV.0200 Special 03. Storm Manhole, 48-Inch Diameter	6.000 VF	_____.	_____.
0316	SPV.0200 Special 04. Storm Manhole, 42-Inch Diameter	13.000 VF	_____.	_____.
0318	SPV.0200 Special 05. Rebuild Storm Structure	4.000 VF	_____.	_____.
0320	SPV.0060 Special 17. Field Facilities Office Space	1.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

