



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

April 7, 2021

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #11: 1146-75-71, WISC 2021264**  
**STH 76 – New London**  
**WI Central Railroad – CTH JJ**  
**STH 15**  
**Outagamie County**

### Letting of April 13, 2021

This is Addendum No. 02, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
9	Railroad Insurance and Coordination – Wisconsin Central Ltd (CN)
27	Select Borrow

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
205.0100	Common Excavation	CY	810,462	-21,669	788,793
208.1100	Select Borrow	CY	101,427	-34,670	66,757
311.0110	Breaker Run	Ton	104,262	13,000	117,262
415.0410	Concrete Pavement Approach Slab	SY	336	540	876
SPV.0035.02	Roadway Embankment	CY	1,234,486	9,935	1,244,421

**Plan Sheets:**

<b>Revised Plan Sheets</b>	
<b>Plan Sheet</b>	<b>Plan Sheet Title (brief description of changes to sheet)</b>
73	Miscellaneous Quantities. Updated the Select Borrow and Breaker Run quantities
75	Miscellaneous Quantities. Updated Concrete Approach Slab quantities
80	Miscellaneous Quantities. Updated Earthwork table
439	Earthwork Summary: Updated summary listing

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 02**

**1146-75-71**

**April 7, 2021**

**Special Provisions**

**3. Prosecution and Progress**

*Insert the following after paragraph three:*

The contract time for completion is based on an expedited work schedule and may require extraordinary forces and equipment. An expedited schedule is anticipated for the Black Otter Creek Restoration which may also include any work necessary to access this area. The proposed schedule of operations indicates that a large force and adequate equipment will be needed to assure that the work will be completed within the established contract time.

*Replace the 1<sup>st</sup> two paragraphs under section titled Interim Completions with the following:*

Complete topsoil placement and final restoration from Station 339+00 to Station 341+00 prior to October 29, 2021.

If the contractor fails to complete all topsoil placement and the final restoration from Station 339+00 – Station 341+00 prior to October 29, 2021, the department will assess the contractor \$1,000 per calendar day in damages for each calendar day that this work remains incomplete after 12:01 AM, October 29, 2021. An entire calendar day will be charged for any period of time within a calendar day that the work remains incomplete beyond 12:01 AM

**9. Railroad Insurance and Coordination – Wisconsin Central Ltd (CN)**

*Delete the following under section titled C.4 Excluded Conditions:*

2. Temporary Construction crossings arranged by the contractor.

**27. Select Borrow**

*Add the following to the end of the article:*

*Delete Standard Spec 208.4.2 and 208.4.3*

The department will measure select borrow in the final position according to standard spec 208.4.4

**Schedule of Items**

Attached, dated April 7, 2021, are the revised Schedule of Items Pages 2, 3, and 15.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 73, 75, 80, and 439.

END OF ADDENDUM

Addendum No. 02  
 ID 1146-75-11  
 Revised Sheet 73  
 April 7, 2021

ALL ITEMS ARE CATEGORY 0010  
 UNLESS OTHERWISE NOTED

Station to Station	Location	208.1100 Select Borrow CY	305.0110 Base Aggregate Dense 3/4-inch Ton	305.0120* Base Aggregate Dense 1 1/4-inch Ton	311.0110* Breaker Run Ton	Base		624.0100 Water Mgal	Dust Control Mgal	2-inch Clear Stone Ton	SPV.0195.01 2-inch Clear Stone Ton	SPV.0195.02 Shot Rock Ton	Remarks	
						312.0110 Select Crush Material Ton	312.0110 Material Ton							
275+00 -- 278+88	STH 15 EB			1,787			2,744	18	7					
275+00 -- 277+07	STH 15 WB			1,423			2,206	14	6					
319+16 -- 321+43	STH 15 EB + WB			284			387	3	1				Median Cross over Driveway Driveway	
320+19 -- --	STH 15 WB		216											
335+00 -- --	STH 15 WB		20											
281+02 -- 339+40	STH 15 EB			10,818			15,894	108	43					
328+00 -- 362+00	STH 15 EB + WB	47,757			88,148								Marsh Excavation Shot Rock for Paritka Pond 2 driveways Median Crossover	
279+86 -- 339+05	STH 15 WB			10,968	16,114			271	108					
346+60 -- --	STH 15 EB + WB		185											
345+46 -- 347+74	STH 15 EB + WB			284			387	3	1					
340+80 -- 372+99	STH 15 EB			5,965			8,764	60	24					
340+46 -- 372+95	STH 15 WB			6,022			8,847	60	24					
373+92 -- 388+64	STH 15 EB			2,727			4,007	27	11					
373+87 -- 388+69	STH 15 WB			2,746			4,034	27	11					
408+54 -- 410+82	STH 15 EB + WB			284			387	3	1				Median Crossover	
434+00 -- --	STH 15 WB		72										Driveway	
446+86 -- 449+14	STH 15 EB + WB			284			387	3	1				Snowmobile Crossover	
429+50 -- 431+50	STH 15 EB + WB	8,000											Marsh Excavation	
450+00 -- 458+00	STH 15 EB + WB	11,000			13,000								Marsh Excavation	
448+00 -- --	STH 15 EB + WB		140				20,540	140	56				2 driveways	
389+56 -- 465+00	STH 15 EB			13,981			20,527	140	56					
389+51 -- 465+00	STH 15 WB			13,972										
23+15 -- 26+26	CTH M			1,180				12	5					
11+30 -- 12+62	N. Crest		19											
12+10 -- --	N. Crest		90										Cul-de-sac 2 driveways	
11+00 -- 26+77	CTH MM			3,280				33	13					
15+27 -- --	CTH MM		78										2 driveways	
25+69 -- --	CTH MM		19										Driveway	
20+00 -- 24+93	Samb's Driveway		370				650							
1+50 -- 4+60	Black Otter Creek													
Total		66,757	1,209	76,021	117,262	Subtotal	89,761	921	368	151	16,230			
											*SEE STRUCTURES FOR ADDITIONAL QUANTITIES			

Addendum No. 02  
 ID 1146-75-71  
 Revised Sheet 75  
 April 7, 2021

ALL ITEMS ARE CATEGORY 0010  
 UNLESS OTHERWISE NOTED

CONCRETE SUMMARY

Station	to	Station	Location	Concrete Pavement Approach Slab S.Y.	Concrete Collar For Pipes Each	Concrete Sidewalk 4-Inch S.F.	Concrete Masonry Eco-Passage C.Y.	Steel Grating S.F.	Remarks
4:15.0410									
278+88	--	--	STH 15 EB	116					B-44-289
277+07	--	--	STH 15 WB	116					B-44-290
281+02	--	--	STH 15 EB	116					B-44-289
279+87	--	--	STH 15 WB	116					B-44-290
309+00	--	--	STH 15 EB				12.9	144	
373+00	--	--	STH 15 EB	64					B-44-291
372+95	--	--	STH 15 WB	64					B-44-292
373+93	--	--	STH 15 EB	64					B-44-291
373+87	--	--	STH 15 WB	64					B-44-292
388+64	--	--	STH 15 EB	39					B-44-293
388+69	--	--	STH 15 WB	39					B-44-294
389+57	--	--	STH 15 EB	39					B-44-293
389+61	--	--	STH 15 WB	39					B-44-294
18+89	--	23+15	CTH M						
107+75	--	108+00	Nash St.		1	200			Replace Temp Asphaltic Surface
111+88	--	112+13	Nash St.		2	125			Replace Temp Asphaltic Surface
Total				876	3	325	12.9	144	

Asphalt Summary

Station	to	Station	Location	Removing Asphaltic Surface Milling SY	Tack Coat GAL	HMA Pavement 3 LT 58-28 S TON	HMA Pavement 4 LT 58-28 S TON	Asphaltic Surface Patching TON	Asphaltic Surface Driveway and Field Entrances TON	Remarks
11+00	--	26+77	CTH MM	204.0120	262.83	455.0605	460.5223	465.0110	465.0120	
25+70	--	--	CTH MM		1.00		460.5224			
23+14	--	28+55	CTH M	1,561.22	199.45	127.13	285.88		13.00	20' PE Wagner Dwy Includes Intersection
107+00	--	113+00	Nash St.	2,003.78	143.64	240.00		14.70		
11+30	--	12+62	N. Crest		49.01	127.13	98.88			
Total				3,565	656	934	1,154	15	13	

Addendum No. 02  
ID 1146-75-11  
Revised Sheet 80  
April 7, 2021

3

ALL ITEMS ARE CATEGORY 0010  
UNLESS OTHERWISE NOTED

Location	From/To Station	205.0100 Excavation Common, CY		Available Material, CY (5)	205.0400 Excavation Marsh, CY (6)	205.0200 Excavation Rock, CY (7)	Fill	Mass Ordinate +/- (8)	SPV.0035.02 Roadway Embankment, CY (4)	Remarks:
		Cut, CY (2)	EBS Ex., CY (3)							
TEMPORARY RAMP	273+61/275+00	1	0	1	0	0	9,935	-9,934	9,935	
STA 275+00 to WCL RR	275+00/279+00	93	0	93	0	0	48,335	-48,242	48,335	
WCL RR to BLACK OTTER CREEK	279+00/340+00	8,576	0	8,576	35,410	0	584,991	-541,004	584,991	
BLACK OTTER CREEK to CTH M	340+00/373+50	1,776	0	1,776	58,771	0	217,781	-157,235	217,781	
CTH M to NASH ST.	373+50/389+00	39,349	0	39,349	0	25,373	59,473	-20,123	59,473	
CTH M	18+62.78/28+55.78	1,355	0	1,355	0	0	400	955	400	
N. CREST ST.	11+30/12+52.02	534	0	534	0	0	125	409	125	
CTH MM	10+15/26+76.55	9,258	0	9,258	0	180	337	8,921	337	
NASH ST. to STH 15 STA 465+00	389+00/465+00	727,849	0	727,849	33,454	0	323,043	438,260	323,043	
Totals, CY		788,793	0	788,793	127,635	25,553	1,244,421	-327,993	1,244,421	
Grand Total, CY		788,793	0	788,793	127,635	25,553	1,244,421	-327,993	1,244,421	

Notes:

- (1) Common Excavation is the sum of the Cut and EBS Excavation columns.
- (2) Salvaged/Unusable Pavement Material is included in Cut
- (3) EBS Excavation to be backfilled with Select Borrow material.
- (4) Roadway Embankment does not include material used to fill Marsh Excavation
- (5) Available Material = Cut - Salvaged/Unusable Pavement Material
- (6) See construction detail for limits of excavation and disposal.
- (7) Excavation Rock not included in Cut
- (8) The Mass Ordinate is for informational purposes only as common excavation and roadway embankment are not balanced for quantity purposes and does not guarantee the quality of common excavation, or if it can be reused on site. EBS and Marsh Excavation NOT included in Mass Ordinate determination.

3

PROJECT NO: 1146-75-11

HWY: STH 15

COUNTY: OUTAGAMIE

MISCELLANEOUS QUANTITIES

SHEET: 80

E

FILE NAME: N:\PDS\1030200\_mq.ppk

PLOT DATE: June 14, 1911

PLOT NAME:

PLOT SCALE: 1:1

Addendum No. 02  
 ID 1146-75-71  
 Revised Sheet 439  
 April 7, 2021

NASH ST. - STH 15 STA 465+00

AL 15eb bypass

STATION	Real Station	Distance	AREA (SF)			Incremental Vol (CY) (Unadjusted)										
			Cut	Salvaged/Unusable Pavement Material	Fill	Marsh Exc	Rock Exc	EBS	Salvaged/Unusable Pavement Material	Fill	Marsh Exc	Rock Exc	EBS			
426+50	42650.00	50.00	2500.76	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
427+00	42700.00	50.00	725.62	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
427+50	42750.00	50.00	128.88	0.00	0.00	284.11	0.00	0.00	0.00	0.00	0.00	270	0	0	0	0
428+00	42800.00	50.00	65.54	0.00	0.00	988.10	0.00	0.00	0.00	0.00	0.00	1,178	0	0	0	0
428+50	42850.00	50.00	50.86	0.00	0.00	1522.78	0.00	0.00	0.00	0.00	0.00	2,325	0	0	0	0
429+00	42900.00	50.00	49.80	0.00	0.00	1978.46	0.00	0.00	0.00	0.00	0.00	3,242	0	0	0	0
429+50	42950.00	50.00	43.40	0.00	0.00	2391.98	728.00	0.00	0.00	0.00	0.00	4,047	674	0	0	0
430+00	43000.00	50.00	12.19	0.00	0.00	3000.01	1458.00	0.00	0.00	0.00	0.00	4,983	2,024	0	0	0
430+50	43050.00	50.00	5.40	0.00	0.00	3681.98	1415.00	0.00	0.00	0.00	0.00	6,187	2,660	0	0	0
431+00	43100.00	50.00	70.32	0.00	0.00	3529.96	1068.00	0.00	0.00	0.00	0.00	6,678	2,299	0	0	0
431+50	43150.00	50.00	68.48	0.00	0.00	2641.61	1076.00	0.00	0.00	0.00	0.00	5,714	1,985	0	0	0
432+00	43200.00	50.00	167.47	0.00	0.00	2236.67	694.00	0.00	0.00	0.00	0.00	4,517	1,639	0	0	0
432+50	43250.00	50.00	303.01	0.00	0.00	1348.35	0.00	0.00	0.00	0.00	0.00	3,319	643	0	0	0
433+00	43300.00	50.00	308.31	0.00	0.00	563.15	0.00	0.00	0.00	0.00	0.00	1,770	0	0	0	0
433+50	43350.00	50.00	362.69	0.00	0.00	251.05	0.00	0.00	0.00	0.00	0.00	754	0	0	0	0
434+00	43400.00	50.00	304.05	0.00	0.00	219.24	0.00	0.00	0.00	0.00	0.00	435	0	0	0	0
434+50	43450.00	50.00	277.91	0.00	0.00	284.92	0.00	0.00	0.00	0.00	0.00	467	0	0	0	0
435+00	43500.00	50.00	243.36	0.00	0.00	272.46	0.00	0.00	0.00	0.00	0.00	516	0	0	0	0
435+50	43550.00	50.00	366.35	0.00	0.00	117.01	0.00	0.00	0.00	0.00	0.00	361	0	0	0	0
436+00	43600.00	50.00	1111.09	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	108	0	0	0	0
436+50	43650.00	50.00	2498.27	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
437+00	43700.00	50.00	3055.97	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
437+50	43750.00	50.00	3235.75	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
438+00	43800.00	50.00	3460.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
438+50	43850.00	50.00	3704.86	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
439+00	43900.00	50.00	4244.98	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
439+50	43950.00	50.00	4626.20	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
440+00	44000.00	50.00	4939.47	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
440+50	44050.00	50.00	5162.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
441+00	44100.00	50.00	5375.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
441+50	44150.00	50.00	5299.35	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
442+00	44200.00	50.00	4721.68	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
442+50	44250.00	50.00	4585.21	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
443+00	44300.00	50.00	4331.42	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
443+50	44350.00	50.00	3799.89	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
444+00	44400.00	50.00	3415.77	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
444+50	44450.00	50.00	3231.60	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0
445+00	44500.00	50.00		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0



Proposal Schedule of Items

Proposal ID: 20210413011 Project(s): 1146-75-71  
Federal ID(s): WISC 2021264

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0036	205.0100 Excavation Common	788,793.000 CY	_____.	_____.
0038	205.0200 Excavation Rock	25,553.000 CY	_____.	_____.
0040	205.0400 Excavation Marsh	127,635.000 CY	_____.	_____.
0042	206.1000 Excavation for Structures Bridges (structure) 01. B-44-289	LS	LUMP SUM	_____.
0044	206.1000 Excavation for Structures Bridges (structure) 02. B-44-290	LS	LUMP SUM	_____.
0046	206.1000 Excavation for Structures Bridges (structure) 03. B-44-291	LS	LUMP SUM	_____.
0048	206.1000 Excavation for Structures Bridges (structure) 04. B-44-292	LS	LUMP SUM	_____.
0050	206.1000 Excavation for Structures Bridges (structure) 05. B-44-293	LS	LUMP SUM	_____.
0052	206.1000 Excavation for Structures Bridges (structure) 06. B-44-294	LS	LUMP SUM	_____.
0054	206.1000 Excavation for Structures Bridges (structure) 07. B-44-295	LS	LUMP SUM	_____.
0056	206.1000 Excavation for Structures Bridges (structure) 08. B-44-296	LS	LUMP SUM	_____.
0058	206.5000 Cofferdams (structure) 02. B-44-290	LS	LUMP SUM	_____.
0060	206.5000 Cofferdams (structure) 03. B-44-289	LS	LUMP SUM	_____.
0062	208.1100 Select Borrow	66,757.000 CY	_____.	_____.
0064	210.1500 Backfill Structure Type A	3,283.000 TON	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20210413011 Project(s): 1146-75-71

Federal ID(s): WISC 2021264

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	211.0100 Prepare Foundation for Asphaltic Paving (project) 31. 1146-75-71	LS	LUMP SUM	_____.
0068	213.0100 Finishing Roadway (project) 01. 1146-75-71	1.000 EACH	_____.	_____.
0070	214.0100 Obliterating Old Road	9.300 STA	_____.	_____.
0072	305.0110 Base Aggregate Dense 3/4-Inch	1,209.000 TON	_____.	_____.
0074	305.0120 Base Aggregate Dense 1 1/4-Inch	77,600.000 TON	_____.	_____.
0076	305.0500 Shaping Shoulders	11.200 STA	_____.	_____.
0078	311.0110 Breaker Run	117,262.000 TON	_____.	_____.
0080	312.0110 Select Crushed Material	89,761.000 TON	_____.	_____.
0082	415.0410 Concrete Pavement Approach Slab	876.000 SY	_____.	_____.
0084	416.1010 Concrete Surface Drains	5.400 CY	_____.	_____.
0086	455.0605 Tack Coat	656.000 GAL	_____.	_____.
0088	460.2000 Incentive Density HMA Pavement	1,090.000 DOL	1.00000	1,090.00
0090	460.5223 HMA Pavement 3 LT 58-28 S	934.000 TON	_____.	_____.
0092	460.5224 HMA Pavement 4 LT 58-28 S	1,154.000 TON	_____.	_____.
0094	465.0110 Asphaltic Surface Patching	15.000 TON	_____.	_____.
0096	465.0120 Asphaltic Surface Driveways and Field Entrances	13.000 TON	_____.	_____.



## Proposal Schedule of Items

Proposal ID: 20210413011 Project(s): 1146-75-71

Federal ID(s): WISC 2021264

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0420	740.0440 Incentive IRI Ride	1,240.000 DOL	1.00000	1,240.00
0422	801.0117 Railroad Flagging Reimbursement	117,000.000 DOL	1.00000	117,000.00
0424	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,100.000 HRS	5.00000	10,500.00
0426	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	5,760.000 HRS	5.00000	28,800.00
0428	SPV.0035 Special 01. Concrete Masonry Eco-Passage	12.900 CY	_____	_____
0430	SPV.0035 Special 02. Roadway Embankment	1,244,421.000 CY	_____	_____
0432	SPV.0060 Special 01. Temporary Slope Drain	8.000 EACH	_____	_____
0434	SPV.0060 Special 02. Wood Gates Double Leaf 20-Foot	2.000 EACH	_____	_____
0436	SPV.0075 Special 01. Street Sweeping	16.000 HRS	_____	_____
0438	SPV.0090 Special 01. Fence Chain Link 5 - FT Special	6,294.000 LF	_____	_____
0440	SPV.0090 Special 02. Pedestrian Overhead Protection	400.000 LF	_____	_____
0442	SPV.0105 Special 01. Reconnect Pipe Underdrain Parcel 165	LS	LUMP SUM	_____
0444	SPV.0165 Special 01. Steel Grating	144.000 SF	_____	_____
0446	SPV.0165 Special 02. Wall Concrete Panel Mechanically Stabilized Earth LRFD/ QMP R-44-17	10,510.000 SF	_____	_____