



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

April 21, 2021

NOTICE TO ALL CONTRACTORS:

Proposal #11: 2030-15-70
N Lovers Lane Road,
Bridge Over UP RR B-40-435
Loc Str
Milwaukee County

Letting of May 11, 2021

This is Addendum No. 01, which provides the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0500	Traffic Control Flexible Marker Posts	EACH	1806	-1763	43
643.0600	Traffic Control Flexible Marker Bases	EACH	1806	-1763	43

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
23	MISCELLANEOUS QUANTITIES (Quantities for Items 643.0500 & 643.0600 revised)

Schedule of Items

Attached, dated April 22, 2021, are the revised Schedule of Items Page 4.

Plan Sheets

The following 8½ x 11-inch sheet is attached and made part of the plans for this proposal:
Revised page #23

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

TRAFFIC CONTROL ITEMS REQUIRED (CATEGORY 0010)		STAGE 1	STAGE 2	STAGE 3	TOTAL	ITEMS	STAGE 1	STAGE 2	STAGE 3	SIZE
ITEM #	DESCRIPTION	(Each) * (Days)	(Each) * (Days)	(Each) * (Days)						
643.0300	TRAFFIC CONTROL DRUMS	18 42	18 42	34 71	3,926	W20-1-A	3	2	2	48"X48"
643.0420	TRAFFIC CONTROL BARRICADES TYPE III	8 42	7 42	12 71	1,482	W24-1L	1	1	-	48"X48"
643.0500	TRAFFIC CONTROL FLEXIBLE TUBULAR MARKER POSTS	22	21	0	43	W24-1R	1	1	2	48"X48"
643.0600	TRAFFIC CONTROL FLEXIBLE TUBULAR MARKER BASES	22	21	0	43	R011-2-L	1	1	2	48"X30"
643.0705	TRAFFIC CONTROL WARNING LIGHTS TYPE A	16 42	14 42	24 71	2,964	W01-6-L	1	1	-	24"X48"
643.0715	TRAFFIC CONTROL WARNING LIGHTS TYPE C	18 42	18 42	34 71	3,926	G20-2-A	2	2	2	36"X18"
643.0900	TRAFFIC CONTROL SIGNS	9 42	8 42	16 71	1,850	W1-6-R	-	-	2	24"X48"
643.1050	TRAFFIC CONTROL SIGNS PCMS	2 7	2 7	2 7	42	W012-1L	-	-	2	24"X24"
						W05-52R	-	-	2	12"X36"
						W05-52L	-	-	2	12"X36"
						TOTAL	9	8	16	

Addendum No. 01
ID 2030-15-70
Revised Sheet 23
April 22, 2021

NOTES:

- # ALL DRUMS HAVE ONE STEADY BURNING YELLOW LIGHT (LIGHTS ARE TO BE PAID FOR SEPERATLY UNDER THEIR APPROPRIATE BID ITEM)
- ## ALL TYPE III BARRICADES HAVE TWO (2) FLASHING YELLOW LIGHTS (LIGHTS ARE TO BE PAID FOR SEPERATLY UNDER THEIR APPROPRIATE BID ITEM)
- ### WHEN PLACING TEMPORARY PAVEMENT MARKING REMOVABLE TAPE, THE TAPE SHALL BE SLICED OR CUT ACROSS IT'S WIDTH EVERY TWENTY FIVE (25) FEET
- #### ALL TEMPORARY PAVEMENT MARKINGS MUST BE REMOVED PRIOR TO FINAL ACCEPTANCE OF PROJECT



Proposal Schedule of Items

Proposal ID: 20210511011 Project(s): 2030-15-70

Federal ID(s): N/A

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0098	643.0500 Traffic Control Flexible Tubular Marker Posts	43.000 EACH	_____.	_____.
0100	643.0600 Traffic Control Flexible Tubular Marker Bases	43.000 EACH	_____.	_____.
0102	643.0705 Traffic Control Warning Lights Type A	2,964.000 DAY	_____.	_____.
0104	643.0715 Traffic Control Warning Lights Type C	3,926.000 DAY	_____.	_____.
0106	643.0900 Traffic Control Signs	1,850.000 DAY	_____.	_____.
0108	643.1050 Traffic Control Signs PCMS	42.000 DAY	_____.	_____.
0110	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0112	646.1020 Marking Line Epoxy 4-Inch	3,339.000 LF	_____.	_____.
0114	649.0150 Temporary Marking Line Removable Tape 4-Inch	4,652.000 LF	_____.	_____.
0116	650.6500 Construction Staking Structure Layout (structure) 001. P-40-589	LS	LUMP SUM	_____.
0118	650.9910 Construction Staking Supplemental Control (project) 001. 2030-15-70	LS	LUMP SUM	_____.
0120	690.0150 Sawing Asphalt	60.000 LF	_____.	_____.
0122	690.0250 Sawing Concrete	100.000 LF	_____.	_____.
0124	715.0415 Incentive Strength Concrete Pavement	1,374.000 DOL	1.00000	1,374.00
0126	715.0502 Incentive Strength Concrete Structures	1,746.000 DOL	1.00000	1,746.00

