



# Wisconsin Department of Transportation

April 29, 2021

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #38: 1530-05-72, WISC 2021362**  
**Ellsworth - Durand**  
**CTH A to East County Line**  
**USH 10**  
**Pierce County**

### Letting of May 11, 2021

This is Addendum No. 01, which provides for the following:

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
305.0110	Base Aggregate Dense ¾-Inch	Ton	1,120	520	1,640

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
614.0397	Guardrail Mow Strip Emulsified Asphalt	SY	0	4,070	4,070
625.0100	Topsoil	SY	0	3,150	3,150

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
614.0396	Guardrail Mow Strip Asphalt	SY	4,070	-4,070	0

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
62	Miscellaneous Quantities (Updated quantity)
64	Miscellaneous Quantities (Updated quantity)
66	Miscellaneous Quantities (Updated quantity)

**Schedule of Items**

Attached, dated April 29, 2021, are the revised Schedule of Items Pages 1 - 9.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 62, 64, and 66.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM



Addendum No. 01  
ID 1530-05-72  
Revised Sheet 64  
April 29, 2021

CONCRETE BARRIER TEMPORARY PRECAST

LOCATION	STATION - STATION	ANCHORING CONCRETE BARRIERS TEMPORARY PRECAST DELIVERED INSTALLED (LF)	CONCRETE BARRIER DELIVERED INSTALLED (LF)	NOTE
603.8500	603.8000	603.8125		
<b>1530-05-72 PROJECT TOTALS</b>				
		300	1,400	2,800

BEAM GUARD

LOCATION	STATION - STATION	OS	3 K (LF)	MCS GUARDBALL SHORT RADIUS (EACH)	TRANSITION (LF)	MCS THREE BEAM (EACH)	NOTE
614.2300	614.2330	614.2810	614.2830	614.2800			
<b>1530-05-72 PROJECT TOTALS</b>							
		10,378.1	13,137.50	487.5	5	240	

TEMPORARY SHORING

LOCATION	STATION - STATION	TEMPORARY SHORING (SFT)	NOTE
511.1100			
<b>PROJECT 1530-05-72 CATEGORY 0010</b>			
546	546		CULVERT REPLACEMENT
656	656		CULVERT REPLACEMENT
774	774		CULVERT REPLACEMENT
<b>1530-05-72 PROJECT TOTALS</b>			
		1,976	

MOW STRIPS

LOCATION	STATION - STATION	OFFSET (SY)	NOTE
<b>PROJECT 1530-05-72 CATEGORY 0010</b>			
8*00	8*00	10+47	614.0397
8*09	8*09	11+60	QUADRANT
33+13	33+13	34+70	MOW STRIP
35+32	35+32	36+89	EMULSIFIED ASPHALT
35+32	35+32	36+89	61
35+32	35+32	36+86	61
55+99	55+99	56+96	170
77+46	77+46	80+80	143
184+31	184+31	184+31	230
184+31	184+31	184+31	230
184+31	184+31	184+31	175
286+32	286+32	284+55	324
286+88	286+88	292+31	216
312+20	312+20	317+55	215
313+45	313+45	318+80	215
375+21	375+21	377+75	591
406+65	406+65	415+10	189
463+48	463+48	470+46	100
463+48	463+48	470+46	100
436+73	436+73	437+20	47
521+88	521+88	522+33	44
522+57	522+57	525+73	157
544+58	544+58	550+93	258
0+40'S	0+40'S	1+67'S	55
<b>PROJECT 1530-05-72 TOTALS</b>			
		4,070	

**LANDSCAPING**

PROJECT 1530-05-72 CATEGORY 0010	LOCATION	STATION-STATION	TOPSOIL (SY)	MULCHING (SY)	SOIL STABILIZER (ACRE)	FERTILIZER TYPE-A (CWT)	SEEDING MIXTURE NO.20 (LB)	SEEDING MIXTURE NO.30 (LB)	SEED WATER (MGAL)
	S.O.P.-320TH ST	7+96	13+46	-	-	1.1	31	13	36
	S.O.P.-320TH ST	32+07	37+96	-	-	1.5	36	28	53
	S.O.P.-320TH ST	46+00	73+61	-	0.4	2.7	101	15	96
	S.O.P.-320TH ST	76+02	83+36	-	0.1	0.6	20	17	21
	S.O.P.-320TH ST	87+88	91+70	-	0.1	0.6	20	17	21
	320TH ST - CTHCC	182+31	191+23	-	0.3	3.1	108	23	108
	CTH CC - QUARRY RD	229+15	229+45	-	-	0.2	4	2	4
	CTH CC - QUARRY RD	251+15	251+40	-	0.2	5	1	5	5
	CTH CC - QUARRY RD	284+88	296+13	-	0.6	3.8	138	24	134
	CTH CC - QUARRY RD	311+20	319+25	-	0.4	2.2	72	20	76
	QUARRY RD - 280TH AVE	344+30	399+16	-	0.6	5.4	197	34	192
	QUARRY RD - 280TH AVE	405+20	419+25	-	-	1.9	62	77	65
	280TH AVE - EOP	544+30	552+37	-	0.3	1.5	50	10	44
	280TH AVE - EOP	544+30	552+37	-	0.3	1.5	50	10	44
	SUBTOTAL		50.986	-	4.7	37.7	1,359	236	1,320
	UNDISTRIBUTED		3.150	1,604	2,500	2.8	97	341	64
	<b>1530-05-72 PROJECT TOTALS</b>		<b>3,150</b>	<b>2,500</b>	<b>7.5</b>	<b>48.0</b>	<b>1,700</b>	<b>300</b>	<b>1,650</b>

**EROSION CONTROL SLOPES AND DITCHES**

PROJECT 1530-05-72 CATEGORY 0010	LOCATION	STATION-STATION	SILT FENCE MAINTENANCE (LF)	EROSION MAT CLASS I TYPE B (SY)	EROSION MAT CLASS III TYPE D (SY)	TEMPORARY DITCH CHECKS (LF)	TRACKING PADS (EACH)
	S.O.P.-320TH ST	7+96	13+42	630	503	-	2
	S.O.P.-320TH ST	32+07	37+96	1,318	-	-	4
	S.O.P.-320TH ST	46+00	73+21	1,824	1,902	310	2
	S.O.P.-320TH ST	76+02	83+36	244	251	340	2
	S.O.P.-320TH ST	87+88	91+70	636	102	80	2
	320TH ST - CTHCC	182+31	191+23	2,930	1,047	190	2
	CTH CC - QUARRY RD	229+15	229+45	131	-	-	2
	CTH CC - QUARRY RD	251+15	251+40	170	-	-	2
	CTH CC - QUARRY RD	284+88	296+13	2,109	2,560	140	2
	CTH CC - QUARRY RD	311+20	319+25	486	270	80	2
	QUARRY RD - 280TH AVE	344+30	399+16	2,862	4,463	330	4
	QUARRY RD - 280TH AVE	405+20	419+25	2,277	815	-	1
	280TH AVE - EOP	544+30	552+37	4,847	9,891	310	7
	280TH AVE - EOP	544+30	552+37	266	788	984	2
	SUBTOTAL		15,291	45,873	1,821	20,400	1,780
	UNDISTRIBUTED		3,909	11,527	7,019	5,100	470
	<b>1530-05-72 PROJECT TOTALS</b>		<b>19,200</b>	<b>57,400</b>	<b>2,300</b>	<b>25,500</b>	<b>2,250</b>

**TEMPORARY PAVEMENT MARKING**

PROJECT 1530-05-72 CATEGORY 0010	LOCATION	STATION-STATION	MARKING REMOVAL 4-INCH LINE (LF)	TEMPORARY MARKING LINE PAINT (LF)	TEMPORARY MARKING STOP LINE (LF)	TEMPORARY MARKING STOP LINE REMOVABLE TAPE 4-INCH (LF)	TEMPORARY MARKING STOP LINE REMOVABLE TAPE 18-INCH (LF)
	S.O.P.-320TH ST	7+96 - STA. 118+00	-	8,206	-	-	-
	S.O.P.-320TH ST	32+07 - STA. 213+00	-	7,125	-	-	-
	CTH CC - QUARRY RD	229+15 - STA. 328+00	5,500	8,475	4,600	8,400	144
	QUARRY RD - 280TH AVE	344+30 - STA. 437+00	1,900	10,424	1,800	2,800	48
	UNDISTRIBUTED		400	2,182	350	600	8
	<b>1530-05-72 PROJECT TOTALS</b>		<b>7,800</b>	<b>44,400</b>	<b>8,750</b>	<b>11,200</b>	<b>200</b>

**TRAFFIC CONTROL**

PROJECT 1530-05-72 CATEGORY 0010	LOCATION	# OF DAYS	DRUMS (DAYS)	BARRICADES TYPE II (DAYS)	TRAFFIC CONTROL WARNING LIGHTS TYPE A (DAYS)	SIGNS TYPE A (DAYS)
	USH 10	120	70,080	-	-	8,940
	CULVERT REPLACEMENT STA 229+31	7	-	7	14	140
	CULVERT REPLACEMENT STA 251+29	7	-	7	14	140
	CULVERT REPLACEMENT STA 315+44	7	-	7	14	140
	CULVERT REPLACEMENT STA 549+39	7	-	7	14	140
	UNDISTRIBUTED		7,020	2	4	860
	<b>CATEGORY 0010 TOTALS</b>		<b>77,100</b>	<b>30</b>	<b>60</b>	<b>9,460</b>
	PARK & RIDE	19	-	95	180	19
	UNDISTRIBUTED		0	10	20	1
	<b>CATEGORY 0020 TOTALS</b>		<b>0</b>	<b>105</b>	<b>210</b>	<b>20</b>
	<b>1530-05-72 PROJECT TOTALS</b>		<b>77,100</b>	<b>135</b>	<b>270</b>	<b>9,480</b>

**MOVING SIGNS**

PROJECT 1530-05-72 CATEGORY 0010	LOCATION	MOVING SIGNS TYPE - SMALL SIGN SUPPORTS (EACH)
	638.2102	638.4000
	UNDISTRIBUTED	25
	<b>1530-05-72 PROJECT TOTALS</b>	<b>25</b>

**MISCELLANEOUS QUANTITIES**

PROJECT NO: 1530-05-72	COUNTY: PIERCE	SHEET 66
------------------------	----------------	----------

FILE NAME: ORIGINATOR: KL ENGINEERING, INC. REV. DATE: PRINT DATE: April 23, 2021



Proposal Schedule of Items

Proposal ID: 20210511038 Project(s): 1530-05-72

Federal ID(s): WISC 2021362

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	111.000 STA	_____.	_____.
0004	201.0205 Grubbing	111.000 STA	_____.	_____.
0006	203.0100 Removing Small Pipe Culverts	3.000 EACH	_____.	_____.
0008	203.0200 Removing Old Structure (station) 01. 315+44	LS	LUMP SUM	_____.
0010	204.0100 Removing Concrete Pavement	304.000 SY	_____.	_____.
0012	204.0120 Removing Asphaltic Surface Milling	253,860.000 SY	_____.	_____.
0014	204.0150 Removing Curb & Gutter	782.000 LF	_____.	_____.
0016	204.0165 Removing Guardrail	22,508.000 LF	_____.	_____.
0018	205.0100 Excavation Common	7,430.000 CY	_____.	_____.
0020	208.0100 Borrow	18,202.000 CY	_____.	_____.
0022	213.0100 Finishing Roadway (project) 01. 1530- 05-72	1.000 EACH	_____.	_____.
0024	305.0110 Base Aggregate Dense 3/4-Inch	1,640.000 TON	_____.	_____.
0026	305.0120 Base Aggregate Dense 1 1/4-Inch	18,770.000 TON	_____.	_____.
0028	305.0500 Shaping Shoulders	795.000 STA	_____.	_____.
0030	416.1010 Concrete Surface Drains	2.000 CY	_____.	_____.
0032	450.4000 HMA Cold Weather Paving	23,200.000 TON	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210511038 Project(s): 1530-05-72

Federal ID(s): WISC 2021362

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	455.0605 Tack Coat	36,570.000 GAL	_____.	_____.
0036	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	1.000 EACH	_____.	_____.
0038	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	1.000 EACH	_____.	_____.
0040	460.2000 Incentive Density HMA Pavement	80.000 DOL	1.00000	80.00
0042	460.2005 Incentive Density PWL HMA Pavement	18,400.000 DOL	1.00000	18,400.00
0044	460.2007 Incentive Density HMA Pavement Longitudinal Joints	81,290.000 DOL	1.00000	81,290.00
0046	460.2010 Incentive Air Voids HMA Pavement	44,800.000 DOL	1.00000	44,800.00
0048	460.6644 HMA Pavement 4 MT 58-34 V	44,915.000 TON	_____.	_____.
0050	465.0105 Asphaltic Surface	4,760.000 TON	_____.	_____.
0052	465.0110 Asphaltic Surface Patching	50.000 TON	_____.	_____.
0054	465.0120 Asphaltic Surface Driveways and Field Entrances	185.000 TON	_____.	_____.
0056	465.0310 Asphaltic Curb	15,560.000 LF	_____.	_____.
0058	465.0315 Asphaltic Flumes	375.000 SY	_____.	_____.
0060	465.0425 Asphaltic Shoulder Rumble Strips 2-Lane Rural	80,402.000 LF	_____.	_____.
0062	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	47,020.000 LF	_____.	_____.



## Proposal Schedule of Items

Proposal ID: 20210511038 Project(s): 1530-05-72

Federal ID(s): WISC 2021362

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	511.1100 Temporary Shoring	1,976.000 SF	_____.	_____.
0066	520.8000 Concrete Collars for Pipe	6.000 EACH	_____.	_____.
0068	520.8700 Cleaning Culvert Pipes	10.000 EACH	_____.	_____.
0070	521.1024 Apron Endwalls for Culvert Pipe Steel 24-Inch	2.000 EACH	_____.	_____.
0072	521.1030 Apron Endwalls for Culvert Pipe Steel 30-Inch	4.000 EACH	_____.	_____.
0074	521.1036 Apron Endwalls for Culvert Pipe Steel 36-Inch	2.000 EACH	_____.	_____.
0076	521.3136 Culvert Pipe Corrugated Steel 36-Inch	17.000 LF	_____.	_____.
0078	522.0142 Culvert Pipe Reinforced Concrete Class III 42-Inch	156.000 LF	_____.	_____.
0080	522.0148 Culvert Pipe Reinforced Concrete Class III 48-Inch	90.000 LF	_____.	_____.
0082	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	56.000 LF	_____.	_____.
0084	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	2.000 EACH	_____.	_____.
0086	522.1042 Apron Endwalls for Culvert Pipe Reinforced Concrete 42-Inch	4.000 EACH	_____.	_____.
0088	522.1048 Apron Endwalls for Culvert Pipe Reinforced Concrete 48-Inch	2.000 EACH	_____.	_____.
0090	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	900.000 LF	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20210511038 Project(s): 1530-05-72

Federal ID(s): WISC 2021362

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0092	601.0588 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBT	40.000 LF	_____.	_____.
0094	603.8000 Concrete Barrier Temporary Precast Delivered	1,400.000 LF	_____.	_____.
0096	603.8125 Concrete Barrier Temporary Precast Installed	2,800.000 LF	_____.	_____.
0098	603.8500 Anchoring Concrete Barrier Temporary Precast	300.000 LF	_____.	_____.
0100	606.0200 Riprap Medium	46.000 CY	_____.	_____.
0102	611.8110 Adjusting Manhole Covers	1.000 EACH	_____.	_____.
0104	611.8120.S Cover Plates Temporary	1.000 EACH	_____.	_____.
0106	611.9800.S Pipe Grates 01. 42-Inch	4.000 EACH	_____.	_____.
0108	611.9800.S Pipe Grates 02. 48-Inch	2.000 EACH	_____.	_____.
0112	614.2300 MGS Guardrail 3	10,378.100 LF	_____.	_____.
0114	614.2330 MGS Guardrail 3 K	13,137.500 LF	_____.	_____.
0116	614.2350 MGS Guardrail Short Radius	487.500 LF	_____.	_____.
0118	614.2500 MGS Thrie Beam Transition	240.000 LF	_____.	_____.
0120	614.2610 MGS Guardrail Terminal EAT	41.000 EACH	_____.	_____.
0122	614.2630 MGS Guardrail Short Radius Terminal	5.000 EACH	_____.	_____.



## Proposal Schedule of Items

Proposal ID: 20210511038 Project(s): 1530-05-72

Federal ID(s): WISC 2021362

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0124	618.0100 Maintenance And Repair of Haul Roads (project) 01. 1530-05-72	1.000 EACH	_____.	_____.
0126	619.1000 Mobilization	1.000 EACH	_____.	_____.
0128	624.0100 Water	670.000 MGAL	_____.	_____.
0130	625.0500 Salvaged Topsoil	62,700.000 SY	_____.	_____.
0132	627.0200 Mulching	2,500.000 SY	_____.	_____.
0134	628.1504 Silt Fence	21,550.000 LF	_____.	_____.
0136	628.1520 Silt Fence Maintenance	64,450.000 LF	_____.	_____.
0138	628.1905 Mobilizations Erosion Control	8.000 EACH	_____.	_____.
0140	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH	_____.	_____.
0142	628.2004 Erosion Mat Class I Type B	35,180.000 SY	_____.	_____.
0144	628.2008 Erosion Mat Urban Class I Type B	2,300.000 SY	_____.	_____.
0146	628.2039 Erosion Mat Class III Type D	25,920.000 SY	_____.	_____.
0148	628.6505 Soil Stabilizer Type A	7.500 ACRE	_____.	_____.
0150	628.7010 Inlet Protection Type B	1.000 EACH	_____.	_____.
0152	628.7504 Temporary Ditch Checks	2,250.000 LF	_____.	_____.
0154	628.7555 Culvert Pipe Checks	370.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210511038 Project(s): 1530-05-72

Federal ID(s): WISC 2021362

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0156	628.7560 Tracking Pads	45.000 EACH	_____.	_____.
0158	629.0205 Fertilizer Type A	48.000 CWT	_____.	_____.
0160	630.0120 Seeding Mixture No. 20	1,700.000 LB	_____.	_____.
0162	630.0130 Seeding Mixture No. 30	300.000 LB	_____.	_____.
0164	630.0500 Seed Water	1,650.000 MGAL	_____.	_____.
0166	633.5200 Markers Culvert End	16.000 EACH	_____.	_____.
0168	638.2102 Moving Signs Type II	25.000 EACH	_____.	_____.
0170	638.4000 Moving Small Sign Supports	25.000 EACH	_____.	_____.
0172	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0174	643.0300 Traffic Control Drums	77,100.000 DAY	_____.	_____.
0176	643.0420 Traffic Control Barricades Type III	135.000 DAY	_____.	_____.
0178	643.0705 Traffic Control Warning Lights Type A	270.000 DAY	_____.	_____.
0180	643.0900 Traffic Control Signs	9,480.000 DAY	_____.	_____.
0182	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0184	645.0120 Geotextile Type HR	130.000 SY	_____.	_____.
0186	646.1020 Marking Line Epoxy 4-Inch	88,750.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210511038 Project(s): 1530-05-72

Federal ID(s): WISC 2021362

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0188	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	117,900.000 LF	_____.	_____.
0190	646.3040 Marking Line Grooved Wet Ref Epoxy 8-Inch	510.000 LF	_____.	_____.
0192	646.5220 Marking Symbol Epoxy	2.000 EACH	_____.	_____.
0194	646.6120 Marking Stop Line Epoxy 18-Inch	320.000 LF	_____.	_____.
0196	646.6464 Cold Weather Marking Epoxy 4-Inch	206,650.000 LF	_____.	_____.
0198	646.6468 Cold Weather Marking Epoxy 8-Inch	510.000 LF	_____.	_____.
0200	646.7020 Marking Diagonal Epoxy 6-Inch	85.000 LF	_____.	_____.
0202	646.8120 Marking Curb Epoxy	65.000 LF	_____.	_____.
0204	646.8220 Marking Island Nose Epoxy	1.000 EACH	_____.	_____.
0206	646.8320 Marking Parking Stall Epoxy	425.000 LF	_____.	_____.
0208	646.9000 Marking Removal Line 4-Inch	7,800.000 LF	_____.	_____.
0210	648.0100 Locating No-Passing Zones	10.760 MI	_____.	_____.
0212	649.0105 Temporary Marking Line Paint 4-Inch	44,400.000 LF	_____.	_____.
0214	649.0150 Temporary Marking Line Removable Tape 4-Inch	18,550.000 LF	_____.	_____.
0216	649.0850 Temporary Marking Stop Line Removable Tape 18-Inch	200.000 LF	_____.	_____.
0218	650.4500 Construction Staking Subgrade	25,441.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210511038 Project(s): 1530-05-72

Federal ID(s): WISC 2021362

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0220	650.5000 Construction Staking Base	25,441.000 LF	_____.	_____.
0222	650.5500 Construction Staking Curb Gutter and Curb & Gutter	940.000 LF	_____.	_____.
0224	650.6000 Construction Staking Pipe Culverts	9.000 EACH	_____.	_____.
0226	650.8000 Construction Staking Resurfacing Reference	56,740.000 LF	_____.	_____.
0228	650.9910 Construction Staking Supplemental Control (project) 01. 1530-05-72	LS	LUMP SUM	_____.
0230	650.9920 Construction Staking Slope Stakes	25,441.000 LF	_____.	_____.
0232	690.0150 Sawing Asphalt	1,335.000 LF	_____.	_____.
0234	690.0250 Sawing Concrete	300.000 LF	_____.	_____.
0236	740.0440 Incentive IRI Ride	52,731.000 DOL	1.00000	52,731.00
0238	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,500.000 HRS	5.00000	12,500.00
0240	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,440.000 HRS	5.00000	7,200.00
0242	SPV.0090 Special 01. Cleaning Ditch	800.000 LF	_____.	_____.
0244	SPV.0105 Special 01. Milling and Removing Temporary Joint	LS	LUMP SUM	_____.
0246	SPV.0105 Special 02. Material Transfer Vehicle	LS	LUMP SUM	_____.
0248	SPV.0105 Special 03. Box Culvert Joint Repair C-47-1869	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20210511038 Project(s): 1530-05-72

Federal ID(s): WISC 2021362

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0250	SPV.0105 Special 04. Prepare Foundation for Asphaltic Paving Special	LS	LUMP SUM	_____.
0252	614.0397 Guardrail Mow Strip Emulsified Asphalt	4,070.000 SY	_____.	_____.
0254	625.0100 Topsoil	3,150.000 SY	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.