



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

January 6, 2022

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #40: 1560-00-76, WISC 2022136
Drummond – USH 2
CTH E East to USH 2
USH 63
Bayfield County

Letting of January 11, 2022

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
649.0105	Temporary Marking Line Paint 4-Inch	LF	20,545	20,545	41,090

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
27	Miscellaneous Quantities (Updated the pavement marking table)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1560-00-76

January 6, 2022

Special Provisions

3. Prosecution and Progress

Replace the fifth paragraph with the following:

Do not allow exposed milled surfaces to remain open to traffic for more than 96 hours.

Schedule of Items

Attached, dated January 6, 2022, are the revised Schedule of Items Page 4.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 27.

END OF ADDENDUM

Addendum No. 01
ID 1560-00-76
Revised Sheet 27
January 6, 2022

3

3

STATION	TO	STATION	LOCATION	646.1020	646.1040	646.3040	649.0105	649.0120	REMARKS
				MARKING LINE EPOXY 4-INCH	MARKING LINE REF EPOXY 4-INCH	MARKING LINE GROOVED WET REF EPOXY 8-INCH	MARKING LINE PAINT 4-INCH	MARKING LINE EPOXY 4-INCH	
				LF	LF	LF	LF	LF	
1172+40	-	1498+96	EDGE LINES	64,157	--	--	--	--	
1172+40	-	1498+96	CENTERLINE	21,770	--	--	--	--	
1172+40	-	1498+96	CENTERLINE	--	--	--	32,898	--	FOR PLACEMENT AFTER MILLING RUMBLE STRIPS FOR PLACEMENT ON MILLED SURFACE AND LOWER LIFT OF HMA FOR PLACEMENT PRIOR TO MILLING RUMBLE STRIPS
1494+74	-	1496+53	CENTERLINE	--	--	180	--	--	
1497+94	-	8+00	TURN LANE	--	--	183	--	--	
7+18	-	130+50	EDGE LINES	24,298	--	--	--	--	
7+18	-	130+50	CENTERLINE	--	--	--	--	--	
7+18	-	130+50	CENTERLINE	--	--	--	6,792	--	FOR PLACEMENT AFTER MILLING RUMBLE STRIPS FOR PLACEMENT ON MILLED SURFACE AND LOWER LIFT OF HMA FOR PLACEMENT PRIOR TO MILLING RUMBLE STRIPS
139+00	-	142+50	EDGE LINES	700	--	--	--	--	
139+00	-	142+50	CENTERLINE	700	--	--	--	--	
139+00	-	142+50	CENTERLINE	--	--	--	1,400	--	FOR PLACEMENT AFTER MILLING RUMBLE STRIPS FOR PLACEMENT ON MILLED SURFACE AND LOWER LIFT OF HMA FOR PLACEMENT PRIOR TO MILLING RUMBLE STRIPS
TOTAL 0010				27,962	89,155	363	41,090	27,962	

STATION	TO	STATION	LOCATION	690.0150	SPV 0180.01
				SAWING ASPHALT	ASPHALTIC BASE PATCH PARTIAL DEPTH
				LF	SY
1230+05	-	1230+92	RT	95	
1233+90	-	1234+88	LT	91	
42+75	-	43+25	MAINLINE DRIVEWAYS	68	
				157	
TOTAL 0010				411	

STATION	TO	STATION	LOCATION	650.8000	650.9910	650.9920
				CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) (1560-00-76)	CONSTRUCTION STAKING	CONSTRUCTION STAKING
				LF	LF	LF
PROJECT				45,338	--	--
1230+25	-	1231+88	PROJECT	--	163	
1232+95	-	1234+75		--	180	
1411+61	-	1416+25		--	464	
TOTAL 0010				45,338	807	

STATION	TO	STATION	LOCATION	SPV 0060.02
				CLEANING STORM SEWER
				EACH
1231+88	-	1231+88	LT	1
1231+88	-	1231+88	RT	1
TOTAL 0010				2

STATION	TO	STATION	LOCATION	SPV 0180.01
				ASPHALTIC BASE PATCH PARTIAL DEPTH
				SY
PROJECT				189
45+25	-	45+75	PROJECT	189
TOTAL 0010				189



Proposal Schedule of Items

Proposal ID: 20220111040 Project(s): 1560-00-76

Federal ID(s): WISC 2022136

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	638.2102 Moving Signs Type II	7.000 EACH	_____.	_____.
0098	638.3000 Removing Small Sign Supports	7.000 EACH	_____.	_____.
0100	638.4000 Moving Small Sign Supports	3.000 EACH	_____.	_____.
0102	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0104	643.0300 Traffic Control Drums	300.000 DAY	_____.	_____.
0106	643.0900 Traffic Control Signs	2,475.000 DAY	_____.	_____.
0108	643.1000 Traffic Control Signs Fixed Message	36.000 SF	_____.	_____.
0110	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0112	645.0120 Geotextile Type HR	155.000 SY	_____.	_____.
0114	646.1020 Marking Line Epoxy 4-Inch	27,962.000 LF	_____.	_____.
0116	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	89,155.000 LF	_____.	_____.
0118	646.3040 Marking Line Grooved Wet Ref Epoxy 8-Inch	363.000 LF	_____.	_____.
0120	648.0100 Locating No-Passing Zones	8.750 MI	_____.	_____.
0122	649.0105 Temporary Marking Line Paint 4-Inch	41,090.000 LF	_____.	_____.
0124	649.0120 Temporary Marking Line Epoxy 4-Inch	27,962.000 LF	_____.	_____.
0126	650.8000 Construction Staking Resurfacing Reference	45,338.000 LF	_____.	_____.